

ADDENDUM NO. 2

TO: PLANS AND SPECIFICATIONS FOR STATE OF MISSOURI

REPLACE ROOF INCLUDING SKY LIGHT
ADMINISTRATION BLDG. & HOUSING UNIT 5
MISSOURI EASTERN CORRECTIONAL CENTER
PACIFIC, MISSOURI
PROJECT NO. C1916-01

Bid Date: 1:30 PM, Thursday, February 27, 2020 (Not Changed)

Bidders are hereby informed that the Construction Plans and/or Specifications are modified as follows:

SPECIFICATION CHANGES:

1. Section 075423 – Thermoplastic Polyolefin (TPO) Roofing

- a. REMOVE 2.5, D.- Insulation Accessories, Cover Board in its entirety. Cover Board material is to meet the specifications for 2.3 Substrate Boards – basis of design: Georgia Pacific Corporation, Dens Deck Prime Roof Boards or equal.

DRAWING CHANGES:

1. SHEET A100

- a. REVISE “East Administration Building Roof” note to read: PROVIDE NEW SINGLE-PLY TPO ROOFING SYSTEM ON R-30 MIN. TAPERED INSULATION, FULLY ADHERED PER ROOFING MFGR. REQUIREMENTS OVER EXISTING CONCRETE ROOF SLAB. SEE DETAIL 7/A500. FLASH PER ROOF MFGR AT ALL ROOF DRAINS, CURBS, AND ROOF ACCESSORIES/EQUIPMENT LOCATIONS. SEE ME DRAWINGS FOR EXISTING EQUIPMENT SCOPE OF WORK. PROVIDE PARAPET COPING, FLASHING, AND OTHER ROOF ACCESSORIES TO ENSURE WEATHER-TIGHT INSTALLATION.

2. SHEET A101

- a. REVISE “North Administration Building and Housing Unit 5 Roof” note to read: PROVIDE NEW SINGLE-PLY TPO ROOFING SYSTEM ON R-30 MIN. TAPERED INSULATION, FULLY ADHERED PER ROOFING MFGR. REQUIREMENTS OVER EXISTING CONCRETE ROOF SLAB. SEE DETAIL 7/A500. FLASH PER ROOF MFGR AT ALL ROOF DRAINS, CURBS, AND ROOF ACCESSORIES/EQUIPMENT LOCATIONS. SEE ME DRAWINGS FOR EXISTING EQUIPMENT SCOPE OF WORK. PROVIDE PARAPET COPING, FLASHING, AND OTHER ROOF ACCESSORIES TO ENSURE WEATHER-TIGHT INSTALLATION.

3. SHEET A500

- a. REVISE Detail 7/A500 Tapered Rigid Insulation note to read: TAPERED RIGID INSULATION ¼” PER 1’-0” SLOPE R-30 MIN. FULLY ADHERED PER ROOFING MFGR. REQUIREMENTS TO MEET FM I-90 STANDARDS.

4. SHEET A501

- a. REVISE Detail 5/A502 Tapered Rigid Insulation note to read: TAPERED RIGID INSULATION ¼" PER 1'-0" SLOPE R-30 MIN. FULLY ADHERED PER ROOFING MFGR. REQUIREMENTS TO MEET FM I-90 STANDARDS.

5. SHEET A502

- a. REVISE Details 2/A501, 5/A501, and 6/A501 Tapered Rigid Insulation note to read: TAPERED RIGID INSULATION ¼" PER 1'-0" SLOPE R-30 MIN. FULLY ADHERED PER ROOFING MFGR. REQUIREMENTS TO MEET FM I-90 STANDARDS.

ATTACHMENTS:

- a. None

February 21, 2020

END ADDENDUM NO.2