

ADDENDUM NO. 2

TO: PLANS AND SPECIFICATIONS FOR STATE OF MISSOURI

**Improvements to Storm Water and Wastewater Collection Systems
Missouri State Fairgrounds
Sedalia, Missouri
PROJECT NO. F2302-01**

Bid Opening Date: 1:30 PM, THURSDAY, OCTOBER 31, 2024, (CHANGED)

Bidders are hereby informed that the construction Plans and/or Specifications are modified as follows:

SPECIFICATION CHANGES:

1. None

DRAWING CHANGES:

1. Sheet C101 – ADD Notes as follows:
 - a. Owner to provide staking as described in Job Special Conditions 6. All additional staking to be provided by Contractor.
 - b. Trenchless methods of pipe replacement are acceptable including pipe bursting. Contractor shall provide a plan of work and specification during submittal reviews.
 - c. Owner to provide onsite stockpile location during the pre-construction meeting.
2. Sheet C201 – ADD Note as follows:
 - a. Contractors shall provide necessary elbows and splashpads for downspout discharges that are disconnected from the sanitary sewer.
 - b. Owner to provide onsite stockpile location during the pre-construction meeting.
 - c. Contractor may propose alternate alignments for evaluation during the shop drawing/submittal phase. It is the intent of the owner to give the contractor the flexibility for alignment adjustments during construction for sewer or service lines in order minimize impacts to the fairgrounds and existing structures. The contractor shall verify all critical elevations prior to executing any adjustments.
 - d. Full lengths of laterals are unknown. Quantities provided on the plan sheet are for general purposes.
 - e. Manhole elevations are to be verified by contractor prior to proceeding with construction.
3. Sheet C209 – Add note as follows:
 - a. Replacement of laterals terminates at edge of building.
4. Sheet C210 – Add to Note 3 as follows:
 - a. Lines internal to the Horse barns shall be replaced and any necessary concrete or other surface disturbed is to be patched to match existing.
5. Sheet C217 – Add to Note 1 as follows:
 - a. The contractor shall tie into the line immediately outside the restrooms. No work is required inside the restrooms.
6. Sheet C232 – Add Sewer Pipe Note 7 as follows:
 - a. All cleanouts at buildings to be two way cleanouts. Cleanouts in drives or vehicle pathways will require concrete pad, those in grass areas do not require concrete pad.

GENERAL COMMENTS:

1. **The Pre-Bid Meeting was held October 15th, 2024 followed by a walk-through of the site. The Pre-Bid Meeting sign-in sheet is attached to addendum No. 1.**

2. Bidders needing additional site inspection should contact Justin Anderson at 660-317-8740 or Jason Moore at 660-281-6333 to schedule a time.
3. Please contact April Howser, Contract Specialist, at 573-751-0053 or april.howser@oa.mo.gov, for questions about bidding procedures and MBE\WBE\SDVE goals and submittal requirements.
4. The deadline for technical questions was noon on October 21st, 2024.
5. Changes to, or clarification of, the bid documents are only made as issued in the addenda.
6. All correspondence with respect to this project must include the State of Missouri project number as indicated above.
7. Current Planholders list available online at:
<https://www.oafmdcplanroom.com/projects/2632/plan-holders/f2302-01-improvements-to-storm-water-wastewater-collection-systems-missouri-state-fairgrounds>
8. Prospective Bidders contact American Document Solutions, 1400 Forum Blvd Suite 1C, Columbia MO 65201, 573-446-7768 to order official plans and specifications.

ATTACHMENTS:

1. None

October 23, 2024

END OF ADDENDUM NO. 2