

ADDENDUM NO. 1

TO: PLANS AND SPECIFICATIONS FOR STATE OF MISSOURI

**Replace Generator & Automatic Transfer Switch
Higginsville Habilitation Center
Higginsville, Missouri
PROJECT NO.: M2317-01**

Bid Opening Date: 1:30 PM, November 2, 2023 (Not Changed)

Bidders are hereby informed that the construction Plans and/or Specifications are modified as follows:

SPECIFICATION CHANGES:

1. SECTION 262816 - ENCLOSED SWITCHES AND CIRCUIT BREAKERS

2.1 FUSIBLE SWITCHES

CHANGE

- A. Type GD, General Duty, Single Throw, 240V ac, 800 amp and Smaller:

2.2 NONFUSIBLE SWITCHES

CHANGE

- B. Type GD, General Duty, Single Throw, 600 A and Smaller:

2. SECTION 263213.13 – DIESEL EMERGENCY ENGINE GENERATORS.

ADD:

3.6 DIESEL FUEL FOR STARTUP AND COMMISSIONING

- A. Contractor is to provide all diesel fuel required for Startup, Commissioning, testing, and training. After the contractor has performed all required tasks, contractor will provide a full tank with fuel.

DRAWINGS CHANGES:

1. SHEET E-601 – One Line Diagram

Equipment List Revisions

REV 1 10/12/2023

EQUIPMENT LIST - BASIS OF DESIGN			
#	ID	QTY	DESCRIPTION
	1	1	NEW GENERATOR - 125KW 208V/3 PHASE 400 AMPS WITH DIESEL FUEL TANK 1055 GAL BASE MOUNTED. CUMMINS C125D6D OR APPROVED EQUAL. SEE SPECIFICATIONS
	2	1	NEW AUTOMATIC TRANSFER SWITCH 208V/3PH RATED AT 400 AMPS. MODEL OTEC400 OR APPROVED EQUAL. NEMA 3R FOR OUTDOOR INSTALLATION
	3	1	EXISTING GROUND ROD, SYSTEM, VERIFY.
	4	1	EXISTING TRANSFORMER, XXXV-208V, 3 PHASE.
	5	2	ALTERNATE 1. NEW DISCONNECT 208V/3PH 400 AMP WITH FUSEABLE LINK
	6	4	ALTERNATE 1. NEW DISCONNECT 208V/3PH 200 AMP WITH FUSEABLE LINK
	7	1	NEW ATS TO GENERATOR CONTROL SIGNAL CONDUCTOR AND CONDUIT.

GENERAL COMMENTS:

1. The Pre-Bid Meeting was held October 11, 2023 followed by an inspection of the project site.
2. Bidders desiring to perform a site inspection should contact staff Eddie Renno at 660-584-4870 eddie.renno@oa.mo.gov to schedule a time to enter the facility.
3. Please contact Paul Girouard 573-751-4797 paul.girouard@oa.mo.gov for questions about bidding procedures, MBE\WBE\SDVE Goals, and other submittal requirements.
4. The deadline for technical questions is October 26th, 2023 at noon (12 pm).
5. Changes to, or clarification of, the bid documents are only made as issued in the addenda.
6. All correspondence with respect to this project must include the State of Missouri project number as indicated above.
7. **All bids shall be submitted on the bid form without additional terms and conditions, modifications, or stipulations. Each space on the bid form shall be properly filled. Failure to do so will result in rejection of the bid.**
8. **MBE/WBE/SDVE participation requirements can be found in DIVISION 00. The MBE/WBE/SDVE participation goals are 10%/10%/3%, respectively. Only certified firms as of the bid opening date can be used to satisfy the MBE/WBE/SDVE participation goals for this project. If a bidder is unable to meet a participation goal, a Good Faith Effort Determination Form must be completed. Failure to complete this process will result in rejection of the bid.**

ATTACHMENTS:

1. Pre-Bid Meeting Sign-In Sheet

October 12, 2023

END ADDENDUM NO. 1

Pre-Bid Meeting Attendance Sheet
Replace Generator & Automatic Transfer Switch, Group Home 1
Higginsville Habilitation Center
Project No. M2317-01
10/11/2023 10:00 AM

Name & Title	Company Name Type of Contracting	MBE/WBE/ SDVE Status	Phone	E-Mail Address
Shannon Thompson Project Manager	OA/FMDC		573-526-3166	Shannon.thompson@oa.mo.gov
Ricky Howard Construction Administrator	OA/FMDC		816-728-0385	ricky.howard@oa.mo.gov
Robert Schmitt Designer	Crossed Swords Engineering		816-309-0099	Robert7721@aol.com
Chris Roberts Estimator/PM	Meyer Electric		573-469-5556	chris@meyerelectric.net
Trent Elliott Estimator/PM	T.S. Companies Tri-County Electric	WBE	573-603-9817	telliott@tri-county-electrical.com
Eddie Rame	OAFMDC		816-565-5373	eddie.rame@oa.mo.gov

Pre-Bid Meeting Attendance Sheet
Replace Generator & Automatic Transfer Switch, Group Home 1
Higginsville Habilitation Center

Project No. M2317-01
 10/11/2023 10:00 AM

Name & Title	Company Name Type of Contracting	MBE/WBE/ SDVE Status	Phone	E-Mail Address
Nathan Marnin Project Manager/Estimator	Reinhold Electric INC. Electrical		314-604-2590	nmarnin@reinholdelectric.com
George Heath Project Manager	American Legacy Construction Electrical		816-352-5939	G.heath@ALC-KC.COM
Lance Persell PM/Est.	VAZQUEZ	MBE	816-204-7083	lancep@VAZQUEZCC.COM
Ben Rogers PM	AMERICAN LEGACY CONSTRUCTION		816-806-1441	ROGERS@ALC-KC.COM
Tylo Strickland Est/pm	SM 5 Electric		660 631- 0889	Tstrickland@smselectric.com
Jeff Gash Owner	Gash Plumbers, LLC		660-641-0609	Jbgash@gmail.com

Pre-Bid Meeting Attendance Sheet
Replace Generator & Automatic Transfer Switch, Group Home 1
Higginsville Habilitation Center
Project No. M2317-01
10/11/2023 10:00 AM

Name & Title	Company Name Type of Contracting	MBE/WBE/ SDVE Status	Phone	E-Mail Address
Tim Collins OA-FMDC (SLM)	OA-FMDC		573-616-5433	Timmy.Collins@oa.no.gov
Justin Semson	G+S Electrical Contractors		660 815-4043	gseci@att.net
Ryan Williams MAX ELECTRIC IPM	MAX ELECTRIC	WBE	573-480-7513	Ryan@maxelectric-ks.com
MIKE FISHER	OA-FMDC		816-512-0109	michael.fisher@oa.mojov