

ADDENDUM NO. 2

TO: PLANS AND SPECIFICATIONS FOR STATE OF MISSOURI

**Repave Parking Area Storage Building (Lower Shop)
Missouri State Highway Patrol General Headquarters
Jefferson City, Missouri
PROJECT NO. R2505-01**

Bid Date is: 1:30 PM, Thursday, August 27, 2026 (NOT CHANGED)

Bidders are hereby informed that the Construction Plans and/or Specifications are modified as follows:

BID FORM CHANGES:

1. None

SPECIFICATION CHANGES:

1. Section 033000 – Cast-In-Place Concrete
 - a. ADD 2.0.F as follows:
 - F. Concrete Mixtures for Building Elements:
 1. Minimum Compressive Strength: 4,000 psi
 2. Maximum W/C Ratio: 0.50
 3. Slump Limit: 4 inches plus or minus 1"
 4. Air Content: 5.5 percent, plus or minus 1.5 percent

DRAWING CHANGES:

1. Sheet C-100 – See Attached revised sheet C-100
 - a. ADD General Note Number 10 as follows:
 10. PLACE CONTROL JOINTS IN NEW PAVEMENT TO CREATE APPROXIMATELY 10'X10' SQUARES. PLACE EXPANSION JOINTS IN NEW PAVEMENT AT MAXIMUM SPACING OF 50 FEET.
 - b. ADD General Note Number 11 as follows:
 11. PROVIDE TEMPORARY EROSION MEASURES AS NEEDED IN ACCORDANCE WITH APPLICABLE REQUIREMENTS.
 - c. ADD General Note Number 12 as follows:
 12. REMOVAL OF ELECTRICAL FROM SALT SHED WILL BE HANDLED BY OWNER PRIOR TO CONTRACTOR'S WORK.

- d. REVISE Keyed Note 3 as follows:

PROTECT EXISTING BUILDING FROM DAMAGE DURING PAVING OPERATIONS. SLOPE PAVEMENT 1/2" PER FOOT AWAY FROM A MINIMUM 15' OUT. INSTALL 1/2" FIBERBOARD EXPANSION JOINT AND JOINT SEALANT WHERE NEW PAVEMENT MEETS THE EXISTING BUILDING.

- e. REMOVE and REPLACE Keyed Note 8 as follows:

ALTERNATE #1: REGRADE GRAVEL DRIVE AND SPREAD 2" OF 1" MINUS CRUSHED ROCK.

- f. REMOVE and REPLACE Keyed Note 11 as follows:

REMOVE AND DISPOSE OF VEGETATION/TOPSOIL. INSTALL 6" OF 1" MINUS CRUSHED ROCK.

2. Sheet A-500 – See Attached revised sheet A-500

- a. REVISE Detail 2 to remove reinforced concrete on back side of salt shed. Install top soil to existing grade, seed and straw.
- b. REVISE Detail 4 to change the orientation of metal siding ribs from horizontal to vertical.
- c. ADD General Note Number 1 as follows:

1. FASTEN SALT SHED RAFTERS TO WALL/BEAM WITH HURRICANE CLIPS.

GENERAL COMMENTS:

1. The Pre-Bid Meeting was held August 13, 2026, followed by a walk-through of the site.
2. Bidders needing additional site inspection prior to noon on August 26, 2026 should contact L. Scott Samuels, PE, at scott.samuels@oa.mo.gov to schedule a date and time.
3. Please contact April Howser, Contract Specialist, at 573-690-9874 or april.howser@oa.mo.gov, for questions about bidding procedures and MBE\WBE\SDVE goals and submittal requirements.
4. Changes to the bid documents are only made as issued in the addenda.
5. All correspondence with respect to this project must include the State of Missouri project number as indicated above.
6. Current Planholders list available online at: [R2505-01 Repave Parking Area Storage Building \(Lower Shop\)-MSHP General Headquarters-Jefferson City :: State of Missouri Office of Administration](#) Prospective Bidders contact American Document Solutions, 1400 Forum Blvd Suite 1C, Columbia MO 65201, 573-446-7768 to order official plans and specifications.
7. **All bids shall be submitted on the bid form without additional terms and conditions, modifications, or stipulations. Each space on the bid form shall be properly filled**

including a bid amount for the alternates. Failure to do so will result in rejection of the bid.

8. MBE/WBE/SDVE participation requirements can be found in DIVISION 00. The MBE/WBE/SDVE participation goals are 0%/0%/3%, respectively. Only certified firms as of the bid opening date can be used to satisfy the MBE/WBE/SDVE participation goals for this project. If a bidder is unable to meet a participation goal, a Good Faith Effort Determination Form must be completed. Failure to complete this process will result in rejection of the bid.

ATTACHMENTS:

1. None

August 20, 2026

END ADDENDUM NO. 2