

**ADDENDUM NO. 02**

**TO: PLANS AND SPECIFICATIONS FOR STATE OF MISSOURI**

Building Envelope Repairs, Troop D Crime Lab  
Troop D Crime Lab  
Springfield, Missouri  
PROJECT NO.: R2516-01

Bid Opening Date: 1:30 PM, Tuesday, April 7, 2026 (Unchanged)

---

**Bidders are hereby informed that the construction Plans and/or Specifications are modified as follows:**

**SPECIFICATION CHANGES:**

1. Section 075420 – Thermoplastic Polyolefin (TPO) Roofing

ADD 2.1.A.1.e as follows:

- e. Duro-Last

**DRAWINGS CHANGES:**

1. Sheet A-1

- a. ADD general Note A as follows:

Contractor to install temporary plastic sheeting as dust protection, at locations where dust to be expected to be generated by work inside the building, as required to protect equipment and areas outside the area of work from dust during construction. Coordinate installation of this temporary protection with the local facility. Any sanding required by work to gypsum board is to be wet sanding, to further reduce the amount of dust generated.

2. Sheet A-3

- a. REPLACE roof plan note #1 as follows:

REMOVE AND DISCARD EXISTING ROOFING DOWN TO EXISTING CONCRETE DECK. PROVIDE AND INSTALL FULLY ADHERED TPO ROOFING OVER 1/2" COVER BOARD OVER (2) LAYERS OF 3" THICK POLYISOCYANURATE INSULATION (EXISTING ROOF DECK SLOPES AS INDICATED) OVER CONCRETE DECK. SET EACH LAYER OF INSULATION (INCLUDING COVER BOARD) IN INSULATION ADHESIVE. SEE SPECIFICATION.

- b. ADD general note F as follows:

At both high and low areas of existing roof, the existing roof system is as follows: Gravel surface built-up asphalt roofing (Asbestos was NOT detected

by an asbestos test performed by Gerken Environmental Enterprises) over 1/2" wood fiber cover board over polyisocyanurate insulation over existing concrete deck (overall thickness of existing roof system is approximately 4" above existing deck).

c. ADD general note G as follows:

Contractor to install temporary dust protection as required during construction to protect intakes for rooftop HVAC equipment, without impacting operation of this equipment. Coordinate installation of this temporary protection with the local facility.

**GENERAL COMMENTS:**

1. NONE

**ATTACHMENTS:**

1. NONE

**END ADDENDUM 02**