

## ADDENDUM NO. 1

TO: PLANS AND SPECIFICATIONS FOR STATE OF MISSOURI

Company Headquarters & Administration Building  
Camp Crowder Training Site  
Neosho, Missouri  
PROJECT NO.: T1833-01

**Bid Opening Date: 1:30 PM, September 5, 2019 (Not Changed)**

**Bidders are hereby informed that the construction Plans and/or Specifications are modified as follows:**

### **SPECIFICATION CHANGES:**

#### 1. Section 133419 – METAL BUILDING SYSTEMS

a. REPLACE Part 2 – Products, 2.2 System Description, Item I.1 as follows:

1. Liner Panels (located at the interior side of the exterior walls and columns):
  - a. Fasteners: Concealed.
  - b. Profile: Flush.
  - c. Texture: Smooth.
  - d. Thickness: 24-gauge.
  - e. Color: Match adjacent gypsum walls.
  - f. Finish Performance Requirements: Match exterior metal wall panels.

b. REPLACE Part 2 – Products, 2.3 Performance Requirements, Item M. as follows:

“Thermal Performance for Opaque Elements: Provide the following maximum assembly U-factors for insulation when tested according to ASTM C1363 or ASTM C518:”

c. DELETE Part 2 – Products, 2.3 Performance Requirements, Item M.1.b. “R-Value: R-40.”

d. DELETE Part 2 – Products, 2.3 Performance Requirements, Item M.2.b. “R-Value: R-26.”

e. ADD Part 2 – Products, 2.4 Structural-Steel Framing, Item F.2.b., as follows:

b. If structural members are larger than those anticipated in the Contract Drawings, Contractor shall notify Architect immediately and the Contractor shall coordinate the work and adjust all dimensions with actual size of structural members at no additional cost to the Owner.

f. ADD Part 2 – Products, 2.6 Metal Wall Panels, Item A.5.a. as follows:

a. Field verify the nearest existing building on site to determine the profile of the exterior walls, roof, trim and soffit panels.

#### 2. SECTION 230550 – TESTING AND ADJUSTING

a. ADD to Paragraph 1.02 Acceptable Testing and Balancing Firms

- i. C&C Group  
2005 West Woodland St

3. SECTION 260939 – LIGHTING CONTROL DEVICES

- a. ADD to paragraph 1.03 Approved Manufacturer's; Hubbell

4. SECTION 265113 – INTERIOR LIGHTING

- a. ADD to paragraph 2.03 Approved Manufacturer's; Dualite, Columbia Lighting, Elumigen

5. Section 265613 – EXTERIOR LIGHTING

- b. ADD to paragraph 2.03 Approved Manufacturer's; Hubbell

**DRAWING CHANGES:**

1. Sheet A-311

- a. WALL SECTION 1: REVISE Pre-engineered Building Faced Insulation (Minimum R-26) to (Minimum Assembly U-Value 0.052).
- b. WALL SECTION 2: REVISE Pre-engineered Building Faced Insulation (Minimum R-26) to (Minimum Assembly U-Value 0.052).
- c. GABLE END DETAIL 3: REVISE Note to read: "Provide combined insulation assembly value at roof no less than U-0.0350"
- d. EAVE OVERHANG DETAIL 4: REVISE Note to read: "Provide combined insulation assembly value at roof no less than U-0.0350"
- e. BASE OF WALL ATTACHMENT DETAIL 5: REVISE Pre-engineered Building Faced Insulation (Minimum R-26) to (Minimum Assembly U-Value 0.052).
- f. GARAGE DOOR HEAD & SILL DETAIL 7: REVISE Pre-engineered Building Faced Insulation (Minimum R-26) to (Minimum Assembly U-Value 0.052).

2. Sheet A-611

- a. WINDOW HEAD & SILL DETAIL 2: REVISE Pre-engineered Building Faced Insulation (Minimum R-26) to (Minimum Assembly U-Value 0.052). 2 locations.
- b. EXTERIOR ALUMINUM DOOR HEAD DETAIL 3: REVISE Pre-engineered Building Faced Insulation (Minimum R-26) to (Minimum Assembly U-Value 0.052).
- c. EXTERIOR HOLLOW METAL DOOR DETAIL 4: REVISE Pre-engineered Building Faced Insulation (Minimum R-26) to (Minimum Assembly U-Value 0.052).
- d. HOLLOW METAL DOOR JAMB DETAIL 8: REVISE Faced Insulation (Minimum R-26) to (Minimum Assembly U-Value 0.052).

**GENERAL COMMENTS:**

- 1. The Pre-Bid Meeting was held August 22, 2019, followed by a walk-through of the facility. The Pre-Bid Meeting sign-in sheet is attached.


2. Bidders needing additional site inspection should contact Jeremy Newton at 1-573-308-6894 to schedule a time.
3. Please contact Marlene Blackburn, Contract Specialist, at 573-522-6035 or [Marlene.Blackburn@oa.mo.gov](mailto:Marlene.Blackburn@oa.mo.gov) for questions about bidding procedures and MBE\WBE\SDVE goals and submittal requirements.
4. The deadline for technical questions was August 28, 2019 at noon.
5. Changes to, or clarification of, the bid documents are only made as issued in the addenda.
6. All correspondence with respect to this project must include the State of Missouri project number as indicated above.
7. Current Planholders list available online at: <https://www.adsplanroom.net/jobs/123/details/t1833-01-company-headquarters-administration-building-camp-crowder-training-site>
8. Prospective Bidders contact American Document Solutions, 1400 Forum Blvd Suite 1C, Columbia MO 65201, 573-446-7768 to order official plans and specifications.

**ATTACHMENTS:**

1. Pre-Bid Meeting Sign-In Sheet

August 30, 2019

**END ADDENDUM NO. 1**



Project T1833-01 HQ + ADMIN @  
CAMP CROWDER - PRE-BID

Project No. \_\_\_\_\_ By \_\_\_\_\_ Ck \_\_\_\_\_  
 Date 8/22/2019 Pg. \_\_\_\_\_ of \_\_\_\_\_

GLMV Architecture

NAME	COMPANY	EMAIL	PHONE
RYAN KOEMER	GLMV Architecture	RYAN.KOEMER@GLMV.COM	816.444.4200
Rick Spivey	CDL Electric	richardospivey@cdl-electric.com	620-231-6420
Craig Erickson	Marelock Builders	Craig@marelockbuilders.com	231-6420
KEN BURMIST	BLACKDOG BMT, SDVS	KBURMIST@BLACKDOG-K.COM	(417) 864-6661
Zach Johnson	Construction Services Group	estimating@morionlc.net	816-591-2622
Scott Lea	Branco	estimating@branco.com	417-592-5164
Jeremy Newton	MOARNG	jeremy.l.newton.nfg@gmail.com	417-592-3893
Kevin Brady	Lyerla Heating & Air	Kevin@lyerlah Heatingandair.com	573-308-6894
JUSTIN UNDERWOOD	DAJAN-KUNDAER CONST.	bidfile@dajankilling.com	417-623-1223
Craig Beck	OA-FMDC	Craig.bock@oa.mo.gov	417-624-0651
			573-751-7831