

ADDENDUM NO. 03

TO: PLANS AND SPECIFICATIONS FOR STATE OF MISSOURI

Replace Fire Alarm System, Infrastructure
Moberly Correctional Center
PROJECT NO.: C2511-01

Bid Opening Date: **1:30 PM, Tuesday, September 01, 2026**

Bidders are hereby informed that the construction Plans and/or Specifications are modified as follows:

SPECIFICATION CHANGES:

1. NONE

DRAWINGS CHANGES:

1. SHEET F-GN-01 – FIRE ALARM GENERAL NOTES

- a. Revise General Note #2, items a, b, c, and d, to read as follows:

ALL WORK SHALL BE DESIGNED, INSTALLED, AND TESTED IN COMPLIANCE WITH THE CODES, STANDARDS, AND AMENDMENTS ADOPTED BY THE STATE OF MISSOURI AND THE CONTRACT DOCUMENTS. PROJECTS DESIGNED THROUGH THE DIVISION OF FACILITIES MANAGEMENT, DESIGN AND CONSTRUCTION SHALL BE DESIGNED IN ACCORDANCE WITH THE LATEST EDITION OF CODES AND STANDARDS PUBLISHED BY THE FOLLOWING:

- a. **2024** INTERNATIONAL BUILDING CODE
- b. **2024** INTERNATIONAL FIRE CODE
- c. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
- d. NATIONAL FIRE PROTECTION ASSOCIATION
 - **2025** NFPA 70 – NATIONAL ELECTRICAL CODE
 - **2026** NFPA 72 – NATIONAL FIRE ALARM AND SIGNALING CODE

2. SHEET F-GN-01 – FIRE ALARM GENERAL NOTES

- a. Add General Note #48 as follows:

TAMPER SWITCHES ARE A MIX OF “BUILT-IN” TAMPER VALVE ASSEMBLIES FROM FACTORY FIRE SPRINKLER VALVES AND “STAND-ALONE” EXTERNAL TAMPERS FOR OS&Y GATE VALVES. TOTAL COUNTS ARE THE FOLLOWING:

- FACTORY BUILT-IN TAMPER BUTTERFLY VALVE ASSEMBLIES: 25
- STAND-ALONE EXTERNAL TAMPERS: 10

3. SHEET F-GN-01 – FIRE ALARM GENERAL NOTES

- a. Add General Note #49 as follows:

PER DOC, THE CAMPUS FIBER NETWORK IS A “CLASS A” WIRING NETWORK USING MULTI-MODE FIBER. PROVIDED BY OTHERS.

GENERAL COMMENTS:

1. Questions related to bid submittal and or the bid forms should be directed to the Contract Specialist at the following contact information:
 - a. Email: Mandy.Roberson@oa.mo.gov Phone #: (573)690-9411

ATTACHMENTS:

- A. NONE

August 25, 2026

END ADDENDUM 03