

ADDENDUM NO. 2

TO: PLANS AND SPECIFICATIONS FOR STATE OF MISSOURI

Replace Fluid Cooler, Wheeler Hall & Administration Building
Missouri School For The Deaf
Fulton, Missouri
Project No.: E2304-01

Bid Opening Date: 1:30 PM, May 11, 2023 (Not Changed)

Bidders are hereby informed that the construction Plans and/or Specifications are modified as follows:

SPECIFICATION CHANGES:

None

DRAWING CHANGES:

1.

Sheet E-101 – Sheet Not Re-issued

- a. Update Keyed Note 8 to read as follows:
“PROVIDE AND INSTALL **NEMA 4** DISCONNECT FOR NEW FC-1.
PROVIDE AND INSTALL NEW WEATHERPROOF GFI CONVENIENCE
OUTLET. ROUTE NEW CONDUIT AND FEEDERS FROM JUNCTION BOX
IN TUNNEL TO DISCONNECT AND GFI OUTLET. ROUTE FEEDERS FOR
GFI OUTLET IN SEPARATE CONDUIT. ROUTE CONTROL WIRING IN
SEPARATE CONDUIT. ALL CONDUIT AND FEEDERS SHALL BE RATED
FOR DIRECT BURY.
- b. Update Keyed Note 10 to read as follows:
“MOUNT VFD ENCLOSURE, FC-1 DISCONNECT, AND GFI OUTLET ON
FIELD FABRICATED FRAME. FRAME SHALL BE FABRICATED FROM
UNISTRUT OR EQUAL AND SHALL BE ANCHORED TO THE CONCRETE
PAD USING POST BASES AND APPROPRIATE CONCRETE FASTENERS.
MOUNTING TO COOLING TOWER IS NOT ACCEPTABLE.

GENERAL COMMENTS:

Response to Bidder Questions:

1. On Sheet E-101 keyed note 9: VFD for fan (10hp) and pump (2hp)? Can you also confirm if required in Nema 4 or Nema 3R. **This enclosure is required to be NEMA 3R, to ensure proper air circulation.**
2. On Sheet E-101 keyed note 8: Disconnect - is this rated at Nema 4 or 3R. **Disconnect is required to be NEMA 4.**

ATTACHMENTS:

NONE

END OF ADDENDUM NO. 2