

ADDENDUM NO. 2

TO: PLANS AND SPECIFICATIONS FOR STATE OF MISSOURI

**Replace Retaining Walls
Mississippi Valley State School
Hannibal, Missouri
PROJECT NO. E2401-01**

Bid Date is: 1:30 PM, Tuesday, June 24, 2025

Bidders are hereby informed that the Construction Plans and/or Specifications are modified as follows:

BID FORM CHANGES:

1. None

SPECIFICATION CHANGES:

1. SECTION 323223 – SEGMENTAL RETAINING WALLS; Clarification: Please note that in accordance with paragraph 1.4 B. Delegated-Design or Engineered Shop Drawing: that a licensed Missouri Engineer is ultimately responsible for these retaining walls designs and that long as the extend and configuration of these retaining walls is kept as shown, minor changes can be considered to insure a safely engineered design.
2. SECTION 323223 – SEGMENTAL RETAINING WALLS; paragraph 2.2 SEGMENTAL RETAINING WALL (SRW) UNITS lists three approved block systems for this project. The AB Collection by Allan Block Retaining Wall Systems as manufactured by Reading Rock, 801 N. McKinley Ave., Champaign, IL 61821 (Phone #630-864-8604) shall be considered an approved equal for this project.

DRAWING CHANGES:

1. Section callouts on the Large Scale Plans on sheets A-201 and A-202 do not callout the correct wall sections as shown on Sheets A-301 or A-302. Disregard these symbols and their locations. Wall Sections on sheet A-301 represent the minimum and maximum height of the South Segmental Retaining Wall and the Wall Sections on sheet A-302 represent the minimum and maximum height of the North Segmental Retaining Wall.
2. Sheet A-201, 4/A-201 SOUTH SEGMENTAL RETAINING WALL – LARGE SCALE PLAN: does not show that there are two doorways and a sidewalk that exit to the exterior and center on the existing sidewalk. Contractor shall saw cut this walk at its juncture with the removed portion of the existing sidewalk and pour a new 6' wide portion of sidewalk out to meet the new sidewalk. Concrete sidewalk details shall be similar to those shown in Wall Section 3/A-301.

GENERAL COMMENTS:

1. The Pre-Bid Meeting was held June 6, 2025 followed by a walk-through of the site. The Pre-Bid Meeting sign-in sheet is attached.
2. Bidders needing additional site inspection should contact Kenneth Sheputis at 417.576.7161 to schedule a time.

3. Please contact April Howser, Contract Specialist, at 573-751-0053 or april.howser@oa.mo.gov, for questions about bidding procedures and MBE\WBE\SDVE goals and submittal requirements.
4. The deadline for technical questions is Noon on June 16, 2025.
5. Changes to, or clarification of, the bid documents are only made as issued in the addenda.
6. All correspondence with respect to this project must include the State of Missouri project number as indicated above.
7. Current Planholders list available online at: [E2401-01 Replace Retaining Walls-State School Building-Mississippi Valley State School :: State of Missouri Office of Administration](#) Prospective Bidders contact American Document Solutions, 1400 Forum Blvd Suite 1C, Columbia MO 65201, 573-446-7768 to order official plans and specifications.
8. **All bids shall be submitted on the bid form without additional terms and conditions, modifications, or stipulations. Each space on the bid form shall be properly filled including a bid amount for the alternates. Failure to do so will result in rejection of the bid.**
9. **MBE/WBE/SDVE participation requirements can be found in DIVISION 00. The MBE/WBE/SDVE participation goals are 10%/10%/3%, respectively. Only certified firms as of the bid opening date can be used to satisfy the MBE/WBE/SDVE participation goals for this project. If a bidder is unable to meet a participation goal, a Good Faith Effort Determination Form must be completed. Failure to complete this process will result in rejection of the bid.**

ATTACHMENTS:

1. None

June 17, 2025

END ADDENDUM NO. 2