

ADDENDUM NO. 2

TO: PLANS AND SPECIFICATIONS FOR STATE OF MISSOURI

**New Fire Station Expansion
Missouri State Fairgrounds
Sedalia, Missouri
PROJECT NO. F2405-01**

Bid Date is: 1:30 PM, Tuesday, October 21, 2025 (UNCHANGED)

Bidders are hereby informed that the Construction Plans and/or Specifications are modified as follows:

SPECIFICATION CHANGES:

1. Section 01 2300 – Alternates
 - a. Page 2, Item 3.1 Schedule of Alternates: Correct Item C to read “Alternate 3- Standing Seam Metal Roofing System.”.
2. Section 07 4646 - Fiber-Cement Siding
 - a. REMOVE and REPLACE 2.01.A.5 as follows
 5. Factory primed for field painting.
3. Section 08 3300 - Rolling Service Doors
 - a. Add the attached section to the specifications.
4. Section 08 3323 Exterior Overhead Coiling Doors
 - a. 2.03 Materials , B, Change the material to read “Minimum 22-gauge steel front slat with a 24-gauge back slat”.
5. Section 08 5659 Service and Teller Window Units
 - a. Add the attached section to the specifications.
6. Section 08 7100 Door Hardware
 - a. 3.05 Schedule; Item B; Hardware Group 2: Exterior Entrance Doors: Correct door number 136 to read “136A”.
 - b. ADD 2.03.A.2.c and d as follows
 - c. Corbin Russwin (CLX3300 Series)
 - d. Sargent (10X Series).
 - c. ADD 2.04.A.2.c and d as follows
 - c. Corbin Russwin (Access 3)
 - d. Sargent (Degree)
7. Section 224000 – Plumbing Fixtures
 - a. ADD 2.8.A.2 as follows:
 2. Other Approved Manufacturers: Sloan DRS120-REF-FIL-SS

8. Section 085200 - Wood Windows
 - a. ADD 2.01.A.5 as follows:
 5. Quaker Commercial Windows W600 Series
9. Section 087100 – Door Hardware
 - a. ADD 2.08 as follows:
 - 2.08 EXIT DEVICES
 - A. Approved Manufactures:
 1. Corbin Russwin (PED4000/PED5000 Series)
 2. Sargent (PE80 Series).
10. Section 085200 - Wood Windows
 - a. ADD 2.01.A.5 as follows:
 5. Quaker

DRAWING CHANGES:

All drawing changes are denoted on the drawings with a cloud and a delta mark 1 or a just a delta mark 1.

1. Sheet G001
 - a. Index of Drawings: Omit Sheet A102 Second Floor Plans from the Index.
2. Sheet G002
 - a. Changes to Code Summary and 1st Floor Code Plan.
- 3.
4. Sheet S100
 - a. Changed Code References.
5. Sheet S200
 - a. Changed North Arrow for Plan.
6. Sheet S210
 - a. Changed Notes and Dimensions on detail F11/S200.
7. Sheet S300
 - a. Added Notes at North side framing.
8. Sheet S300A
 - a. Changed North Arrow for Plan.
9. Sheet S312
 - a. Revised Detail S30/S300.
10. Sheet A101
 - a. Miscellaneous changes as denoted on the attached drawing.
11. Sheet A102
 - a. Miscellaneous changes as denoted on the attached drawing and Changes to the Equipment Schedule.

12. Sheet A103
 - a. Added Interior Partition Types. Miscellaneous changes as denoted on the attached drawing.
13. Sheet A104
 - a. Changes to Detail K4/A104. Change to Roof Plan.
14. Sheet A105
 - a. Changes to Room Finish Schedule, Finish Legend and First Floor Finish Plan as denoted.
15. Sheet A201
 - a. Miscellaneous changes as denoted on the attached drawing.
16. Sheet A202
 - a. Miscellaneous changes as denoted on the attached drawing.
17. Sheet A203
 - a. Miscellaneous changes as denoted on the attached drawing.
18. Sheet A301
 - a. Miscellaneous changes as denoted on the attached drawing.
19. Sheet A302
 - a. Miscellaneous changes as denoted on the attached drawing.
20. Sheet A601
 - a. Miscellaneous changes as denoted on the attached drawing.
21. Sheet E501
 - a. Added note regarding Transformer requirements.

GENERAL COMMENTS:

NONE

ATTACHMENTS:

1. 083300 Rolling Service Door
2. 085659 Service and Teller Window Units
3. Sheet G002, S100, S200, S210, S300, S300A, S312, A101, A102, A103, A104, A105, A201, A202, A203, A301, A302, A601, A602, E501

END ADDENDUM NO. 2

SECTION 08 3300 ROLLING SERVICE DOORS

PART 1 GENERAL

1.1 SUMMARY

- A. Section Includes: Manual overhead rolling doors.
- B. Related Sections:
 - 1. 06 10 00 Rough Carpentry. Door opening jamb and head members.

1.2 SYSTEM DESCRIPTION

- A. Design Requirements:
 - 1. Cycle Life:
 - a. Standard construction for normal use of up to 20 cycles per day maximum, and a life cycle expectancy of up to 50,000.

1.3 SUBMITTALS

- A. Reference Section 01 33 00 Submittal Procedures; submit the following items:
 - 1. Product Data.
 - 2. Shop Drawings.
 - 3. Closeout Submittals:
 - a. Operation and Maintenance Manual.
 - b. Warranty documentation.

1.4 QUALITY ASSURANCE

- A. Qualifications:
 - 1. Manufacturer Qualifications: ISO 9001:2015 registered and a minimum of five years' experience in producing doors of the type specified.
 - 2. Installer Qualifications: Manufacturer's approval.

1.5 DELIVERY STORAGE AND HANDLING

- A. Follow manufacturer's instructions.

1.6 WARRANTY

- A. Standard Warranty: Two years from date of shipment against defects in material and workmanship.

PART 2 PRODUCTS

2.1 MANUFACTURER

- 1. Cookson: 1901 South Litchfield Road, Goodyear, AZ 85338. Telephone: (855) 719-4040
- 2. Cornell.
- 3. Clopay Building Products.
- 4. Substitutions: See Division 1.

2.2 PRODUCT INFORMATION

- A. Model: ESD10

2.3 MATERIALS

A. Curtain:

1. Slats:
 - a. Aluminum: No. 5F, 16 gauge (0.050 mm) aluminum.
2. Finish:
 - a. Aluminum: Medium bronze anodized.

B. Endlocks:

Alternate slats each secured with two ¼" (6.35 mm) rivets. Fabricate interlocking sections with high strength nylon.

C. Bottom Bar

1. Configuration:
 - a. Extruded Aluminum (Standard to 21'4" opening width): Extruded aluminum alloy 6063-T5.
2. Finish:
 - a. Aluminum: Medium bronze anodized.

D. Guides:

1. Fabrication:
 - a. Structural aluminum angles. Provide windlock bars as required, removable bellmouths, and bottom bar stoppers of same material.
2. Finish:
 - b. Aluminum: Medium bronze anodized.

E. Counterbalance Shaft Assembly:

1. Barrel: Steel pipe capable of supporting curtain load with maximum deflection of 0.03 inches per foot (2.5 mm per meter) of width
2. Spring Balance: Oil-tempered, heat-treated steel helical torsion spring assembly designed for proper balance of door to ensure that maximum effort to operate will not exceed 25 lbs. (110 N). Provide wheel for applying and adjusting spring torque

F. Brackets:

Fabricate from minimum 3/16 inch (5 mm) steel plate with permanently lubricated ball or roller bearings at rotating support points to support counterbalance shaft assembly and form end closures

1. Finish:
 - a. Powder Coat:
 - 1) Zirconium pre-treatment followed by baked-on polyester powder coat. minimum 2.5 mils (0.065 mm) cured film thickness; ASTM D-3363 pencil hardness: H or better.
 - a) Stock color to match curtain [gray] [tan] [white] [brown]
 - b) SpectraShield color as selected by Architect from manufacturer's color range, more than 180 colors
 - c) Custom color as selected by Architect
 - d) AtmoShield textured environmental coating; color as selected by Architect.

G. Hood:

Aluminum with reinforced top and bottom edges. Provide intermediate support brackets as required.

1. Finish:
 - a. Aluminum: Medium bronze anodized.

- H. Weatherstripping:
 1. Bottom Bar: Replaceable, bulb-style, compressible EDPM gasket extending into guides.
 2. Guides: Vinyl strip sealing against fascia side of curtain.

2.4 OPERATION

- A. Manual ControlGard Chain Hoist: Provide chain hoist operator with endless steel chain, chain pocket wheel and guard, geared reduction unit, and chain keeper secured to guide. Chain hoist to include integral brake mechanism that will immediately stop upward or downward travel and maintain the door in a stationary position when the hand chain is released by the user.

2.5 ACCESSORIES

- A. Locking:
 4. Master keyable cylinder operable from coil side of opening, options for all types of operation. See Specification Section 08 7100 for core information.
- F. Interior Aesthetic Covers:
 1. Operator and Bracket Mechanism Cover: Aluminum sheet metal to enclose exposed operating components at coil area of unit. Finish matching hood.
 2. Guide Trim Package: Powder coated steel to match guides.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Examine substrates upon which work will be installed and verify conditions are in accordance with approved shop drawings
- B. Coordinate with responsible entity to perform corrective work on unsatisfactory substrates
- C. Commencement of work by installer is acceptance of substrate.

3.2 INSTALLATION

- A. Install door and operating equipment with necessary hardware, anchors, inserts, hangers and supports.
- B. Follow manufacturer's installation instructions.

3.3 ADJUSTING

- A. Following completion of installation, including related work by others, lubricate, test, and adjust doors for ease of operation, free from warp, twist, or distortion.

3.4 CLEANING

- A. Clean surfaces soiled by work as recommended by manufacturer.
- B. Remove surplus materials and debris from the site.

3.5 DEMONSTRATION

- A. Demonstrate proper operation to Owner's Representative.
- B. Instruct Owner's Representative in maintenance procedures.

END OF SECTION 08 3300

SECTION 08 5659
SERVICE AND TELLER WINDOW UNITS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Service and teller window units.

1.02 REFERENCE STANDARDS

- A. AAMA 611 - Specification for Anodized Architectural Aluminum; 2024.
- B. ASTM B221 - Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes; 2020.
- C. ASTM B221M - Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes (Metric); 2013.

1.03 SUBMITTALS

- A. See Division 1 for submittal procedures.
- B. Product Data: Submit manufacturer's product data for specified products indicating materials, operation, glazing, finishes, and installation instructions.
- C. Shop Drawings: Indicate configuration, sizes, rough-in, mounting, anchors and fasteners, and installation clearances.
- D. Manufacturer Qualification Statement.
- E. Installer Qualification Statement.
- F. Warranty: Submit manufacturer warranty and ensure that forms have been completed in Owner's name and registered with manufacturer.

1.04 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing products specified in this section with at least ten years documented experience, and with ability to provide test reports showing that their standard manufactured products meet the specified requirements.
- B. Installer Qualifications: Company specializing in performing work of the type specified and with at least three years of documented experience.

1.05 DELIVERY, STORAGE, AND HANDLING

- A. Deliver units in manufacturer's original packaging and unopened containers with identification labels intact.
- B. Store units in area protected from exposure to weather and vandalism.

1.06 WARRANTY

- A. See Division 1 for additional warranty requirements.
- B. Provide manufacturer's warranty agreeing to repair or replace units and their components that fail in materials or workmanship within five years from Date of Substantial Completion.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Service and Teller Window Units:
 - 1. Quikserv; Model SC3030: www.quikserv.com/#sle.
 - 2. Ready Access, Inc; Single Panel Sliding Service Window: www.ready-access.com/#sle.
 - 3. CR Laurence; DW36360XGA Sliding Service Window: <https://www.crlaurence.com>
 - 4. Substitutions: See Division 1.

2.02 SERVICE AND TELLER WINDOW UNITS

- A. Location: Built within interior wall, as indicated on drawings.
- B. Window Type: Sliding, single horizontal.
 - 1. Operation: Manual.
 - 2. Mounting: Flush with wall surface.
 - 3. Window Size: 36 inch wide by 36 inch high.
 - 4. Material: Aluminum.
 - a. Finish: Pigmented coating, manufacturer's standard type.
 - b. Finish Color: As selected from manufacturer's standard colors.
 - 5. Header: Manufacturer's standard type.
 - 6. Sill: Manufacturer's standard type.
- C. Glazing: Single (monolithic), clear.
 - 1. Tempered safety glazing.

2.03 ASSEMBLY COMPONENTS

- A. Windows: Factory-fabricated, finished, and glazed, with extruded aluminum frame and glazing stops; complete with hardware and anchors.
 - 1. Provide window units that are re-glazable from the secure side without dismantling the non-secure side of framing.

2. Rigidly fit and secure joints and corners with internal reinforcement. Make joints and connections flush, hairline, and weatherproof. Fully weld corners.
3. Apply factory finish to exposed surfaces.

2.04 MATERIALS

- A. Aluminum Extrusions: Minimum 1/8 inch thick frame and sash material complying with ASTM B221 and ASTM B221M.
- B. Sealant for Setting Sills and Sill Flashing: Non-curing butyl type.

2.05 FINISHES

- A. Class II Natural Anodized Finish: AAMA 611 AA-M12C22A31 Clear anodic coating not less than 0.4 mils thick.
- B. Color: To be selected by Architect from manufacturer's standard range.

2.06 ACCESSORIES

- A. Hardware and Security Devices for Sliding Windows:
 1. Auto-Lock Handle: Stainless steel auto-locking handle on all self-closing sliders to prevent intrusion.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that window openings are ready for installation of windows.
- B. Verify that correct embedded anchors are in place and in proper location; repair or replace anchors as required to achieve satisfactory installation.
- C. Notify Architect if conditions are not suitable for installation of units; do not proceed until conditions are satisfactory.

3.02 INSTALLATION

- A. Install in accordance with manufacturer's instructions.
- B. Install units in correct orientation (inside/outside or secure/non-secure).
- C. Anchor units securely in manner so as to achieve performance specified.
- D. Set sill members and sill flashing in continuous bead of sealant.

3.03 ADJUSTING

- A. Adjust operating components for smooth operation while also maintaining a secure, weather-tight enclosure and a tight fit at the contact points; lubricate operating hardware.

3.04 CLEANING

- A. Remove protective material from factory finished surfaces.
- B. Clean exposed surfaces promptly after installation without damaging finishes.

3.05 PROTECTION

- A. Provide temporary protection to ensure that service and teller windows are without damage upon Date of Substantial Completion.

END OF SECTION 08 5659



09/19/2025



PWArchitects, Inc.
2120 Forest Blvd., Ste. 101
St. Louis, MO 63114
Phone: (314) 433-1100
Fax: (314) 433-1101
Email: info@pwarchitects.com
Website: www.pwarchitects.com

OFFICE OF
ADMINISTRATION
DIVISION OF
FACILITIES
MANAGEMENT,
DESIGN AND
CONSTRUCTION

NEW FIRE STATION
MISSOURI STATE FAIR
SEDALIA, MISSOURI

PROJECT # F2405-01
SITE # 1501
ASSET # 3511501027
PWA # 202011.13

REVISION: ADDENDUM J
REVISION: 09/17/2025
REVISION: 09/17/2025
DATE: 09/19/2025

CAD DWG FILE:
DRAWN BY: JG
DESIGNED BY: JG
SHEET TITLE:
ENLARGED
FLOOR PLAN

SHEET NUMBER:
A-102
26 OF 57 SHEETS
09/19/2025

ITEM #	DESCRIPTION
K-1	STAINLESS STEEL TABLE, 78" X 30" X 28" W/ DRAWER & SHELF, F.B.G.C., 18" G.C.
K-2	1/2" L.P. MACHINE, F.B.G.C., 18" G.C.
K-3	1/2" L.P. MACHINE, F.B.G.C., 18" G.C.
K-4	1/2" L.P. MACHINE, F.B.G.C., 18" G.C.
K-5	1/2" L.P. MACHINE, F.B.G.C., 18" G.C.
K-6	1/2" L.P. MACHINE, F.B.G.C., 18" G.C.
K-7	1/2" L.P. MACHINE, F.B.G.C., 18" G.C.
K-8	1/2" L.P. MACHINE, F.B.G.C., 18" G.C.
K-9	1/2" L.P. MACHINE, F.B.G.C., 18" G.C.
K-10	1/2" L.P. MACHINE, F.B.G.C., 18" G.C.
K-11	1/2" L.P. MACHINE, F.B.G.C., 18" G.C.
K-12	1/2" L.P. MACHINE, F.B.G.C., 18" G.C.
K-13	1/2" L.P. MACHINE, F.B.G.C., 18" G.C.
K-14	1/2" L.P. MACHINE, F.B.G.C., 18" G.C.
K-15	1/2" L.P. MACHINE, F.B.G.C., 18" G.C.
K-16	1/2" L.P. MACHINE, F.B.G.C., 18" G.C.
K-17	1/2" L.P. MACHINE, F.B.G.C., 18" G.C.
K-18	1/2" L.P. MACHINE, F.B.G.C., 18" G.C.
K-19	1/2" L.P. MACHINE, F.B.G.C., 18" G.C.
K-20	1/2" L.P. MACHINE, F.B.G.C., 18" G.C.
K-21	1/2" L.P. MACHINE, F.B.G.C., 18" G.C.
K-22	1/2" L.P. MACHINE, F.B.G.C., 18" G.C.
K-23	1/2" L.P. MACHINE, F.B.G.C., 18" G.C.
K-24	1/2" L.P. MACHINE, F.B.G.C., 18" G.C.

GENERAL FLOOR PLAN NOTES

- VERIFY ALL DIMENSIONS AND CONDITIONS PRIOR TO EXECUTING ANY WORK. IF ANY DISCREPANCIES ARE FOUND, NOTIFY THE ARCHITECT IMMEDIATELY. DIMENSIONS ON WORK DIFFERING FROM THIS SET OF DRAWINGS SHALL BE THE ARCHITECT'S INTENT.
- VERIFY ALL ROUGH OPENINGS FOR ALL MECHANICAL, ELECTRICAL, AND PLUMBING ITEMS PRIOR TO PROCEEDING WITH WORK. EXECUTION OF ANY WORK AFFECTED BY THESE CONDITIONS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- VERIFY ALL ROUGH OPENINGS FOR ALL MECHANICAL, ELECTRICAL, AND PLUMBING ITEMS PRIOR TO PROCEEDING WITH WORK. EXECUTION OF ANY WORK AFFECTED BY THESE CONDITIONS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- COORDINATE ALL FLOOR DRAINS AND OTHER MECHANICAL, ELECTRICAL, AND PLUMBING ITEMS WITH THE MECHANICAL, ELECTRICAL, AND PLUMBING ENGINEERS PRIOR TO PROCEEDING WITH THE WORK.
- COORDINATE ALL REQUIRED UTILITIES WITH THE UTILITY MANUFACTURER PRIOR TO PROCEEDING WITH THE WORK.
- ALL DIMENSIONS ARE TO FACE OF STUD IO UNLESS OTHERWISE NOTED.
- DO NOT SCALE DRAWINGS. WHERE DIMENSIONS ARE NOTED, THEY SHALL TAKE PRECEDENCE OVER DIMENSIONS SHOWN ON THE DRAWINGS.
- COORDINATE HEIGHTS OF OUTLETS & OTHER MECHANICAL, ELECTRICAL, AND PLUMBING ITEMS WITH THE MECHANICAL, ELECTRICAL, AND PLUMBING ENGINEERS PRIOR TO PROCEEDING WITH THE WORK.
- SEE A300 FOR INTERIOR PARTITION WALL TYPES AND DETAILS.
- SEE A300 FOR INTERIOR PARTITION WALL TYPES AND DETAILS.

ENLARGED FLOOR PLAN
SCALE: 3/8"=1'-0"



OFFICE OF
ADMINISTRATION
DIVISION OF
FACILITIES
MANAGEMENT,
DESIGN AND
CONSTRUCTION

NEW FIRE STATION
MISSOURI STATE FAIR
SEDALIA, MISSOURI

PROJECT # F2405-01
SITE # 1501
ASSET # 3511501027
PWA # 202011.13

REVISION: ADDITIONAL
REVISION: REVISION
REVISION: REVISION
DATE: 09/19/2025

CAD DWG FILE:
DRAWN BY:
DESIGNED BY: ENLUC
SHEET TITLE:

REFLECTED
CEILING PLANS




SHEET NUMBER:
A103


27 OF 57 SHEETS
09/19/2025

GENERAL REF. CEILING PLAN NOTES

1. FIELD VERIFY ALL DIMENSIONS AND WORK. NOTIFY ARCHITECT OF ANY DISCREPANCIES PRIOR TO PROCEEDING. THE ARCHITECT PRIOR TO PROCEEDING WITH THE WORK.
2. VERIFY ALL VOUCHER OPENINGS FOR DOORS, WINDOWS, EQUIPMENT, & VENTILATION. PROVIDE VOUCHER TO EXISTING OF ANY WORK AFFECTED BY SAME.
3. COORDINATE ALL REQUIRED UTILITIES WITH EQUIPMENT MANUFACTURER. COORDINATE ALL REQUIRED UTILITIES WITH EQUIPMENT MANUFACTURER. COORDINATE ALL REQUIRED UTILITIES WITH EQUIPMENT MANUFACTURER.
4. ALL DIMENSIONS ARE TO FINISH WALL. - DO NOT SCALE DRAWINGS - WHERE ENCOUNTERED, PROVIDE MEASUREMENTS. ENCOUNTERED NOTED ARCHITECT PRIOR TO PROCEEDING WITH THE WORK. COORDINATE ALL LIGHT FIXTURES, DRAWINGS.
5. COORDINATE ALL LIGHT FIXTURES, DRAWINGS.
6. COORDINATE ALL LIGHT FIXTURES, DRAWINGS.


CEILING MATERIAL LEGEND












ROOM FINISH SCHEDULE									
ROOM NO.	ROOM NAME	FLOOR MAT'L	BASE MAT'L	NORTH	EAST	SOUTH	WEST	FINISH	CEILING

101	VESTIBULE	LVF-1	REB-1	P-1	P-1	P-1	P-1	P-2	10' 0"
102	VESTIBULE	LVF-1	REB-1	P-1	P-1	P-1	P-1	ACT-1	8' 0"
103	VESTIBULE	LVF-1	REB-1	P-1	P-1	P-1	P-1	ACT-1	8' 0"
104	RESTROOM	LVF-1	REB-1	P-1	P-1	P-1	P-1	ACT-1	8' 0"
105	DISPATCH	OPT-1	REB-1	P-1	P-1	P-1	P-1	ACT-1	8' 0"
106	MECHANICAL	S.C.	REB-1	P-1	P-1	P-1	P-1	P-2	10' 0"
107	OFFICE	LVF-1	REB-1	P-1	P-1	P-1	P-1	ACT-1	8' 0"
108	OFFICE	LVF-1	REB-1	P-1	P-1	P-1	P-1	ACT-1	8' 0"
109	GEAR STORAGE	S.C.	REB-1	P-1	P-1	P-1	P-1	P-2	10' 3"
110	KITCHEN	LVF-1	REB-1	P-1	P-1	P-1	P-1	ACT-2	8' 0"
111	UTILITY	LVF-1	REB-1	P-1	P-1	P-1	P-1	ACT-1	8' 0"
112	UNDEX RR	LVF-1	REB-1	P-1	P-1	P-1	P-1	ACT-1 / P-2	8' 0"
113	SPRINKLER	S.C.	REB-1	P-1	P-1	P-1	P-1	P-2	8' 0"
114	MECH	LVF-1	REB-1	P-1	P-1	P-1	P-1	ACT-1	8' 0"
115	HALL	LVF-1	REB-1	P-1	P-1	P-1	P-1	ACT-1	8' 0"
116	OFFICE	LVF-1	REB-1	P-1	P-1	P-1	P-1	ACT-1	8' 0"
117	OFFICE	LVF-1	REB-1	P-1	P-1	P-1	P-1	ACT-1	8' 0"
118	OFFICE	LVF-1	REB-1	P-1	P-1	P-1	P-1	ACT-1	8' 0"
119	BUNK #1	OPT-1	REB-1	P-1	P-1	P-1	P-1	ACT-1	8' 0"
120	BUNK #2	OPT-1	REB-1	P-1	P-1	P-1	P-1	ACT-1	8' 0"
121	LAUNDRY	LVF-1	REB-1	P-1	P-1	P-1	P-1	ACT-1	8' 0"
122	MECH / ELEC	LVF-1	REB-1	P-1	P-1	P-1	P-1	ACT-1	8' 0"
123	MECH / ELEC	S.C.	REB-1	P-1	P-1	P-1	P-1	P-2	10' 8"
124	MECH / ELEC	S.C.	REB-1	P-1	P-1	P-1	P-1	P-2	10' 8"
125	WOMEN'S RR	LVF-1	REB-1	P-1	P-1	P-1	P-1	ACT-1 / P-2	8' 0"
126	WOMEN'S RR	LVF-1	REB-1	P-1	P-1	P-1	P-1	ACT-1	8' 0"
127	WOMEN'S RR	LVF-1	REB-1	P-1	P-1	P-1	P-1	ACT-1	8' 0"
128	HALL	LVF-1	REB-1	P-1	P-1	P-1	P-1	ACT-1	8' 0"
129	HALL	LVF-1	REB-1	P-1	P-1	P-1	P-1	ACT-1	8' 0"
130	CORRIDOR	LVF-1	REB-1	P-1	P-1	P-1	P-1	ACT-1	8' 0"
131	CORRIDOR	LVF-1	REB-1	P-1	P-1	P-1	P-1	ACT-1	8' 0"
132	UNEX'G MEETING	LVF-1	REB-1	P-1	P-1	P-1	P-1	ACT-1	12' 0"
133	BUNK #5	OPT-1	REB-1	P-1	P-1	P-1	P-1	ACT-1	8' 0"
134	BUNK #6	OPT-1	REB-1	P-1	P-1	P-1	P-1	ACT-1	8' 0"
135	BUNK #7	OPT-1	REB-1	P-1	P-1	P-1	P-1	ACT-1	8' 0"
136	HALL	LVF-1	REB-1	P-1	P-1	P-1	P-1	ACT-1	8' 0"





GENERAL SECTION NOTES

1. MEASURE ALL DIMENSIONS AND CONDITIONS PRIOR TO EXECUTING ANY WORK. VERIFY EXISTING CONDITIONS AND WORK OFFERING FROM THAT SHOWN FOR CLARIFICATION BY THE ARCHITECT PRIOR TO PROCEEDING WITH CONSTRUCTION.
2. VERIFY ALL SOLID OPENINGS FOR DOORS, WINDOWS, EQUIPMENT & OTHER "HULL IN" ITEMS PRIOR TO THE EXECUTION OF ANY WORK AFFECTED BY SAME.

STATE OF MISSOURI
MIKE KEHOE
GOVERNOR



PwArchitects, Inc.
2120 Forest Blvd., Ste. 101
Plymouth, MO 64575
Phone: (417) 333-1111
Fax: (417) 333-1112
Email: info@pwarchitects.com
Website: www.pwarchitects.com

OFFICE OF
ADMINISTRATION
DIVISION OF
FACILITIES
MANAGEMENT,
DESIGN AND
CONSTRUCTION

NEW FIRE STATION
MISSOURI STATE FAIR
SEDALIA, MISSOURI

PROJECT # F2405-01
SITE # 1501
ASSET # 3511501027
PWA # 202011.13


REVISION: ADDENDUM J
REVISION: JULIE 2024
DATE: 09/19/2025


CAD DWG FILE: 1501
DRAWN BY: JLM
DESIGNED BY: JLM

SHEET TITLE:
BUILDING
SECTIONS AND
DETAILS

SHEET NUMBER:
A301

33 OF 57 SHEETS
09/19/2025







OFFICE OF
ADMINISTRATION
DIVISION OF
FACILITIES
MANAGEMENT,
DESIGN AND
CONSTRUCTION

EXPANSION
FIRE STATION

PROJECT #	F2405-01
SITE #	1501
ASSET #	3511501027
PWA #	202011.13

REVISION: ADDENDUM #1
DATE: 10/14/2025
REVISION: _____
DATE: _____
REVISION: _____
DATE: _____

CAD DWG FILE: 20201113-SEDAL
DRAWN BY: WN
CHECKED BY: EM
DESIGNED BY: EM/WN

SHEET TITLE:


DOOR SCHEDULE
& ELEVATIONS

SHEET NUMBER: _____

A-601

35 OF 57 SHEETS

5606192025

[illegible]



Pecham & Wright Architects, Inc., d.b.a.
PWArchitects, Inc.
2120 Fenim Blvd., Ste. 101
Columbia, Missouri 65203
PWArchitects.com | 573.449.2683

Pecham & Wright Architects are Architectural Corporation
Missouri State Certificate of Authority No. 000244

EXPANSION
RESTATION
MISSOURI STATE FAIR
MEDALIA, MISSOURI

PROJECT #	F2405-01
ITE #	1501
SSSET #	3511501027
NA #	202011.13

REVISION: ADDENDUM #1
DATE: 10/14/2025
REVISION: _____
DATE: _____
REVISION: _____
DATE: _____
ISSUE DATE: 09/19/2025

READ DWG FILE: SEFS A600s.dwg
DRAWN BY: LC, WN
CHECKED BY: EM
SIGNED BY: EM/WN
SHEET TITLE:

WINDOW &
DOOR DETAILS

A-602
36 OF 57 SHEETS
09/19/2025

