# PROJECT MANUAL

Renovate Lobby and Restroom

1st and 2nd Floor

Howerton State Office Building

Jefferson City, Missouri

Designed By: OA-FMDC Project Design Unit

301 West High Street, Room 780

Jefferson City, MO 65101

Date Issued: December 13, 2024

Project No.: O2339-01

State of Missouri

OFFICE of ADMINISTRATION
Facilities Management, Design and Construction

# SECTION 000107 - PROFESSIONAL SEALS AND CERTIFICATIONS

PROJECT NUMBER: 02339-01

THE FOLLOWING DESIGN PROFESSIONALS HAVE SIGNED AND SEALED THE ORIGINAL PLANS AND SPECIFICATIONS FOR THIS PROJECT, WHICH ARE ON FILE WITH THE DIVISION OF FACILITIES MANAGEMENT, DESIGN AND CONSTRUCTION:



Brad M. Schaefer - Architect MO# A-2009027294

PROJECT MANUAL DIVISIONS 1, 2, 5, 6, 7, 8, 9, 10 &12



Tracie L. Siebeneck - Engineer MO# PE-2013019114

PROJECT MANUAL DIVISIONS 1, 21, 22, 23, 26 & 28

## TABLE OF CONTENTS

	TABLE OF CONTENTS	
<b>SECTION</b>	TITLE NUMBER (	OF PAGES
DIVISION 00	- PROCUREMENT AND CONTRACTING INFORMATION	
000000 INTI	RODUCTORY INFORMATION	
000101	Project Manual Cover	1
000107	Professional Seals and Certifications	1
000110	Table of Contents	3
000115	List of Drawings	3
001116 INVI	TATION FOR BID (IFB)	1
002113 INST	RUCTIONS TO BIDDERS	7
	NOTICE TO BIDDERS	
	The following procurement forms can be found on our website at:	
	https://oa.mo.gov/facilities/bid-opportunities/bid-listing-electronic-plans and shall be submitted with your bid to FMDCBids@oa.mo.gov	
004000 DDO		
004000 PRO 004113	CUREMENT FORMS & SUPPLEMENTS Bid Form	*
004322	Unit Prices Form	*
004322	Proposed Subcontractors Form	*
004337	MBE/WBE/SDVE Compliance Evaluation Form	*
004338	MBE/WBE/SDVE Eligibility Determination	*
001330	Form for Joint Ventures	
004339	MBE/WBE/SDVE Good Faith Effort (GFE)	*
	Determination Forms	
004340	SDVE Business Form	*
004541	Affidavit of Work Authorization	*
004545	Anti-Discrimination Against Israel Act Certification form	*
005000 CON	TRACTING FORMS AND SUPPLEMENTS	
005213	Construction Contract	3
006000 PRO	JECT FORMS	
006113	Performance and Payment Bond	2
006325	Product Substitution Request	2
006519.16	Final Receipt of Payment and Release Form	1
006519.18	MBE/WBE/SDVE Progress Report	2
006519.21	Affidavit of Compliance with Prevailing Wage Law	1
007000 CON	DITIONS OF THE CONTRACT	
007213	General Conditions	20
007300	Supplementary Conditions	1
007346	Wage Rate	4
DIVISION 1 -	GENERAL REQUIREMENTS	
011000	Summary of Work	2
012600	Contract Modification Procedures	2
013100	Coordination	3
013115	Project Management Communications	3
013200	Schedules	3
013300	Submittals  Size Size Size Size Size Size Size Size	6
013513.10	Site Security and Health Requirements (OA)	4
015000	Construction Facilities and Temporary Controls	6
017400	Cleaning	3

# TECHNICAL SPECIFICATIONS INDEX:

<b>DIVISION 2</b> – 1 024119	EXISTING CONDITIONS Selective Demolition	5
<b>DIVISION 5</b> – 1 051200 055000	METALS Structural Steel Framing Metal Fabrications	6 2
<b>DIVISION 6</b> – 3 061000 064200	WOOD, PLASTICS, AND COMPOSITES Rough Carpentry Stacked Wood Wall Panels	5 2
<b>DIVISION 7</b> – 7 079200	THERMAL AND MOISTURE PROTECTION  Joint Sealants	6
081113 081416 084313 087100 087113 088000	OPENINGS Hollow Metal Doors and Frames Flush Wood Doors Aluminum-Framed Storefronts Door Hardware Power Door Operators Glazing	5 6 4 10 3 4
092116 092216 092226.23 093000 095100 096500 096813 099123	Gypsum Board Assemblies Non-Structural Metal Framing Metal Suspension Systems Tiling Acoustical Ceilings Resilient Flooring Tile Carpeting Interior Painting	4 4 4 5 3 4 3 6
<b>DIVISION 10</b> – 102113.19 102800	- SPECIALTIES Plastic Toilet Compartments Toilet, Bath, and Laundry Accessories	2 3
<b>DIVISION 12</b> – 123600	FURNISHINGS Countertops	3
<b>DIVISION 21</b> – 211300	FIRE SUPPRESSION Fire-Suppression Sprinkler Systems	2
<b>DIVISION 22</b> – 221006 224000	PLUMBING Plumbing Piping Specialties Plumbing Fixtures	1 4
DIVISION 23 – 230593 230713 233100 233300 233700	HEATING, VENTILATING, AND AIR-CONDITIONING (HVAC) Testing, Adjusting, and Balancing for HVAC Duct Insulation HVAC Ducts and Casings Air Duct Accessories Air Outlets and Inlets	3 2 3 1 2
<b>DIVISION 26</b> – 260519 260526 260529	- ELECTRICAL  Low-Voltage Electrical Power Conductors and Cables  Grounding and Bonding for Electrical Systems  Hangers and Supports for Electrical Systems	6 2 3

260533.13	Conduit for Electrical Systems	4
260533.16	Boxes for Electrical Systems	3
260583	Wiring Connections	1
262726	Wiring Devices	4
265100	Interior Lighting	4
<b>DIVISION 28</b> – 284600	ELECTRONIC SAFETY AND SECURITY Fire Detection and Alarm	2

# **SECTION 000115 – LIST OF DRAWINGS**

## **PART 1 - GENERAL**

# 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract including General and Supplementary Conditions, Bid Form, and other Division 1 Specification Sections apply to this Section.

# 1.2 SUMMARY

A. This Section provides a comprehensive list of the drawings that comprise the Bid Documents for this project.

# PART 2 - PRODUCTS (NOT APPLICABLE)

# **PART 3 - EXECUTION**

# 3.1 LIST OF DRAWINGS

A. The following list of drawings is a part of the Bid Documents:

	<u>TITLE</u>	SHEET #	<b>DATE</b>	<u>CAD</u>
1.	Cover Sheet	G-001	12/13/2024	G-001_O2409_01
2.	First Floor Lobby & Restroom Demolition Plan	A-100	12/13/2024	A-100_O2409_01
3.	Second Floor Lobby & Restroom Demolition Plan	A-101	12/13/2024	A-101_O2409_01
4.	First Floor Lobby Renovation Plan	A-102	12/13/2024	A-102_O2409_01
5.	Second Floor Lobby Renovation Plan	A-103	12/13/2024	A-103_O2409_01
6.	First Floor Restroom Renovation Plan	A-104	12/13/2024	A-104_O2409_01
7.	Second Floor Restroom Renovation Plan	A-105	12/13/2024	A-105_O2409_01
8.	Lobby Feature Wall Elevations and Details	A-200	12/13/2024	A-200_O2409_01
9.	First Fl. Women's Lobby Restroom Elevations	A-201	12/13/2024	A-201_O2409_01
10.	First Fl. Men's Lobby Restroom Elevations	A-202	12/13/2024	A-202_O2409_01
11.	Second Fl. Women's Lobby Restroom Elevations	A-203	12/13/2024	A-203_O2409_01
12.	Second Fl. Men's Lobby Restroom Elevations	A-204	12/13/2024	A-204_O2409_01

13.	First Fl. Women's Staff Restroom Elevations	A-205	12/13/2024	A-205_O2409_01
14.	First Fl. Men's Staff Restroom Elevations	A-206	12/13/2024	A-206_O2409_01
15.	Second Fl. Women's Staff Restroom Elevations	A-207	12/13/2024	A-207_O2409_01
16.	Second Fl. Men's Staff Restroom Elevations	A-208	12/13/2024	A-208_O2409_01
17.	Restroom Details	A-500	12/13/2024	A-500_O2409_01
18.	Door Details	A-501	12/13/2024	A-501_O2409_01
19.	First Floor Demolition RCP	A-700	12/13/2024	A-700_O2409_01
20.	Second Floor Demolition RCP	A-701	12/13/2024	A-701_O2409_01
21.	First Floor Renovation RCP	A-702	12/13/2024	A-702_O2409_01
22.	Second Floor Renovation RCP	A-703	12/13/2024	A-703_O2409_01
23.	1 <sup>st</sup> & 2 <sup>nd</sup> Floor Staff Restroom Renovation RCP	A-704	12/13/2024	A-704_O2409_01
24.	Fire Protection Plan – 1st Floor	F-101	12/13/2024	F-101.dwg
25.	Fire Protection Plan – 2 <sup>nd</sup> Floor	F-102	12/13/2024	F-102.dwg
26.	Fire Protection Plan – Staff Restrooms	F-103	12/13/2024	F-103.dwg
27.	Plumbing Demolition Plan Restrooms	PD-101	12/13/2024	PD-101.dwg
28.	Plumbing Renovation Plan Restrooms	P-101	12/13/2024	P-101.dwg
29.	Plumbing Schedules and Details	P-601	12/13/2024	P-601.dwg
30.	Mech and Elec Demolition Plan 1st Floor	MED-101	12/13/2024	MED-101.dwg
31.	Mech and Elec Demolition Plan 2 <sup>nd</sup> Floor	MED-102	12/13/2024	MED-102.dwg
32.	Mech and Elec Demolition Plan Staff Restrooms	MED-103	12/13/2024	MED-103.dwg
33.	Mechanical Renovation Plan 1 <sup>st</sup> Floor	M-101	12/13/2024	M-101.dwg
34.	Mechanical Renovation Plan 2 <sup>nd</sup> Floor	M-102	12/13/2024	M-102.dwg
35.	Mechanical Renovation Plan Staff Restrooms	M-103	12/13/2024	M-103.dwg
36.	Electrical Renovation Plan 1 <sup>st</sup> Floor	E-101	12/13/2024	E-101.dwg
37.	Electrical Renovation Plan 2 <sup>nd</sup> Floor	E-102	12/13/2024	E-102.dwg

-103 12/13/2024

E-103.dwg

# **END OF SECTION 000115**

#### SECTION 001116 - INVITATION FOR BID

#### 1.0 OWNER:

A. The State of Missouri

Office of Administration,

Division of Facilities Management, Design and Construction

Jefferson City, Missouri

#### 2.0 PROJECT TITLE AND NUMBER:

A. Renovate Lobby and Restroom 1st and 2nd Floor

Howerton State Office Building Jefferson City, Missouri

Project No.: O2339-01

#### 3.0 BIDS WILL BE RECEIVED:

A. Until: 1:30 PM, April 22, 2025

B. Only electronic bids sent to FMDCBids@oa.mo.gov shall be accepted: (See Instructions to Bidders for further detail)

#### 4.0 DESCRIPTION:

A. Scope: The project includes restroom updates, paint, door replacements, first and second floor lobby modifications and updates, as well as creating a new conference room and two storage rooms. The Work also includes selective demolition and renovation of fire sprinkler system, replacement and integration of ceiling mounted fire alarm strobes and smoke detectors into the existing fire

protection system, replacement of restroom plumbing fixtures and adjustment of water supply inlet for urinal and water closet installation, replacement of air devices and modification of any associated duct, replacement of lighting fixtures and extension of lighting circuit, installation of new feature light, and replacement of all wiring devices located within area of work.

B. MBE/WBE/SDVE Goals: MBE 10%, WBE 10%, and SDVE 3%. NOTE: Only MBE/WBE firms certified by the State of Missouri Office of Equal Opportunity as of the date of bid opening, or SDVE(s) meeting the requirements of Section 34.074, RSMo and 1 CSR 30-5.010, can be used to satisfy the MBE/WBE/SDVE participation goals for this project.

#### 5.0 PRE-BID MEETING:

- A. Place/Time: 11 AM, April, 8, 2025, at 615 Howerton Court, Jefferson City, MO. 65102.
- B. Access to State of Missouri property requires presentation of a photo ID by all persons

#### 6.0 HOW TO GET PLANS & SPECIFICATIONS:

- A. View Only Electronic bid sets are available at no cost or paper bid sets for a **deposit of \$100.00** from American Document Solutions (ADS). MAKE CHECKS PAYABLE TO: American Document Solutions. Mail to: American Document Solutions, 1400 Forum Blvd., Suite 7A, Columbia, Missouri 65203. Phone 573-446-7768, Fax 573-355-5433, <a href="https://www.adsplanroom.net">https://www.adsplanroom.net</a>. NOTE: Prime contractors will be allowed a maximum of two bid sets at the deposit rate shown above. Other requesters will be allowed only one bid set at this rate. Additional bid sets or parts thereof may be obtained by any bidder at the cost of printing and shipping by request to American Document Solutions at the address shown above. Bidder must secure at least one bid set to become a planholder.
- B. Refunds: Return plans and specifications in unmarked condition within 15 working days of bid opening to American Document Solutions, 1400 Forum Blvd., Suite 7A, Columbia, Missouri 65203. Phone 573-446-7768, Fax 573-355-5433. Deposits for plans not returned within 15 working days shall be forfeited.
- C. Information for upcoming bids, including downloadable plans, specifications, Invitation for Bid, bid tabulation, award, addenda, and access to the ADS planholders list, is available on the Division of Facilities Management, Design and Construction's web site: <a href="https://oa.mo.gov/facilities/bid-opportunities/bid-listing-electronic-plans">https://oa.mo.gov/facilities/bid-opportunities/bid-listing-electronic-plans</a>.

#### 7.0 POINT OF CONTACT:

- A. Designer: OA-FMDC Project Design Unit, Brad M. Schaefer, 573-526-0136, email: Brad.Schaefer@oa.mo.gov
- B. Project Manager: Andy Carroll, 573-751-8913, email: Andy.Carroll@oa.mo.gov

# 8.0 GENERAL INFORMATION:

- A. The State reserves the right to reject any and all bids and to waive all informalities in bids. No bid may be withdrawn for a period of 20 working days subsequent to the specified bid opening time. The contractor shall pay not less than the prevailing hourly rate of wages for work of a similar character in the locality in which the work is performed, as determined by the Missouri Department of Labor and Industrial Relations and as set out in the detailed plans and specifications.
- B. Bid results will be available at <a href="https://oa.mo.gov/facilities/bid-opportunities/bid-listing-electronic-plans">https://oa.mo.gov/facilities/bid-opportunities/bid-listing-electronic-plans</a> after it is verified that at least one bid is awardable and affordable.

#### **SECTION 002113 - INSTRUCTIONS TO BIDDERS**

#### 1.0 - SPECIAL NOTICE TO BIDDERS

- A. If awarded a contract, the Bidder's employees, and the employees of all subcontractors, who perform the work on the project must adhere to requirements in Section 013513 Site Security and Health Requirements as applicable per Agency.
- B. The Bidder's prices shall include all city, state, and federal sales, excise, and similar taxes that may lawfully be assessed in connection with the performance of work, and the purchased of materials to be incorporated in the work. **THIS PROJECT IS NOT TAX EXEMPT.**

## 2.0 - BID DOCUMENTS

- A. The number of sets obtainable by one (1) party may be limited in accordance with available supply.
- B. For the convenience of contractors, subcontractors and suppliers, bidding documents are available on the Owner's website at <a href="https://oa.mo.gov/facilities/bid-opportunities/bid-listing-electronic-plans">https://oa.mo.gov/facilities/bid-opportunities/bid-listing-electronic-plans</a>.

#### 3.0 - BIDDERS' OBLIGATIONS

- A. Bidders must carefully examine the entire site of the work and shall make all reasonable and necessary investigations to inform themselves thoroughly as to the facilities available as well as to all the difficulties involved in the completion of all work in accordance with the specifications and the plans. Bidders are required to examine all maps, plans and data mentioned in the specifications. No plea of ignorance concerning observable existing conditions or difficulties that may be encountered in the execution of the work under this contract will be accepted as an excuse for any failure or omission on the part of the successful Bidder (contractor) to fulfill every detail of the requirements of the contract, nor accepted as a basis for any claims for extra compensation or time extension.
- B. Under no circumstances will Bidders give their plans and specifications to other Bidders. It is highly encouraged, but not required, that all Bidders be on the official planholders list to receive project updates including but not limited to any addenda that are issued during the bidding process.

#### 4.0 - INTERPRETATIONS

- A. No Bidder shall be entitled to rely on oral or written representations from any person as to the meaning of the plans and specifications or the acceptability of alternate products, materials, form or type of construction.
- B. Bidders shall make all requests for interpretations in writing and submit all requests to the Project Designer and Project Manager identified in Section 007300 Supplementary Conditions with all necessary supporting documentation no less than five (5) working days before opening of bids. Responses to requests for interpretation will be issued via a written addendum and will be sent as promptly as is practicable to all official planholders and posted on the Owner's website. All such addenda shall become part of the bid and contract documents.
- C. Bidders shall make all requests for an "Acceptable Substitution" on the Section 006325 Substitution Request Form. The request shall be emailed to the Project Designer and Project Manager identified in Section 007300 Supplementary Conditions no less than five (5) working days before opening of bids. Responses to requests for substitutions will be issued via a written addendum and will be sent as promptly as is practicable to all official planholders and posted on the Owner's website. All such addenda shall become part of the bid and contract documents.
- D. An "Acceptable Substitution" requested after the award of bid will only be approved if proven to the satisfaction of the Owner and the Designer that the product is acceptable in design, strength, durability, usefulness, and convenience for the purpose intended. Approval of the substitution after award is at the sole discretion of the Owner and all requests of this nature must be submitted in accordance with Article 3.1 of the General Conditions.

#### 5.0 - BIDS AND BIDDING PROCEDURE

- A. Bidders shall submit all submission forms and accompanying documents listed in Section 004113 Bid Form, Article 5.0, Attachments to Bid by the stated time on the bid documents or the bid will be rejected for being non-responsive.
- B. Depending on the specific project requirements, **the following is a GENERIC list** of all possible bid forms that may be due with bid submittals. Bidders must verify each specific project's requirements in Section 004113 to ensure they have provided all the required documentation with their submission.

Bid Submittal -	due before stated date and time of bid opening (see IFB):
004113	Bid Form (all pages are always required)
004322	Unit Prices Form
004336	Proposed Subcontractors Form
004337	MBE/WBE/SDVE Compliance Evaluation Form
004338	MBE/WBE/SDVE Eligibility Determination for Joint Ventures
004339	MBE/WBE/SDVE GFE Determination
004340	SDVE Business Form
004541	Affidavit of Work Authorization
004545	Anti-Discrimination Against Israel Act Certification form

- C. The Bidder shall submit its bid on the forms provided by the Owner in the same file format (PDF) with each space fully and properly completed, typewritten or legibly printed, including all amounts required for alternate bids, unit prices, cost accounting data, etc. The Owner will reject bids that are not on the Owner's forms or that do not contain all requested information. All forms can be found on the Owner's website at <a href="https://oa.mo.gov/facilities/bid-opportunities/bid-listing-electronic-plans">https://oa.mo.gov/facilities/bid-opportunities/bid-listing-electronic-plans</a> and shall be submitted with your bid to <a href="mailto:FMDCBids@oa.mo.gov">FMDCBids@oa.mo.gov</a>.
- D. All bids shall be submitted without additional terms and conditions, modifications, or reservations. The completed forms should not include interlineations, alterations, or erasures. Bids not in compliance with the requirements of this paragraph will be rejected as non-responsive.
- E. All bids shall be accompanied by a bid bond executed by the bidder and a duly authorized surety company, certified check, cashier's check or bank draft made payable to the Division of Facilities Management, Design and Construction, State of Missouri, in the amount indicated in the bid documents in Section 004113. Failure of the Bidder to submit the duly authorized bid bond or the full amount required shall be sufficient cause to reject his bid. The Bidder agrees that the proceeds of the check, draft, or bond shall become the property of the State of Missouri, if for any reason the Bidder withdraws his bid after bid closing or if the Bidder, within ten (10) working days after notification of award, refuses or is unable to 1) execute the tendered contract, 2) provide an acceptable performance and payment bond, or 3) provide evidence of required insurance coverage.
- F. The bid bond check or draft submitted by the successful Bidder will be returned after the receipt of an acceptable performance and payment bond and execution of the formal contract. Checks or drafts of all other Bidders will be returned within a reasonable time after it is determined that the bid represented by same will receive no further consideration by the State of Missouri.

# **6.0 - SIGNING OF BIDS**

- A. A bid should contain the full and correct legal name of the Bidder. If the Bidder is an entity registered with the Missouri Secretary of State, the Bidder's name on the bid form should appear as shown in the Secretary of State's records. If the Bidder is an entity organized in a state other than Missouri, the Bidder must provide a Certificate of Authority to do business in the State of Missouri.
- B. If the successful Bidder is doing business in the State of Missouri under a fictitious name, the Bidder shall furnish to Owner, attached to the Bid Form, a properly certified copy of the certificate of Registration of Fictitious Name from the State of Missouri, and such certificate shall remain on file with the Owner.
- C. A bid from an individual shall be signed as noted on the Bid Form.
- D. A bid from a partnership or joint venture shall require only one signature of a partner, an officer of the joint venture authorized to bind the venture, or an attorney-in-fact. If the bid is signed by an officer of

- a joint venture or an attorney-in-fact, a document evidencing the individual's authority to execute contracts should be included with the bid form.
- E. A bid from a limited liability company (LLC) shall be signed by a manager or a managing member of the LLC.
- F. A bid from a corporation shall have the correct corporate name thereon and the signature of an authorized officer of the corporation. Title of office held by the person signing for the corporation shall appear, along with typed name of said individual and the corporate license number shall be provided. In addition, for corporate proposals, the President or Vice-President listed per the current filing with the Missouri Secretary of State should sign as the Bidder. If the signatory is other than the corporate president or vice president, the bidder must provide satisfactory evidence that the signatory has the legal authority to bind the corporation.

#### 7.0 - RECEIVING BID SUBMITTALS

- A. It is the Bidder's sole responsibility to ensure receipt of the bid submittals by Owner on or before the date and time specified in the Invitation for Bid or as modified via written addenda. Bids received after the date and time specified will not be considered by the Owner.
- B. All bids shall be received via email at <a href="mailto:FMDCBids@oa.mo.gov">FMDCBids@oa.mo.gov</a> and bids received by the Owner through any other means, including hard copies, will not be considered, and will be discarded by the Owner unopened.

#### 8.0 - MODIFICATION AND WITHDRAWAL OF BIDS

- A. Bidder may withdraw a bid at any time prior to the scheduled closing time for receipt of bids, but no bidder may withdraw his bid for a period of twenty (20) working days after the scheduled closing time for receipt of bids.
- B. Bidder may modify a bid until the scheduled closing time by sending a revised bid to <a href="mailto:FMDCBids@oa.mo.gov">FMDCBids@oa.mo.gov</a> with a note in the subject line and body of the email that it is a revised bid. All revised bids must be submitted to <a href="mailto:FMDCBids@oa.mo.gov">FMDCBids@oa.mo.gov</a>, revised bids sent any other way will not be considered.

## 9.0 - AWARD OF CONTRACT

- A. The Owner reserves the right to reject any and/or all bids and further to waive all informalities in bidding when deemed in the best interest of the State of Missouri.
- B. The Owner reserves the right to let other contracts in connection with the work including, but not limited to, contracts for the furnishing and installation of furniture, equipment, machinery, appliances and other apparatuses.
- C. The Owner will award a contract to the lowest, responsive, and responsible Bidder in accordance with Section 8.250, RSMo. No contract will be awarded to any Bidder who has had a contract with the Owner terminated within the preceding twelve months for material breach of contract or who has been suspended or debarred by the Owner.
- D. Award of alternates, if any, will be made in numerical order unless all bids received are such that the order of acceptance of alternates does not affect the determination of the lowest, responsive, responsible bidder.
- E. No award shall be considered binding upon the Owner until the written contract has been properly executed and the following documentation has been provided: 1) performance and payment bond consistent with Article 6.1 of the General Conditions; 2) proof of the required insurance coverage; 3) an executed Section 004541 Affidavit of Work Authorization form; and 4) documentation evidence enrollment and participation in a federal work authorization program.
- F. Failure to execute and return the contract and associated documents within the prescribed period shall be treated, at the option of the Owner, as a breach of Bidder's obligation and the Owner shall be under no further obligation to Bidder.
- G. Transient employers subject to Sections 285.230 and 285.234, RSMo, (out-of-state employers who temporarily transact any business in the State of Missouri) may be required to file a bond with the

- Missouri Department of Revenue. No contract will be awarded by the Owner unless the successful Bidder certifies that he has complied with all applicable provisions of Section 285.230-234.
- H. Sections 285.525 and 285.530, RSMo, require business entities to enroll and participate in a federal work authorization program in order to be eligible to receive award of any state contract in excess of \$5,000. Bidders should submit with their bid an Affidavit of Work Authorization (Section 004541) along with appropriate documentation evidencing such enrollment and participation. Bidders must also submit an E-Verify Memorandum before the Owner may award a contract to the Bidder. Information regarding a E-Verify is located at <a href="https://www.uscis.gov/e-verify/">https://www.uscis.gov/e-verify/</a>. The contractor shall be responsible for ensuring that all subcontractors and suppliers associated with this contract enroll in E-Verify.
- The successful Bidder must be registered in MissouriBUYS powered by MOVERS at <u>https://missouribuys.mo.gov/supplier-registration#</u> as an approved vendor prior to being issued a contract.

#### 10.0 - CONTRACT SECURITY

A. The successful Bidder shall furnish a performance/payment bond as set forth in General Conditions Article 6.1 prior to the State executing the contract and issuing a notice to proceed.

#### 11.0 - LIST OF SUBCONTRACTORS

A. If required by "Section 004113 – Bid Form," each Bidder must submit as part of their bid a list of subcontractors to be used in performing the work (Section 004336). The list must specify the name of the single designated subcontractor, manufacturer, or suppliers for each category of work listed in "Section 004336 - Proposed Subcontractors Form." If work within a category will be performed by more than one subcontractor, the bidder must provide the name of each subcontractor and specify the exact portion of the work to be done by each. If the Bidder intends to perform any of the designated subcontract work with the use of his own employees, the Bidder shall make that fact clear, by listing his own firm for the subject category. If any category of work is left vacant or if more than one subcontractor is listed for any category without designating the portion of work to be performed by each, the bid shall be rejected.

#### 12.0 - WORKING DAYS

- A. Contract duration time is stated in working days and will use the following definition in determining the actual calendar date for contract completion:
  - 1. Working days are defined as all calendar days except Saturdays, Sundays and the following State of Missouri observed holidays: New Year's Day, Martin Luther King, Jr. Day, Lincoln Day, Washington's Birthday, Truman Day, Memorial Day, Juneteenth, Independence Day, Labor Day, Columbus Day, Veterans Day, Thanksgiving Day and Christmas Day.

# 13.0 - AMERICAN AND MISSOURI - MADE PRODUCTS AND FIRMS

- A. By signing the bid form and submitting a bid on this project, the Bidder certifies that it will use American and Missouri products as set forth in Article 1.7 of the General Conditions. Bidders are advised to review those requirements carefully prior to bidding.
- B. A preference shall be given to Missouri firms, corporations or individuals, or firms, corporations or individuals that maintain Missouri offices or places of business, when the quality of performance promised is equal or better and the price quoted is the same or less.
- C. Pursuant to Section 34.076, RSMo, a contractor or Bidder domiciled outside the boundaries of the State of Missouri shall be required, in order to be successful, to submit a bid the same percent less than the lowest bid submitted by a responsible contractor or Bidder domiciled in Missouri as would be required for such a Missouri domiciled contractor or Bidder to succeed over the bidding contractor or Bidder domiciled outside Missouri on a like contract or bid being let in the Bidder's domiciliary state and, further, the contractor or Bidder domiciled outside the boundaries of Missouri shall be required to submit an audited financial statement as would be required of a Missouri domiciled contractor or Bidder on a like contract or bid being let in the domiciliary state of that contractor or Bidder.

# 14.0 - ANTI-DISCRIMINATION AGAINST ISRAEL ACT CERTIFICATION:

A. If the Bidder meets the section 34.600, RSMo., definition of a "company" and the Bidder has ten or more employees, the Bidder must certify in writing that the Bidder is not currently engaged in a boycott of goods or services from the State of Israel and shall not engage in a boycott of goods or services from the State of Israel, if awarded a contract, for the duration of the contract. The Bidder is required to complete and submit the applicable portion of Section 004545 - Anti-Discrimination Against Israel Act Certification with its Bid Form. The applicable portion of the exhibit must be submitted prior to execution of a contract by the Owner and issuance of Notice to Proceed.

# 15.0 - MBE/WBE/SDVE INSTRUCTIONS

- A. Definitions:
  - 1. "MBE" means a Minority Business Enterprise.
  - 2. "MINORITY" has the same meaning as set forth in 1 C.S.R. 10-17.010.
  - 3. "MINORITY BUSINESS ENTERPRISE" has the same meaning as set forth in section 37.020, RSMo.
  - 4. "WBE" means a Women's Business Enterprise.
  - 5. "WOMEN'S BUSINESS ENTERPRISE" has the same meaning as set forth in section 37.020, RSMo.
  - 6. "SDVE" means a Service-Disabled Veterans Enterprise.
  - 7. "SERVICE-DISABLED VETERAN" has the same meaning as set forth in section 34.074, RSMo.
  - 8. "SERVICE-DISABLED VETERAN ENTERPRISE" has the same meaning as "Service-Disabled Veteran Business" set forth in section 34.074, RSMo.
- B. MBE/WBE/SDVE General Requirements:
  - 1. For all bids greater than \$100,000, the Bidder shall obtain MBE, WBE and SDVE participation in an amount equal to or greater than the percentage goals set forth in the Invitation for Bid and the Bid Form, unless the Bidder is granted a Good Faith Effort waiver by the Director of the Division, as set forth below. If the Bidder does not meet the MBE, WBE and SDVE goals, or make a good faith effort to do so, the Bidder shall be nonresponsive, and its bid shall be rejected.
  - 2. The Bidder should submit with its bid all the information requested in the MBE/WBE/SDVE Compliance Evaluation Form for every MBE, WBE, or SDVE subcontractor or material supplier the Bidder intends to use for the contract work. The Bidder is required to submit all MBE/WBE/SDVE documentation before the stated time and date set forth in the Invitation for Bid. If the Bidder fails to provide such information by the specified date and time, the Owner shall reject the bid.
  - 3. The Director reserves the right to request additional information from a Bidder to clarify the Bidder's proposed MBE, WBE, and/or SDVE participation. The Bidder shall submit the clarifying information requested by the Owner within two (2) working days of receiving the request for clarification.
  - 4. Pursuant to section 34.074, RSMo, a Prime Bidder that qualifies as an SDVE shall receive a three-percentage point bonus preference in the contract award evaluation process. The bonus preference will be calculated and applied by reducing the bid amount of the eligible SDVE by three percent of the apparent low responsive Bidder's bid. Based on this calculation, if the eligible SDVE's evaluation is less than the apparent low responsive Bidder's bid, the eligible SDVE's bid will become the apparent low responsive bid. This reduction is for evaluation purposes only and will have no impact on the actual amount(s) of the bid or the amount(s) of any contract awarded. In order to be eligible for the SDVE preference, the Bidder must complete and submit with its bid the Missouri Service-Disabled Veteran Business Form, and any information required by the form.
- C. Computation of MBE/WBE/SDVE Goal Participation:
  - 1. A Bidder who is a MBE, WBE, or SDVE may count 100% of the contract towards the MBE, WBE or SDVE goal, less any amounts awarded to another MBE, WBE or SDVE. (NOTE: a MBE firm that bids as general contractor must obtain WBE and SDVE participation; a WBE firm that bids as a general contractor must obtain MBE and SDVE participation; and a SDVE firm that bids as general

- contractor must obtain MBE and WBE participation.) For the remaining contract amount to be counted towards the MBE, WBE or SDVE goal, the Bidder must complete the MBE/WBE/SDVE Compliance Evaluation Form (Section 004337) identifying itself as an MBE, WBE or SDVE.
- 2. The total dollar value of the work granted to a certified MBE, WBE or SDVE by the Bidder shall be counted towards the applicable goal.
- 3. Expenditures for materials and supplies obtained from a certified MBE, WBE, or SDVE supplier or manufacturer may be counted towards the MBE, WBE and SDVE goals, if the MBE, WBE, or SDVE assumes the actual and contractual responsibility for the provision of the materials and supplies.
- 4. The total dollar value of the work granted to a second or subsequent tier subcontractor or a supplier may be counted towards a Bidder's MBE, WBE and SDVE goals, if the MBE, WBE, or SDVE properly assumes the actual and contractual responsibility for the work.
- 5. The total dollar value of work granted to a certified joint venture equal to the percentage of the ownership and control of the MBE, WBE, or SDVE partner in the joint venture may be counted towards the MBE/WBE/SDVE goals.
- 6. Only expenditures to a MBE, WBE, or SDVE that performs a commercially useful function in the work may be counted towards the MBE, WBE and SDVE goals. A MBE, WBE, or SDVE performs a commercially useful function when it is responsible for executing a distinct element of the work and carrying out its responsibilities by performing, managing and supervising the work or providing supplies or manufactured materials.

#### D. Certification of MBE/WBE/SDVE Subcontractors:

- 1. In order to be counted towards the goals, an MBE or WBE must be certified by the State of Missouri Office of Equal Opportunity and an SDVE must be certified by the State of Missouri, Office of Equal Opportunity or by the Federal U.S. Small Business Administration directory.
- 2. The Bidder may determine the certification status of a proposed MBE or WBE subcontractor or supplier by referring to the Office of Equal Opportunity (OEO)'s online MBE/WBE directory <a href="https://apps1.mo.gov/MWBCertifiedFirms/">https://apps1.mo.gov/MWBCertifiedFirms/</a>. The Bidder may determine the eligibility of a SDVE subcontractor or supplier by referring to the Office of Equal Opportunity online SDVE directory at <a href="https://oeo.mo.gov/sdve-certification-program/">https://oeo.mo.gov/sdve-certification-program/</a> or the Federal U.S. Small Business Administration directory <a href="https://veterans.certify.sba.gov/#search">https://veterans.certify.sba.gov/#search</a>.
- 3. Additional information, clarifications, or other information regarding the MBE/WBE/SDVE listings in the directories may be obtained by contacting the Contract Specialist of record as shown in the Supplementary Conditions (Section 007300).

# E. Waiver of MBE/WBE/SDVE Participation:

- 1. If a Bidder has made a good faith effort to secure the required MBE, WBE and/or SDVE participation and has failed, the Bidder shall submit with its bid the information requested in MBE/WBE/SDVE Good Faith Effort (GFE) Determination form. The Director will determine if the Bidder made a good faith effort to meet the applicable goals. If the Director determines that the Bidder did not make a good faith effort, the bid shall be rejected as being nonresponsive to the bid requirements. Bidders who demonstrate that they have made a good faith effort to include MBE, WBE, and/or SDVE participation will be granted a waiver and will be considered to be responsive to the applicable participation goals, regardless of the percent of actual participation obtained, if the bid is otherwise acceptable.
- 2. In determining whether a Bidder has made a good faith effort to obtain MBE, WBE and/or SDVE participation, the Director may evaluate the factors set forth in 1 CSR 30-5.010(6)(C) and the following:
  - a. The amount of actual participation obtained;

- b. How and when the Bidder contacted potential MBE, WBE, and SDVE subcontractors and suppliers;
- The documentation provided by the Bidder to support its contacts, including whether the Bidder provided the names, addresses, phone numbers, and dates of contact for MBE/WBE/SDVE firms contacted for specific categories of work;
- d. If project information, including plans and specifications, were provided to MBE/WBE/SDVE subcontractors;
- e. Whether the Bidder made any attempts to follow-up with MBE, WBE or SDVE firms prior to bid;
- f. Amount of bids received from any of the subcontractors and/or suppliers that the Bidder contacted:
- g. The Bidder's stated reasons for rejecting any bids;

# F. Contractor MBE/WBE/SDVE Obligations

- 1. If awarded a contract, the Bidder will be contractually required to subcontract with or obtain materials from the MBE, WBE, and SDVE firms listed in its bid, in amounts equal to or greater than the dollar amount in the bid, unless the amount is modified in writing by the Owner.
- 2. If the Contractor fails to meet or maintain the participation requirements contained in the Contractor's bid, the Contractor must satisfactorily explain to the Director why it cannot comply with the requirement and why failing meeting the requirement was beyond the Contractor's control. If the Director finds the Contractor's explanation unsatisfactory, the Director may take any appropriate action including, but not limited to:
  - a. Declaring the Contractor ineligible to participate in any contracts with the Division for up to twelve (12) months (suspension); and/or
  - b. Declaring the Contractor be nonresponsive to the Invitation for Bid, or in breach of contract and rejecting the bid or terminating the contract.
- 3. If the Contractor replaces an MBE, WBE, or SDVE during the course of the contract, the Contractor shall replace it with another MBE, WBE, or SDVE or make a good faith effort to do so. All MBE, WBE and SDVE substitutions must be approved by the Director in writing.
- 4. The Contractor shall provide the Owner with regular reports on its progress in meeting its MBE/WBE/SDVE obligations. At a minimum, the Contractor shall report the dollar-value of work completed by each MBE, WBE, or SDVE during the preceding month and the cumulative total of work completed by each MBE, WBE or SDVE to date with each monthly application for payment. The Contractor shall also make a final report, which shall include the total dollar-value of work completed by each MBE, WBE, and SDVE during the entire contract.



# State of Missouri **Construction Contract**

**THIS AGREEMENT** is made (DATE) by and between:

#### Contractor Name and Address

hereinafter called the "Contractor," and the State of Missouri, hereinafter called the "Owner", represented by the Office of Administration, Division of Facilities Management, Design and Construction.

WITNESSETH, that the Contractor and the Owner, for the consideration stated herein agree as follows:

#### ARTICLE 1. STATEMENT OF WORK

The Contractor shall furnish all labor and materials and perform all work required for furnishing and installing all labor, materials, equipment and transportation and everything necessarily inferred from the general nature and tendency of the plans and specifications for the proper execution of the work for:

**Project Name:** Renovate Lobby and Restroom 1st and 2nd Floor

> **Howerton State Office Building** Jefferson City, Missouri

**Project Number:** O2339-01

in strict accordance with the Contract Documents as enumerated in Article 7, all of which are made a part hereof.

# ARTICLE 2. TIME OF COMPLETION

The contract performance time is 120 working days from the transmittal date of this agreement. The contract completion date is MONTH, DAY, YEAR. This time includes ten (10) working days for the Contractor to receive, sign and return the contract form along with required bonding and insurance certificates. Failure of the Contractor to provide correct bonding and insurance within the ten (10) working days shall not be grounds for a time extension. Receipt of proper bonding and insurance is a condition precedent to the formation of the contract and if not timely received, may result in forfeiture of the Contractor's bid security. Work may not commence until the Owner issues a written Notice to Proceed and must commence within seven (7) working days thereafter.

#### ARTICLE 3. LIQUIDATED DAMAGES

Whenever time is mentioned in this contract, time shall be and is of the essence of this contract. The Owner would suffer a loss should the Contractor fail to have the work embraced in this contract fully completed on or before the time above specified. THEREFORE, the parties hereto realize in order to adjust satisfactorily the damages on account of such failure that it might be impossible to compute accurately or estimate the amount of such loss or damages which the Owner would sustain by reason of failure to complete fully said work within the time required by this contract. The Contractor hereby covenants and agrees to pay the Owner, as and for liquidated damages, the sum of \$1,000 per day for each and every day, Sunday and legal holidays excepted, during which the work remains incomplete and unfinished. Any sum which may be due the Owner for such damages shall be deducted and retained by the Owner from any balance which may be due the Contractor when said work shall have been finished and accepted. But such provisions shall not release the Bond of the Contractor from liability according to its terms. In case of failure to complete, the Owner will be under no obligation to show or prove any actual or specific loss or damage.

#### ARTICLE 4. CONTRACT SUM

The Owner shall pay the Contractor for the prompt, faithful and efficient performance of the conditions and undertakings of this contract, subject to additions, and deductions as provided herein, in current funds the sum of:

ase Bid:

Accepted Alternates, if applicable to the Project and accepted by the Owner.

# TOTAL CONTRACT AMOUNT: (\$CONTRACT AMOUNT)

**UNIT PRICES:** The Owner accepts the following Unit Prices:

For changing specified quantities of work from those indicated by the contract drawings and specifications, upon written instructions of Owner, the following unit prices shall prevail. The unit prices include all labor, overhead and profit, materials, equipment, appliances, bailing, shoring, shoring removal, etc., to cover the finished work of the several kinds of work called for. Only a single unit price shall be given and it shall apply for either MORE or LESS work than that shown on the drawings and called for in the specifications or included in the Base Bid. In the event of more or less units than so indicated or included, change orders may be issued for the increased or decreased amount.

#### ARTICLE 5. PREVAILING WAGE RATE

MISSOURI PREVAILING WAGE LAW (Sections 290.210 to 290.340, RSMo): The Contractor shall pay not less than the specified hourly rate of wages, as set out in the wage order attached to and made part of the specifications for work under this contract, to all workers performing work under the contract, in accordance with sections 290.210 to 290.340, RSMo. The Contractor shall forfeit a penalty to the Owner of one hundred dollars per day (or portion of a day) for each worker that is paid less than the specified rates for any work done under the contract by the Contractor or by any subcontractor, in accordance with section 290.250, RSMo.

**DAVIS-BACON ACT:** If this Project is financed in whole or in part from Federal funds (as indicated in the Instructions to Bidders or other bid or contract documents for this Project), then this contract shall be subject to all applicable federal labor statutes, rules and regulations, including provisions of the Davis-Bacon Act, 40 U.S.C. §3141 et seq., and the "Federal Labor Standards Provisions," as further set forth in Section 007333 – Supplementary General Conditions for Federally Funded/Assisted Construction Projects, which is incorporated into the contract by reference. Where the Missouri Prevailing Wage Law and the Davis-Bacon Act require payment of different wages for work performed under this contract, the Contractor and all Subcontractors shall pay the greater of the wages required under either law, on a classification-by-classification basis.

# ARTICLE 6. MINORITY/WOMEN/SERVICE DISABLED VETERAN BUSINESS ENTERPRISE PARTICIPATION

The Contractor has been granted a waiver of the 10% MBE and 10% WBE and 3% SDVE participation goals. The Contractor agrees to secure the MBE/WBE/SDVE participation amounts for this project as follows: (OR)

The Contractor has met the MBE/WBE/SDVE participation goals and agrees to secure the MBE/WBE/SDVE participation amounts for this project as follows:

MBE/WBE/SDVE Firm: Subcontract Amt:\$
MBE/WBE/SDVE Firm: Subcontract Amt:\$
MBE/WBE/SDVE Firm: Subcontract Amt:\$

Total \$

MBE/WBE/SDVE assignments identified above shall not be changed without a contract change signed by the Owner.

The Director of the Division of Facilities Management, Design and Construction or his Designee shall be the final authority to resolve disputes and disagreements between the Contractor and the MBE/WBE/SDVE firms listed above when such disputes impact the subcontract amounts shown above.

## ARTICLE 7. CONTRACT DOCUMENTS

The following documents are hereby incorporated into this contract by reference (all division/section numbers and titles are as utilized in the Project Manual published by the Owner for this Project):

- 1. Division 0 Procurement and Contracting Information, including, but not limited to:
  - a. Invitation for Bid (Section 001116)
  - b. Instructions to Bidders (Section 002113)
  - c. Supplementary Instructions to Bidders (if applicable) (Section 002213)
  - d. The following documents as completed and executed by the Contractor and accepted by the Owner, if applicable:
    - i. Bid Form (Section 004113)
    - ii. Unit Prices (Section 004322)
    - iii. Proposed Contractors Form (Section 004336)
    - iv. MBE, WBE, SDVE Compliance Evaluation Form(s) (Section 004337)
    - v. MBE, WBE, SDVE Eligibility Determination Form for Joint Ventures (Section 004338)
    - vi. MBE, WBE, SDVE Good Faith Effort (GFE) Determination Form (Section 004339)
    - vii. Missouri Service Disabled Veteran Business Form (Section 004340)
    - viii. Affidavit of Work Authorization (Section 004541)
    - ix. Affidavit for Affirmative Action (Section 005414), if applicable
  - e. Performance and Payment Bond, completed and executed by the Contractor and surety (Section 006113)
  - f. General Conditions (Section 007213)
  - g. Supplementary Conditions (Section 007300)
  - h. Supplementary General Conditions for Federally Funded/Assisted Construction Projects (Section 007333), if applicable
  - i. Wage Rate(s) (Section 007346)
- 2. Division 1 General Requirements
- 3. All Drawings identified in the Project Manual
- 4. All Technical Specifications included in the Project Manual
- 5. Addenda, if applicable

#### ARTICLE 8 – CERTIFICATION

By signing this contract, the Contractor hereby re-certifies compliance with all legal requirements set forth in Section 6.0, Bidder's Certifications of the Bid Form.

By signature below, the parties hereby execute this contract document.

APPROVED:

Brian Yansen, Director
Division of Facilities Management,
Design and Construction

I, Corporate Secretary, certify that I am Secretary of the corporation named above and that (CONTRACTOR NAME), who signed said contract on behalf of the corporation, was then (TITLE) of said corporation and that said contract was duly signed for and in behalf of the corporation by authority of its governing body, and is within the scope of its corporate powers.

Bond No.	
----------	--

# SECTION 006113 - PERFORMANCE AND PAYMENT BOND FORM

KNOW ALL MEN BY THESE	PRESENTS, THAT we		
as principal, and			
		as Surety, are held and firmly	bound unto the
STATE OF MISSOURI. in the	sum of	Dollars (\$	)
for payment whereof the Princip	oal and Surety bind themselves, th	eir heirs, executors, administrators and s	uccessors, jointly
and severally, firmly by these pr	resents.		
WHEREAS, the Principal has, b	y means of a written agreement d	lated the	
day of	, 20	, enter into a contract with the State	of Missouri for
	·		
	(Insert Project	Title and Number)	

NOW, THEREFORE, if the Principal shall faithfully perform and fulfill all the undertakings, covenants, terms, conditions and agreements of said contract during the original term of said contract and any extensions thereof that may be granted by the State of Missouri, with or without notice to the Surety and during the life of any guaranty required under the contract; and shall also faithfully perform and fulfill all undertakings, covenants, terms, conditions and agreements of any and all duly authorized modifications of said contract that may hereafter be made with or without notice to the Surety; and shall also promptly make payment for materials incorporated, consumed or used in connection with the work set forth in the contract referred to above, and all insurance premiums, both compensation and all other kinds of insurance, on said work, and for all labor performed on such work, whether by subcontractor or otherwise, at not less than the prevailing hourly rate of wages for work of a similar character (exclusive of maintenance work) in the locality in which the work is performed and not less than the prevailing hourly rate of wages for legal holiday and overtime work (exclusive of maintenance work) in the locality in which the work is performed both as determined by the Department of Labor and Industrial Relations or determined by the Court of Appeal, as provided for in said contract and in any and all duly authorized modifications of said contract that may be hereafter made, with or without notice to the Surety, then, this obligation shall be void and of no effect, but it is expressly understood that if the Principal should make default in or should fail to strictly, faithfully and efficiently do, perform and comply with any or more of the covenants, agreements, stipulations, conditions, requirements or undertakings, as specified in or by the terms of said contract, and with the time therein named, then this obligation shall be valid and binding upon each of the parties hereto and this bond shall remain in full force and effect; and the same may be sued on at the instance of any material man, laborer, mechanic, subcontractor, individual, or otherwise to whom such payment is due, in the name of the State of Missouri, to the use of any such person.

forbearance on the part of either the Owner or the Principal to the other, shall not in any way release the Principal and the Surety, or either or any of them, their heirs, executors, administrators and successors, from their liability hereunder, notice to the Surety of any such extension, modifications or forbearance being hereby waived. IN WITNESS WHEREOF, the above bounden parties have executed the within instrument this \_\_\_\_\_\_ day of \_\_\_\_\_, 20 \_\_\_\_. **AS APPLICABLE:** AN INDIVIDUAL Name: Signature: A PARTNERSHIP Name of Partner: Signature of Partner: Name of Partner: Signature of Partner: **CORPORATION** Firm Name: Signature of President: **SURETY** Surety Name: Attorney-in-Fact: Address of Attorney-in-Fact: Telephone Number of Attorney-in-Fact: Signature Attorney-in-Fact:

AND, IT IS FURTHER specifically provided that any modifications which may hereinafter be made in the terms of the contract or in the work to be done under it or the giving by the Owner of any extension of the time for the performance of the contract or any other

**NOTE**: Surety shall attach Power of Attorney



# STATE OF MISSOURI OFFICE OF ADMINISTRATION DIVISION OF FACILITIES MANAGEMENT, DESIGN AND CONSTRUCTION

PRODUCT SUBSTIT	TUTION REQUEST		
PROJECT TITLE AND LOCATION			
CHECK APPROPRIATE BOX			
SUBSTITUTION PRIOR TO BID OPENING (Minimum of (5) working days prior to receipt of Bids as per Article 4 – Instructions to Bidders)			
☐ SUBSTITUTION FOLLOWIN	SUBSTITUTION FOLLOWING AWARD  (Maximum of (20) working days from Notice to Proceed as per Article 3 – General Conditions)		
FROM: BIDDER/CONTRACTOR (PRINT COMPANY NAME)	The same of the sa	STATE OF THE PROPERTY OF THE P	
TO: ARCHITECT/ENGINEER (PRINT COMPANY NAME)			
Bidder/Contractor hereby requests a provisions of Division One of the Bidd	cceptance of the following product or syste ing Documents:	ms as a substitution in accordance with	
SPECIFIED PRODUCT OR SYSTEM			
SPECIFICATION SECTION NO.			
SUPPORTING DATA			
	tion is attached (include description of product, st ample will be sent, if requested	andards, performance, and test data)	
QUALITY COMPARISON	ample will be sent, if requested		
GOALITI GOMI ARIGOR	SPECIFIED PRODUCT	SUBSTITUTION REQUEST	
NAME, BRAND	3. 2025		
CATALOG NO.			
MANUFACTURER			
VENDOR			
PREVIOUS INSTALLATIONS	·		
PROJECT	ARCHITECT/ENGINEER		
LOCATION	<u> </u>	DATE INSTALLED	
SIGNIFICANT VARIATIONS FROM SPECIFIE	D PRODUCT		
		_	
-			

REASON FOR SUBSTITUTION		
DOES PROPOSED SUBSTITUTION AFFECT OTHER PARTS OF WORK?		
☐ YES ☐ NO		
IF YES, EXPLAIN		
SUBSTITUTION REQUIRES DIMENSIONAL REVISION OR REDESIGN OF STRUCTURE OR A/E WORK  YES NO		
	SUBSTITUTION TO CONTRACT	
BIDDER'S/CONTRACTOR'S STATEMENT OF CONFORMANCE OF PROPOSED SUBSTITUTION TO CONTRACT REQUIREMENT:		
We have investigated the proposed substitution. We believe that it is equal or superior in all respects to specified product, except as stated above; that it will provide the same Warranty as specified product; that we have included complete implications of the substitution; that we will pay redesign and other costs caused by the substitution which subsequently become apparent; and that we will pay costs to modify other parts of the Work as may be needed, to make all parts of the Work complete and functioning as a result of the substitution.		
BIDDER/CONTRACTOR	DATE	
REVIEW AND ACTION	1	
Resubmit Substitution Request with the following additional information:		
Substitution is accepted.		
Substitution is accepted with the following comments:		
Substitution is not accepted.		
ARCHITECT/ENGINEER	DATE	

PROJECT NUMBER

KNOW ALL MEN BY THESE PRESENT THAT: hereinafter called "Subcontractor" who heretofore entered into an agreement with hereinafter called "Contractor", for the performance of work and/or furnishing of material for the construction of the project entitled
(PROJECT TITLE, PROJECT LOCATION, AND PROJECT NUMBER)
at
(ADDRESS OF PROJECT)
for the State of Missouri (Owner) which said subcontract is by this reference incorporated herein, in consideration of such final payment by Contractor.
DOES HEREBY:
<ol> <li>ACKNOWLEDGE that they have been PAID IN FULL all sums due for work and materials contracted or done by their Subcontractors, Material Vendors, Equipment and Fixture Suppliers, Agents and Employees, or otherwise in the performance of the Work called for by the aforesaid Contract and all modifications or extras or additions thereto, for the construction of said project or otherwise.</li> <li>RELEASE and fully, finally, and forever discharge the Owner from any and all suits, actions, claims, and demands for payment for work performed or materials supplied by Subcontractor in accordance with the requirements of the above referenced Contract.</li> <li>REPRESENT that all of their Employees, Subcontractors, Material Vendors, Equipment and Fixture Suppliers, and everyone else has been paid in full all sums due them, or any of them, in connection with performance of said Work, or anything done or omitted by them, or any of them in connection with the construction of said improvements, or otherwise.</li> </ol>
NAME OF SUBCONTRACTOR
BY (TYPED OR PRINTED NAME)
SIGNATURE
TITLE

ORIGINAL: FILE/Closeout Documents



# STATE OF MISSOURI OFFICE OF ADMINISTRATION DIVISION OF FACILITIES MANAGEMENT, DESIGN AND CONSTRUCTION

		REPORT

PAY APP NO.	PROJECT NUMBER
CHECK IF FINAL	DATE

опоск арргорпало вох,				
			-	
UM (Same as Line Item 1. on F	Form A of Application for	TOTAL CONTRACT SU of Application for Paymo	JM TO DATE (Same a ent)	is Line Item 3. on Form A
/WBE/SDVE PARTICI RACT: <b>\$</b>	PATION DOLLAR AMO	OUNT OF THIS PE	ROJECT AS INI	DICATED IN THE
ORIGINAL CONTRACT PARTICIPATION AMOUNT	PARTICIPATION AMOUNT PAID-TO-DATE (includes approved contract changes)	CONTRACTOR	SUBCONTRA	CTOR/SUPPLIER
\$	\$			
\$	\$			
\$	\$			
\$	\$			
\$	\$			
\$	\$			
	WBE/SDVE PARTICIRACT: \$  ORIGINAL CONTRACT PARTICIPATION AMOUNT  \$  \$  \$	UM (Same as Line Item 1. on Form A of Application for  WBE/SDVE PARTICIPATION DOLLAR AMORACT: \$  ORIGINAL CONTRACT PARTICIPATION AMOUNT PAID-TO-DATE (includes approved contract changes)  \$ \$  \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	WBE/SDVE PARTICIPATION DOLLAR AMOUNT OF THIS PERACT: \$  ORIGINAL CONTRACT PARTICIPATION AMOUNT PAID-TO-DATE (includes approved contract changes)  \$  \$  \$  \$  \$  \$  \$  \$  \$  \$  \$  \$  \$	UM (Same as Line Item 1. on Form A of Application for of Application for Payment)  WBE/SDVE PARTICIPATION DOLLAR AMOUNT OF THIS PROJECT AS INITRACT:  ORIGINAL CONTRACT PARTICIPATION AMOUNT PAID-TO-DATE (includes approved contract changes)  \$  \$  \$  \$  \$  \$  \$  \$  \$  \$  \$  \$  \$

Revised 06/2023

## **INSTRUCTIONS FOR MBE/WBE/SDVE PROGRESS REPORT**

#### CONTRACTOR OR CONSULTANT TO FILL OUT AND REMIT WITH EACH PAY APPLICATION:

The MBE/WBE/SDVE Progress Report for the project is issued with the contract comprising values reported in the consultant's Proposal or on the successful contractor's Section 004337 Compliance Evaluation Forms.

At Initial Pay Application fill in the following:

- 1. Pay App No. Start with 1.
- 2. Fill in the Project Number and Date.
- 3. Enter Project Title, Project Location, and Firm.
- 4. Fill in the "Original Contract Sum" and "Total Contract Sum To Date" (Reference applicable Line Items on Form A of Application for Payment).
- 5. Indicate the Total Participation Dollar Amount from the Original Contract.
- 6. Select MBE, WBE, or SDVE for each Consultant/Subconsultant or Contractor/Subcontractor/Supplier.
- 7. Enter the "Total Amount of Subcontract", "\$ Amount (Paid-To-Date)", and Company Name.

For all subsequent Pay Applications fill in the following:

- 1. Pay App No.
- 2. If Final Pay App, check box.
- 3. Fill in the Project Number and Date.
- 4. Enter Project Title, Project Location, and Firm
- 5. At each Pay App fill in the "Original Contract Sum" and "Total Contract Sum To Date" (reference applicable Line Items on Form A of Application for Payment).
- 6. Indicate the Total Participation Dollar Amount from the Original Contract.
- 7. Select MBE, WBE, or SDVE for each Consultant/Subconsultant or Contractor/Subcontractor/Supplier
- 8. Enter the "Total Amount of Subcontract", "\$ Amount (Paid-To-Date)", and Company Name.



# STATE OF MISSOURI OFFICE OF ADMINISTRATION DIVISION OF FACILITIES MANAGEMENT, DESIGN AND CONSTRUCTION AFFIDAVIT – COMPLIANCE WITH PREVAILING WAGE LAW

PROJECT NUMBER

State of	personally cam	e and appeared		
-		(NAME	<u> </u>	
	of t	he		
(a corporation) (a partner	rship) (a proprietorship) ar	(NAME OF THE COMP and after being duly sworn	rany) did depose and say that al	– Il provisions
and requirements set out	t in Chapter 290, Sections	290.210 through and inc	luding 290.340, Missouri R	Revised
Statutes, pertaining to the	e payment of wages to wo	orkmen employed on publ	ic works project have beer	n fully satisfied
and there has been no ex	xception to the full and co	mpleted compliance with	said provisions and require	ements
and with Wage Determin				
-			,	
Department of Labor and	d Industrial Relations, Stat	e of Missouri on the	day of	20 _
in carrying out the contra	act and working in connect	ion with		
		(NAME OF PROJECT)		
Located at		in		County
(NAME OF THE II	NSTITUTION)			
Missouri, and completed	on the	day of		
SNATURE				
SNATURE				
OTARY INFORMATION DTARY PUBLIC EMBOSSER OR	STATE		COUNTY (OR CITY OF ST. L	OUIS)
OTARY INFORMATION	STATE		COUNTY (OR CITY OF ST. L	OUIS)
OTARY INFORMATION DTARY PUBLIC EMBOSSER OR		EEODE ME TUIS	COUNTY (OR CITY OF ST. L	OUIS)
OTARY INFORMATION DTARY PUBLIC EMBOSSER OR	SUBSCRIBED AND SWORN BI		COUNTY (OR CITY OF ST. L	
OTARY INFORMATION DITARY PUBLIC EMBOSSER OR		F YEAR MY COMMISSION		
OTARY INFORMATION DTARY PUBLIC EMBOSSER OR	SUBSCRIBED AND SWORN BI	F YEAR		
OTARY INFORMATION DTARY PUBLIC EMBOSSER OR	SUBSCRIBED AND SWORN BI	F YEAR MY COMMISSION EXPIRES		

FILE: Closeout Documents

# **GENERAL CONDITIONS**

# **INDEX**

## ARTICLE:

- 1. General Provisions
  - 1.1. Definitions
  - 1.2. Drawings and Specifications
  - 1.3. Compliance with Laws, Permits, Regulations and Inspections
  - 1.4. Nondiscrimination in Employment
  - 1.5. Anti-Kickback
  - 1.6. Patents and Royalties
  - 1.7. Preference for American and Missouri Products and Services
  - 1.8. Communications
  - 1.9. Separate Contracts and Cooperation
  - 1.10. Assignment of Contract
  - 1.11. Indemnification
  - 1.12. Disputes and Disagreements
- 2. Owner/Designer Responsibilities
- 3. Contractor Responsibilities
  - 3.1. Acceptable Substitutions
  - 3.2. Submittals
  - 3.3. As-Built Drawings
  - 3.4. Guaranty and Warranties
  - 3.5. Operation and Maintenance Manuals
  - 3.6. Other Contractor Responsibilities
  - 3.7. Subcontracts
- 4. Changes in the Work
  - 4.1. Changes in the Work
  - 4.2. Changes in Completion Time
- 5. Construction and Completion
  - 5.1. Construction Commencement
  - 5.2. Project Construction
  - 5.3. Project Completion
  - 5.4. Payments
  - **6.** Bond and Insurance

- 6.1. Bond
- 6.2. Insurance
- 7. Termination or Suspension of Contract
  - 7.1. For Site Conditions
  - 7.2. For Cause
  - 7.3. For Convenience

#### **SECTION 007213 - GENERAL CONDITIONS**

- A. These General Conditions apply to each section of these specifications. The Contractor is subject to the provisions contained herein.
- B. The General Conditions are intended to define the relationship of the Owner, the Designer and the Contractor thereby establishing certain rules and provisions governing the operation and performance of the work so that the work may be performed in a safe, orderly, expeditious and workmanlike manner.

#### **ARTICLE 1 – GENERAL PROVISIONS**

#### **ARTICLE 1.1 - DEFINITIONS**

As used in these contract documents, the following terms shall have the meanings and refer to the parties designated in these definitions.

- 1. "COMMISSIONER": The Commissioner of the Office of Administration.
- 2. "CONSTRUCTION DOCUMENTS": The "Construction Documents" shall consist of the Project Manual, Drawings and Addenda.
- 3. "CONSTRUCTION
  REPRESENTATIVE:" Whenever the term
  "Construction Representative" is used, it shall
  mean the Owner's Representative at the work
  site.
- 4. "CONTRACTOR": Party or parties who have entered into a contract with the Owner to furnish work under these specifications and drawings.
- 5. "DESIGNER": When the term "Designer" is used herein, it shall refer to the Architect, Engineer, or Consultant of Record specified and defined in Paragraph 2.0 of the Supplemental Conditions, or his duly authorized representative. The Designer may be either a consultant or state employee.
- 6. "DIRECTOR": Whenever the term "Director" is used, it shall mean the Director of the Division of Facilities Management, Design and Construction or his Designee, representing the Office of Administration, State of Missouri. The Director is the agent of the Owner.
- 7. "DIVISION": Shall mean the Division of Facilities Management, Design and Construction, State of Missouri.

- 8. "INCIDENTAL JOB BURDENS": Shall mean those expenses relating to the cost of work, incurred either in the home office or on the job-site, which are necessary in the course of doing business but are incidental to the job. Such costs include office supplies and equipment, postage, courier services, telephone expenses including long distance, water and ice and other similar expenses.
- 9. **"JOINT VENTURE"**: An association of two (2) or more businesses to carry out a single business enterprise for profit for which purpose they combine their property, capital, efforts, skills and knowledge.
- 10. "OWNER": Whenever the term "Owner" is used, it shall mean the State of Missouri. Acting by and through the Office of Administration, Division of Facilities Management, Design and Construction.
- 11. **"PROJECT"**: Wherever the term "Project" is used, it shall mean the work required to be completed by the construction contract.
- 12. "PROJECT MANUAL": The "Project shall consist of Introductory Manual" Information, Invitation for Bid, Instructions to Bidders. Bid Documents. Additional Information, Standard Forms, General Conditions, Supplemental General Conditions, General Requirements and Technical Specifications.
- 13. "SUBCONTRACTOR": Party or parties who contract under, or for the performance of part or this entire Contract between the Owner and Contractor. The subcontract may or may not be direct with the Contractor.
- 14. "WORK": All supervision, labor, materials, tools, supplies, equipment, and any incidental operations and/or activities required by or reasonably inferable from the Contract Documents necessary to construct the Project and to produce the results intended by the Contract Documents in a safe, expeditious, orderly, and workmanlike manner so that the project shall be complete and finished in the best manner known to each respective trade.
- 15. "WORKING DAYS": are all calendar days except Saturdays, Sundays and the following holidays: New Year's Day, Martin Luther King, Jr. Day, Lincoln Day, Washington's Birthday (observed), Truman Day, Memorial Day, Juneteenth, Independence Day, Labor Day, Columbus Day, Veterans Day (observed), Thanksgiving Day, Christmas Day.

# ARTICLE 1.2 DRAWINGS AND SPECIFICATIONS

- A. In case of discrepancy between drawings and specifications, specifications shall govern. Should discrepancies in architectural drawings, structural drawings and mechanical drawings occur, architectural drawings shall govern and, in case of conflict between structural and mechanical drawings, structural drawings shall govern.
- B. Specifications are separated into titled divisions for convenience of reference only and to facilitate letting of contracts and subcontracts. The Contractor is responsible for establishing the scope of work for subcontractors, which may cross titled divisions. Neither the Owner nor Designer will establish limits and jurisdiction of subcontracts.
- C. Figured dimensions take precedence over scaled measurements and details over smaller scale general drawings. In the event of conflict between any of the documents contained within the contract, the documents shall take precedence and be controlling in the following sequence: addenda, supplementary general conditions, general conditions, division 1 specifications, technical division specifications, drawings, bid form and instructions to bidders.
- D. Anything shown on drawings and not mentioned in these specifications or vice versa, as well as any incidental work which is obviously necessary to complete the project within the limits established by the drawings and specifications, although not shown on or described therein, shall be performed by the Contractor at no additional cost as a part of his contract.
- E. Upon encountering conditions differing materially from those indicated in the contract documents, the Contractor shall promptly notify the Designer and Construction Representative in writing before such conditions are disturbed. The Designer shall promptly investigate said conditions and report to the Owner, with a recommended course of action. If conditions do materially differ and cause an increase or decrease in contract cost or time required for completion of any portion of the work, a contract change will be initiated as outlined in Article 4 of these General Conditions.
- E. Only work included in the contract documents is authorized, and the Contractor shall do no work other than that described therein or in accordance with appropriately authorized and approved contract changes.

# ARTICLE 1.3 - COMPLIANCE WITH LAWS, PERMITS, REGULATIONS AND INSPECTIONS

- A. Since the Owner is the State of Missouri, municipal or political subdivisions, zoning ordinances, construction codes (other than licensing of trades), and other like ordinances are not applicable to construction on Owner's property, and Contractor will not be required to submit drawings and specifications to any municipal or political subdivision, authority, obtain construction permits or any other licenses (other than licensing of trades) or permits from or submit to inspections by any municipality or political subdivision relating to the construction for this All permits or licenses required by municipality or political subdivision for operation on property not belonging to Owner shall be obtained by and paid for by Contractor. Each Contractor shall comply with all applicable laws, ordinances, rules and regulations that pertain to the work of this contract.
- B. Contractors, subcontractors and their employees engaged in the businesses of electrical, mechanical, plumbing, carpentry, sprinkler system work, and other construction related trades shall be licensed to perform such work by the municipal or political subdivision where the project is located, if such licensure is required by local code. Local codes shall dictate the level (master, journeyman, and apprentice) and the number, type and ratio of licensed tradesmen required for this project within the jurisdiction of such municipal or political subdivision.
- C. Equipment and controls manufacturers and their authorized service and installation technicians that do not maintain an office within the jurisdiction of the municipal or political subdivision but are a listed or specified contractor or subcontractor on this project are exempt from Paragraph 1.3 B above.
- D. The Contractor shall post a copy of the wage determination issued for the project and included as a part of the contract documents, in a prominent and easily accessible location at the site of construction for the duration of the project.
- E. Any contractor or subcontractor to such contractor at any tier signing a contract to work on this project shall provide a ten-hour Occupational Safety and Health Administration (OSHA) construction safety program for their on-site employees which includes a course in construction safety and health approved by OSHA or a similar program approved by the Department of Labor and Industrial Relations which is at least as stringent as an approved OSHA program. The contractor shall forfeit as a penalty to the public body on whose

behalf the contract is made or awarded, two thousand five hundred dollars plus one hundred dollars for each employee employed by the contractor or subcontractor, for each calendar day, or portion thereof, such employee is employed without the required training.

# ARTICLE 1.4 - NONDISCRIMINATION IN EMPLOYMENT

- A. The Contractor and his subcontractors will not discriminate against individuals based on race, color, religion, national origin, sex, disability, or age, but may use restrictions which relate to bona fide occupational qualifications. Specifically, the Contractor and his subcontractors shall not discriminate:
  - 1. Against recipients of service on the basis of race, color, religion, national origin, sex, disability or age.
  - 2. Against any employee or applicant, for employment on the basis of race, color, religion, national origin, sex or otherwise qualified disability status.
  - 3. Against any applicant for employment or employee on the basis of age, where such applicant or employee is between ages 40 and 70 and where such Contractor employs at least 20 persons.
  - 4. Against any applicant for employment or employee on the basis of that person's status as a disabled or Vietnam-era veteran.

The Contractor and his Subcontractors will ensure applicants for employment and employees are treated equally without regard to race, color, religion, national origin, sex, disability, or age. Such action shall include, but not be limited to, the following: employment, upgrading, demotion and transfer; recruitment or recruitment advertising; selection for training. including The Contractor and his apprenticeship. Subcontractors will give written notice of their commitments under this clause to any labor union with which they have bargaining or other agreements under this clause to any labor union with which they have bargaining or other agreements.

B. In the event of the Contractor's or his subcontractor's noncompliance with any provisions of this Article of the Contract, the Owner may cancel this contract in whole or in part or require the Contractor to terminate his contract with the subcontractor.

#### **ARTICLE 1.5 - ANTI-KICKBACK**

No employee of the division, shall have or acquire any pecuniary interest, whether direct or indirect, in this contract or in any part hereof. No officer, employee, designer, attorney, or administrator of or for the Owner who is authorized in such capacity and on behalf of the Owner to exercise any legislative, executive, supervisory or other similar functions in connection with the construction of the project, shall have or acquire any pecuniary interest, whether direct or indirect, in this contract, any material supply contract, subcontract, insurance contract, or any other contract pertaining to the project.

#### **ARTICLE 1.6 - PATENTS AND ROYALTIES**

- A. The Contractor shall hold and save the Owner and its officers, agents, servants, and employees harmless from liabilities of any nature or kind, including cost and expenses, for, or on account of, any patented or unpatented invention, process, article or appliance manufactured or used in the performance of this contract, including its use by the Owner, unless otherwise specifically stipulated in the contract documents.
- B. If the Contractor uses any design, device or materials covered by letters, patent or copyright, the Contractor shall provide for such use by suitable agreement with the Owner of such patented or copyrighted design, device or material. It is mutually agreed and understood, without exception, that the contract prices shall include all royalties or costs arising from the use of such design, device or materials, in any way involved in the work. The Contractor and/or his sureties shall indemnify and save harmless the Owner of the project from any and all claims for infringement by reason of the use of such patented or copyrighted design, device or materials or any trademark or copyright in connection with work agreed to be performed under this contract and shall indemnify the Owner for any cost, expense or damage it may be obliged to pay by reason of such infringement at any time during the prosecution of the work or after completion of the work.

# ARTICLE 1.7 - PREFERENCE FOR AMERICAN AND MISSOURI PRODUCTS AND SERVICES

- A. By virtue of statutory authority a preference will be given to Missouri labor and to products of mines, forests and quarries of the state of Missouri when they are found in marketable quantities in the state, and all such materials shall be of the best quality and suitable character that can be obtained at reasonable market prices, all as provided for in Section 8.280, Missouri Revised Statutes and Cumulative Supplements.
- B. Furthermore, pursuant to Section 34.076 Missouri Revised Statutes and Cumulative Supplements, a preference shall be given to those persons doing business as Missouri firms, corporations, or individuals, or which maintain Missouri offices or places of business, when the quality of performance promised is equal or better and the price quoted is the same or less. In addition, in order for a non-domiciliary bidder to be successful, his bid must be that same percentage lower than a domiciliary Missouri bidder's bid, as would be required for a Missouri bidder to successfully bid in the non-domiciliary state.
- In accordance with the Missouri Domestic Products Procurement Act Section 34.350 RSMo and Cumulative Supplements any manufactured goods or commodities used or supplied in the performance of this contract or any subcontract thereto shall be manufactured, assembled or produced in the United States, unless the specified products are not manufactured, assembled or produced in the United States in sufficient quantities to meet the agency's requirements or cannot be manufactured, assembled or produced in the United States within the necessary time in sufficient quantities to meet the contract requirements, or if obtaining the specified products manufactured, assembled or produced in the United States would increase the cost of this contract for purchase of the product by more than ten percent.

#### **ARTICLE 1.8 - COMMUNICATIONS**

- A. All notices, requests, instructions, approvals, and claims must be in writing and shall be delivered to the Designer and copied to the Construction Representative for the project except as required by Article 1.12 Disputes and Disagreements, or as otherwise specified by the Owner in writing as stated in Section 012600. Any such notice shall be deemed to have been given as of the time of actual receipt.
- B. The Contractor shall attend on-site progress and coordination meetings, as scheduled by the Construction Representative, no less than once a month.

C. The Contractor shall ensure that major subcontractors and suppliers shall attend monthly progress meetings as necessary to coordinate the work, and as specifically requested by the Construction Representative.

# ARTICLE 1.9 - SEPARATE CONTRACTS AND COOPERATION

- A. The Owner reserves the right to let other contracts in connection with this work. The Contractor shall afford other contractors reasonable opportunity for the introduction and storage of their materials and the execution of their work and shall properly connect and coordinate his work with theirs.
- B. The Contractor shall consult the drawings for all other contractors in connection with this work. Any work conflicting with the above shall be brought to the attention of the Owner's Representative before the work is performed. If the Contractor fails to do this, and constructs any work which interferes with the work of another contractor, the Contractor shall remove any part so conflicting and rebuild same, as directed by the Owner's Representative at no additional cost to the Owner.
- C. Each contractor shall be required to coordinate his work with other contractors so as to afford others reasonable opportunity for execution of their work. No contractor shall delay any other contractor by neglecting to perform contract work at the proper time. If any contractor causes delay to another, they shall be liable directly to that contractor for such delay in addition to any liquidated damages which might be due the Owner.
- D. Should the Contractor or project associated subcontractors refuse to cooperate with the instructions and reasonable requests of other Contractors or other subcontractors in the overall coordinating of the work, the Owner may take such appropriate action and issue directions, as required, to avoid unnecessary and unwarranted delays.
- E. Each Contractor shall be responsible for damage done to Owner's or other Contractor's property by him/her or workers in his employ through their fault or negligence.
- F. Should a Contractor sustain any damage through any act or omission of any other Contractor having a contract with the Owner, the Contractor so damaged shall have no claim or cause of action against the Owner for such damage, but shall have a claim or cause of action against the other Contractor to recover any and all damages sustained by reason of the acts or omissions of such Contractor. The phrase "acts or omissions" as used in this section shall be defined to include, but

not be limited to, any unreasonable delay on the part of any such contractors.

#### ARTICLE 1.10 - ASSIGNMENT OF CONTRACT

A. No assignment by Contractor of any amount or any part of this contract or of the funds to be received there under will be recognized unless such assignment has had the written approval of the Director and the surety has been given due notice of such assignment and has furnished written consent thereto. In addition to the usual recitals in assignment contracts, the following language must be set forth: "It is agreed that the funds to be paid to the assignee under this assignment are subject to performance by the Contractor of this contract and to claims or liens for services rendered or materials supplied for the performance of the work called for in said contract in favor of all persons, firms or corporations rendering such services or supplying such materials."

#### **ARTICLE 1.11 - INDEMNIFICATION**

- A. Contractor agrees to indemnify and save harmless Owner and its respective commissioners, officers, officials, agents, consultants and employees and Designer, their agents, servants and employees, from and against any and all liability for damage arising from injuries to persons or damage to property occasioned by any acts or omissions of Contractor, any subcontractors, agents, servants or employees, including any and all expense, legal or otherwise, which may be incurred by Owner or Designer, its agents, servants or employees, in defense of any claim, action or suit.
- B. The obligations of the Contractor under this paragraph shall not extend to the liability of the Designer, his agents or employees, arising out of (1) the preparation or approval of maps, drawings, opinions, reports, surveys, contract changes, design or specifications, or (2) giving of or the failure to give directions or instructions by the Designer, his agents or employees as required by this contract documents provided such giving or failure to give is the primary cause of the injury or damage.

# ARTICLE 1.12 - DISPUTES AND DISAGREEMENTS

It is hereby expressly agreed and understood that in case any controversy or difference of opinion arises during construction, best efforts will be given to resolution at the field level. Should those efforts be unsuccessful, the Contractor has the right to appeal in writing, the decision of the Director's Designee to the Director at Room 730 Truman Building, P.O. Box 809, Jefferson City, Missouri 65102. The decision of the Director shall be final and binding on all parties.

# ARTICLE 2 -- OWNER/DESIGNER RESPONSIBILITIES

- A. The Owner shall give all orders and directions contemplated under this contract relative to the execution of the work. During progress of work the Owner will be represented at the project site by the Construction Representative and/or Designer, whose responsibilities are to see that this contract is properly fulfilled.
- B. The Owner shall at all times have access to the work whenever it is in preparation or progress. The Contractors shall provide proper facilities for such access and for inspection and supervision.
- C. All materials and workmanship used in the work shall be subject to the inspection of the Designer and Construction Representative, and any work which is deemed defective shall be removed, rebuilt or made good immediately upon notice. The cost of such correction shall be borne by the Contractor. Contractor shall not be entitled to an extension of the contract completion date in order to remedy defective work. All rejected materials shall be immediately removed from the site of the work.
- D. If the Contractor fails to proceed at once with the correction of rejected defective materials or workmanship, the Owner may, by separate contract or otherwise, have the defects remedied or rejected. Materials removed from the site and charge the cost of the same against any monies which may be due the Contractor, without prejudice to any other rights or remedies of the Owner.
- E. Failure or neglect on the part of Owner to observe faulty work, or work done which is not in accordance with the drawings and specifications shall not relieve the Contractor from responsibility for correcting such work without additional compensation.
- F. The Owner shall have the right to direct the Contractor to uncover any completed work.
  - 1. If the Contractor fails to adequately notify the Construction Representative and/or Designer of an inspection as required by the Contract Documents, the Contractor shall, upon written request, uncover the work. The Contractor shall bear all costs associated with uncovering and again covering the work exposed.
  - 2. If the Contractor is directed to uncover work, which was not otherwise required by the Contract\_Documents to be inspected, and the work is found to be defective in any respect, no compensation shall be allowed for this work. If, however, such work is found to meet

the requirements of this contract, the actual cost of labor and material necessarily involved in the examination and replacement plus 10% shall be allowed the Contractor.

- G. The Designer shall give all orders and directions contemplated under this contract relative to the scope of the work and shall give the initial interpretation of the contract documents.
- H. The Owner may file a written notice to the Contractor to dismiss immediately any subcontractors, project managers, superintendents, foremen, workers, watchmen or other employees whom the Owner may deem incompetent, careless or a hindrance to proper or timely execution of the work. The Contractor shall comply with such notice as promptly as practicable without detriment to the work or its progress.
- I. If in the Owner's judgment it becomes necessary at any time to accelerate work, when ordered by the Owner in writing, the Contractor shall redirect resources to such work items and execute such portions of the work as may be required to complete the work within the current approved contract schedule.

## ARTICLE 3 -- CONTRACTOR RESPONSIBILITIES

The Contractor shall register and utilize the Owner's eBuilder digital project management system for submission of documents described in the following sections. This includes but is not limited to submittals as required by designer, payment applications, Request for Information (RFI), construction change orders, Request for Proposals (RFP), Designer Supplemental Instructions (DSI), etc.

#### **ARTICLE 3.1 -- ACCEPTABLE SUBSTITUTIONS**

- A. The Contractor may request use of any article, device, product, material, fixture, form or type of construction which in the judgment of the Owner and Designer is equal in all respects to that named. Standard products of manufacturers other than those specified will be accepted when, prior to the ordering or use thereof, it is proven to the satisfaction of the Owner and Designer that they are equal in design, strength, durability, usefulness and convenience for the purpose intended.
- B. Any changes required in the details and dimensions indicated on the drawings for the substitution of products other than those specified shall be properly made at the expense of the Contractor requesting the substitution or change.
- C. The Contractor shall submit a request for such substitutions in writing to the Owner and Designer within twenty (20) working days after the date of

- the "Notice to Proceed." Thereafter no consideration will be given to alternate forms of accomplishing the work. This Article does not preclude the Owner from exercising the provisions of Article 4 hereof.
- D. Any request for substitution by the Contractor shall be submitted in accordance with SECTION 002113 INSTRUCTIONS TO BIDDERS.
- E. When a material has been approved, no change in brand or make will be permitted unless:
  - 1. Written verification is received from the manufacturer stating they cannot make delivery on the date previously agreed, or
  - 2. Material delivered fails to comply with contract requirements.

#### **ARTICLE 3.2 -- SUBMITTALS**

- A. The Contractor's submittals must be submitted with such promptness as to allow for review and approval so as not to cause delay in the work. The Contractor shall coordinate preparation and processing of submittals with performance of construction activities.
  - Coordinate each submittal with fabrication, = purchasing, testing, delivery, other submittals, and related activities that require sequential activity.
  - Submit four (4) copies to the Designer and additional copies as required for the subcontractors and material suppliers. Also provide copies to meet the requirements for maintenance manuals.
- B. All subcontractors' shop drawings and schedules shall be submitted by the Contractor and shall bear evidence that Contractor has received, reviewed, and approved them. Any shop drawings and schedules submitted without this evidence will be returned to the Contractor for resubmission.
- C. The Contractor shall include with the shop drawing, a letter indicating any and all deviations from the drawings and/or specifications. Failure to notify the Designer of such deviations will be grounds for subsequent rejection of the related work or materials. If, in the opinion of the Designer, the deviations are not acceptable, the Contractor will be required to furnish the item as specified and indicated on the drawings.
- D. The Designer shall check shop drawings and schedules with reasonable promptness and approve them only if they conform to the design concept of the project and comply with the information given in the contract documents. The approval shall not relieve the Contractor from the responsibility to comply with the drawings and specifications, unless the Contractor has called the Designer's attention to the deviation, in writing, at the time of

submission and the Designer has knowingly approved thereof. An approval of any such modification will be given only under the following conditions:

- 1. It is in the best interest of the Owner
- 2. It does not increase the contract sum and/or completion time
- 3. It does not deviate from the design intent
- 4. It is without prejudice to any and all rights under the surety bond.
- E. No extension of time will be granted because of the Contractor's failure to submit shop drawings and schedules in ample time to allow for review, possible resubmission, and approval. Fabrication of work shall not commence until the Contractor has received approval. The Contractor shall furnish prints of approved shop drawings and schedules to all subcontractors whose work is in any way related to the work under this contract. Only prints bearing this approval will be allowed on the site of construction
- F. The Contractor shall maintain a complete file onsite of approved shop drawings available for use by the Construction Representative.

## **ARTICLE 3.3 – AS-BUILT DRAWINGS**

A. The Contractor shall update a complete set of the construction drawings, shop drawings and schedules of all work monthly by marking changes, and at the completion of their work (prior to submission of request for final payment) note all changes and turn the set over to the Construction Representative. The updates shall show all addenda, all field changes that were made to adapt to field conditions, changes resulting from contract changes or supplemental instructions, and all locations of structures, buried installations of piping, conduit, and utility services. All buried and concealed items both inside and outside shall be accurately located as to depth and referenced to permanent features such as interior or exterior wall faces and dimensions shall be given in a neat and legible manner in a contrasting colored pencil or ink. If approved by the Designer, an electronic file format may be provided.

# ARTICLE 3.4 – GUARANTY AND WARRANTIES

#### A. General Guaranty

 Neither the final certificate of payment nor any provision in the contract documents nor partial use or occupancy of the premises by the Owner shall constitute an acceptance of work not done in accordance with contract requirements.

- 2. The Contractor or surety shall remedy any defects in the work and pay for any damage to property resulting there from which shall appear within a period of one (1) year from the date of substantial completion unless a longer period is otherwise specified or a differing guaranty period has been established in the substantial completion certificate. The Owner will give notice of observed defects with reasonable promptness.
- 3. In case of default on the part of the Contractor in fulfilling this part of this contract, the Owner may correct the work or repair the damage and the cost and expense incurred in such event shall be paid by or recoverable from the Contractor or surety.
- 4. The work will be free from defects not inherent in the quality required or permitted, and that the Work will conform to the requirements of the Contract Documents. Work not conforming to these requirements, including substitutions not properly approved and authorized, may be considered defective. The Contractor's guaranty excludes remedy for damage or defect caused by abuse, modifications not executed by the Contractor, or insufficient maintenance. improper improper operation, or normal wear and tear under normal usage. If required by the Contractor Owner, the shall furnish satisfactory evidence as to the kind and quality of materials and equipment

# B. Extended Warranty

Manufacturer's certificates of warranty shall be obtained for all major equipment. Warranty shall be obtained for at least one year. Where a longer period is offered at no additional cost or called for in the specific equipment specifications, the longer period shall govern.

# ARTICLE 3.5 -- OPERATION AND MAINTENANCE MANUALS

- A. Immediately after equipment submittals are approved and no later than ten (10) working days prior to the substantial completion inspection, the Contractor shall provide to the Designer three (3) copies of operating instructions and service manuals, containing the following:
  - Start-up and Shut-down Procedures: Provide a step-by-step write up of all major equipment. When manufacturer's printed start-up, trouble shooting and shut-down procedures are available; they may be incorporated into the operating manual for reference.

- 2. Operating Instructions: Written operating instructions shall be included for the efficient and safe operation of all equipment.
- 3. Equipment List: List of all major equipment as installed shall be prepared to include model number, capacities, flow rate, name place data, shop drawings and air and water balance reports.
- 4. Service Instructions: Provide the following information for all pieces of equipment.
  - Recommended spare parts including catalog number and name of local supplier or factory representative.
  - b. Belt sizes, types, and lengths.
  - c. Wiring diagrams.
- 5. Manufacturer's Certificate of Warranty as described in Article 3.4.
- 6. Prior to the final payment, furnish to the Designer three (4) copies of parts catalogs for each piece of equipment furnished by him/her on the project with the components identified by number for replacement ordering.
- B. Submission of operating instructions shall be done in the following manner.
  - 1. Manuals shall be in quadruplicate, and all materials shall be bound into volumes of standard 8½" x 11" hard binders. Large drawings too bulky to be folded into 8½" x 11" shall be separately bound or folded and in envelopes, cross referenced and indexed with the manuals.
  - The manuals shall identify project name, project number, and include the name and address of the Contractor, subcontractors and manufacturers who were involved with the activity described in that particular manual.
  - Internally subdivide the binder contents with permanent page dividers, logically organized with tab titles clearly printed under reinforced laminated plastic tabs.
  - 4. Contents: Prepare a Table of Contents for each volume, with each product or system description identified.

# ARTICLE 3.6 – OTHER CONTRACTOR RESPONSIBILITIES

A. The Contractor shall keep on site, during progress of the work, a competent superintendent satisfactory to the Construction Representative. The superintendent shall represent the Contractor and all agreements made by the superintendent shall be binding. The superintendent shall

- carefully study and compare all drawings, specifications and other instructions and shall promptly notify the Construction Representative and Designer, in writing, any error, inconsistency or omission which may be discovered. The superintendent shall coordinate all work on the project. Any change of the superintendent shall be approved by the Construction Representative.
- B. Contractor shall, at all times, enforce strict discipline and good order among his employees, and shall not employ on the work any unfit person or anyone not skilled in the work assigned to him/her.
- C. The Contractor shall supply sufficient labor, material, plant and equipment and pay when due any laborer, subcontractor or supplier for supplies furnished and otherwise prosecute the work with diligence to prevent work stoppage and ensure completion thereof within the time specified.
- D. The Contractor and each of his subcontractors shall submit to the Construction Representative, through the Designer such schedules of quantities and costs, progress schedules, payrolls, reports, estimates, records and other data as the Owner may request concerning work performed or to be performed under this contract.
- E. The Contractor, subcontractors, and material suppliers shall upon written request, give the Owner access to all time cards, material invoices, payrolls, estimates, profit and loss statements, and all other direct or indirect costs related to this work.
- F. The Contractor shall be responsible for laying out all contract work such as layout of architectural, structural, mechanical and electrical work, which shall be coordinated with layouts of subcontractors for general construction work. The Contractor is also responsible for unloading, uncrating and handling of all materials and equipment to be erected or placed by him/her, whether furnished by Contractor or others. No extra charges or compensation will be allowed as a result of failure to verify dimensions before ordering materials or fabricating items.
- G. The Contractor must notify the Construction Representative at least one working day before placing concrete or burying underground utilities, pipelines, etc.
- H. Contractors shall prearrange time with the Construction Representative for the interruption of any facility operation. Unless otherwise specified in these documents, all connections, alterations or relocations as well as all other portions of the work will be performed during normal working hours.

- The Contractor shall coordinate all work so there will not be prolonged interruptions of existing equipment operation. Any existing plumbing, heating, ventilating, air conditioning or electrical disconnections necessary for the project, which affect portions of this construction or building or any other building must be scheduled with the Construction Representative to minimize or avoid any disruption of facility operations. In no case, unless previously approved in writing by the Construction Representative, shall utilities be left disconnected at the end of a work day or over a Any interruption of utilities either intentionally or accidentally shall not relieve the Contractor responsible for the interruption from the responsibility to repair and restore the utility to normal service. Repairs and restoration shall be made before the workers responsible for the repair and restoration leave the job.
- J. Contractors shall limit operations and storage of materials to the area within the project, except as necessary to connect to existing utilities, and shall not encroach on neighboring property. The Contractor shall be responsible for repair of their damage to property on or off the project site occurring during construction of project. All such repairs shall be made to the satisfaction of the property owner.
- K. Unless otherwise permitted, all materials shall be new and both workmanship and materials shall be of the best quality.
- L. Unless otherwise provided and stipulated within these specifications, the Contractor shall furnish, construct, and/or install and pay for materials, devices, mechanisms, equipment, all necessary personnel, utilities including, but not limited to water, heat, light and electric power, transportation services, applicable taxes of every nature, and all other facilities necessary for the proper execution and completion of the work.
- M. Contractor shall carefully examine the plans and drawings and shall be responsible for the proper fitting of his material, equipment and apparatus into the building.
- N. The Contractor or subcontractors shall not overload, or permit others to overload, any part of any structure during the performance of this contract.
- O. All temporary shoring, bracing, etc., required for the removal of existing work and/or for the installation of new work shall be included in this contract. The Contractor shall make good, at no cost to the Owner, any damage caused by improper support or failure of shoring in any respect. Each Contractor shall be responsible for shoring

- required to protect his work or adjacent property and improvements of Owner and shall be responsible for shoring or for giving written notice to adjacent property owners. Shoring shall be removed only after completion of permanent supports.
- P. The Contractor shall provide at the proper time such material as is required for support of the work. If openings are required, whether shown on drawings or not, the Contractor shall see that they are properly constructed.
- Q. During the performance of work the Contractor shall be responsible for providing and maintaining warning signs, lights, signal devices, barricades, guard rails, fences and other devices appropriately located on site which will give proper and understandable warning to all persons of danger of entry onto land, structure or equipment.
- R. The Contractor shall be responsible for protection, including weather protection, and proper maintenance of all equipment and materials.
- The Contractor shall be responsible for care of the finished work and shall protect same from damage or defacement until substantial completion by the Owner. If the work is damaged by any cause, the Contractor shall immediately begin to make repairs accordance with the drawings specifications. Contractor shall be liable for all damage or loss unless attributable to the acts or omissions of the Owner or Designer. Any claim for reimbursement shall be submitted in accordance with Article 4. After substantial completion the Contractor will only be responsible for damage resulting from acts or omissions of the Contractor or subcontractors through final warranty.
- T. In the event the Contractor encounters an unforeseen hazardous material, the Contractor shall immediately stop work in the area affected and report the condition to the Owner and Designer in writing. The Contractor shall not be required, pursuant to Article 4, to perform, any work relating to hazardous materials.
- U. In an emergency affecting safety of persons or property, the Contractor shall act, at the Contractor's discretion, to prevent threatened damage, injury or loss. Additional compensation or extension of time claimed by the Contractor on account of an emergency shall be determined as provided in Article 4.
- V. Before commencing work, Contractors shall confer with the Construction Representative and facility representative and review any facility rules and regulations which may affect the conduct of the work.

W. Project signs will only be erected on major projects and only as described in the specifications. If no sign is specified, none shall be erected.

#### **ARTICLE 3.7 -- SUBCONTRACTS**

- A. Subcontractor assignments as identified in the bid form shall not be changed without written approval of the Owner. The Owner will not approve changes of a listed subcontractor unless the Contractor documents, to the satisfaction of the Owner that the subcontractor cannot or will not perform the work as specified.
- B. The Contractor is fully responsible to the Owner for the acts and omissions of all subcontractors and of persons either directly or indirectly employed by them.
- C. Every subcontractor shall be bound by the applicable terms and provisions of these contract documents, but no contractual relationship shall exist between any subcontractor and the Owner unless the right of the Contractor to proceed with the work is suspended or this contract is terminated as herein provided, and the Owner in writing elects to assume the subcontract.
- D. The Contractor shall upon receipt of "Notice to Proceed" and prior to submission of the first payment request, notify the Designer and Construction Representative in writing of the names of any subcontractors to be used in addition to those identified in the bid form and all major material suppliers proposed for all parts of the work.

#### ARTICLE 4 -- CHANGES IN THE WORK

#### 4.1 CHANGES IN THE WORK

- A. The Construction Representative, without giving notice to the surety and without invalidating this contract, may order extra work or make changes by altering, adding to or deducting from the work, this contract sum being adjusted accordingly. All such work shall be executed under the conditions of the original contract. A claim for extension of time caused by any change must be adjusted at the time of ordering such change. No future request for time will be considered.
- B. Each Contract Change shall include all costs required to perform the work including all labor, material, equipment, overheads and profit, delay, disruptions, or other miscellaneous expenses. No subsequent requests for additional compensation including claims for delay, disruption, or reduced efficiency as a result of each change will be considered. Values from the Schedule of Values will not be binding as a basis for additions to or deductions from the contract price.

- C. The amount of any adjustment in this contract price for authorized changes shall be agreed upon before such changes become effective and shall be determined, through submission of a request for proposal, as follows:
  - 1. By an acceptable fixed price proposal from the Contractor. Breakdowns shall include all takeoff sheets of each Contractor and subcontractor. Breakdown shall include a listing of each item of material with unit prices and number of hours of labor for each task. Labor costs per hour shall be included with labor burden identified, which shall be not less than the prevailing wage rate, etc. Overhead and profit shall be shown separately for each subcontractor and the Contractor.
  - 2. By a cost-plus-fixed-fee (time and material) basis with maximum price, total cost not to exceed said maximum. Breakdown shall include a listing of each item of material with unit prices and number of hours of labor for each task. Labor costs per hour shall be included with labor burden identified, which shall be not less than the prevailing wage rate, etc. Overhead and profit shall be shown separately for each subcontractor and the Contractor.
  - 3. By unit prices contained in Contractor's original bid form and incorporated in the construction contract.
- D. Overhead and Profit on Contract Changes shall be applied as follows:
  - 1. The overhead and profit charge by the Contractor and all subcontractors shall be considered to include, but is not limited to: incidental job burdens, small truck (under 1 ton) expense, mileage, small hand tools, warranty costs, company benefits and general office overhead. Project supervision including field supervision and job site office expense shall be considered a part of overhead and profit unless a compensable time extension is granted.
  - 2. The percentages for overhead and profit charged on Contract Changes shall be subject to the following limits: (a) the percentage mark-up for the Contractor shall be limited to the Contractor's fee: (b) fifteen percent (15%) maximum for Work directly performed by employees of a subcontractor, or subsubcontractor; (c) five percent (5%) maximum for the Work performed or passed through to the Owner by the Contractor; (d) five percent (5%) maximum subcontractor's mark-up for

Work performed by a sub-subcontractor and passed through to the Owner by the subcontractor and Contractor; and (e) in no case shall the total overhead and profit paid by the Owner on any Contract Changes exceed twenty-five percent (25%) of the cost of materials, labor and equipment (exclusive of Contractor or any Subcontractor overhead and profit) necessary to put the contract change work in place.

- 3. The Contractor will be allowed to add the cost of Contractor's payment and performance bonding, builder's risk insurance, and general liability insurance to their cost of work. The above listed bonding and insurance cost shall not exceed two percent (2%) and shall be allowed on the total cost of the added work, including overhead and profit.
- 4. On proposals covering both increases and decreases in the amount of this contract, the application of overhead and profit shall be on the net change in the cost of the work.
- 5. The percentage(s) for overhead and profit to be credited to the Owner on Contract Changes that are solely decreases in the quantity of work or materials shall be the same as those for additive Contract Changes provided above.
- E. No claim for an addition to this contract sum shall be valid unless authorized as aforesaid in writing by the Owner. In the event that none of the foregoing methods are agreed upon, the Owner may order the Contractor to perform work on a time and material basis. The cost of such work shall be determined by the Contractor's actual labor and material cost to perform the work plus overhead and profit as outlined herein. The Designer and Construction Representative shall approve the Contractor's daily time and material invoices for the work involved.
- F. If the Contractor claims that any instructions involve extra cost under this contract, the Contractor shall give the Owner's Representative written notice thereof within a reasonable time after the receipt of such instructions, and in any event before proceeding to execute the work. No such claim shall be valid unless so made and authorized by the Owner, in writing.
- G. In an emergency affecting the safety of life or of the structure or of adjoining property, the Contractor, without special instruction or authorization from the Construction Representative, is hereby permitted to act at their discretion to prevent such threatened loss or injury. The Contractor shall submit a claim for compensation for such emergency work in writing to the Owner's Representative.

## ARTICLE 4.2 – CHANGES IN COMPLETION TIME

- A. Extension of the number of work days stipulated in the Contract for completion of the work with compensation may be made when:
  - 1. The contractor documents that proposed Changes in the work, as provided in Article 4.1, extends construction activities critical to contract completion date, OR
  - 2. The Owner suspends all work for convenience of the Owner as provided in Article 7.3, OR
  - 3. An Owner caused delay extends construction activities critical to contract completion (except as provided elsewhere in these General Conditions). The Contractor is to review the work activities yet to begin and evaluate the possibility of rescheduling the work to minimize the overall project delay.
- B. Extension of the number of work days stipulated in the Contract for completion of the work without compensation may be made when:
  - 1. Weather-related delays occur, subject to provisions for the inclusion of a specified number of "bad weather" days when provided for in Section 012100-Allowances, OR
  - 2. Labor strikes or acts of God occur, OR
  - The work of the Contractor is delayed on account of conditions which were beyond the control of the Contractor, subcontractors or suppliers, and were not the result of their fault or negligence.
- C. No time extension or compensation will be provided for delays caused by or within the control of the Contractor, subcontractors or suppliers and for concurrent delays caused by the Owner.
- D. The Contractor shall notify the Owner promptly of any occurrence or conditions which in the Contractor's opinion results in a need for an extension of time. The notice shall be in writing and shall include all necessary supporting materials with details of any resultant costs and be submitted in time to permit full investigation and evaluation of the Contractor's claim. The Owner shall promptly acknowledge the Contractor's notice and, after recommendation from the Owner's Representative and/or Designer, shall provide a decision to the Contractor. Failure on the part of the Contractor to provide such notice and to detail the costs shall constitute a waiver by the Contractor of any claim. Requests for extensions of time shall be for working days only.

# ARTICLE 5 - CONSTRUCTION AND COMPLETION

## ARTICLE 5.1 – CONSTRUCTION COMMENCEMENT

- A. Upon receipt of the "Intent to Award" letter, the Contractor must submit the following properly executed instruments to the Owner:
  - 1. Contract:
  - 2. Performance/payment bond as described in Article 6.1;
  - 3. Certificates of Insurance, or the actual policies themselves, showing that the Contractor has obtained the insurance coverage required by Article 6.2.

Above referenced items must be received by the Owner within ten (10) working days after the effective date of the contract. If not received, the Owner may treat the failure to timely submit them as a refusal by the Contractor to accept a contract for this work and may retain as liquidated damages the Contractor's bid bond, cashier's check or certified check as provided in the Instructions to Bidders. Upon receipt the Owner will issue a "Notice to Proceed" with the work to the Contractor.

- B. Within the time frame noted in Section 013200 Schedules, following receipt of the "Notice to Proceed", the Contractor shall submit to the Owner a progress schedule and schedule of values, showing activities through the end of the contract period. Should the Contractor not receive written notification from the Owner of the disapproval of the schedule of values within fifteen (15) working days, the Contractor may consider it approved for purpose of determining when the first monthly Application and Certification for Payment may be submitted.
- C. The Contractor may commence work upon receipt of the Division of Facilities Management, Design and Construction's "Notice to Proceed" letter. Contractor shall prosecute the work with faithfulness and energy, and shall complete the entire work on or before the completion time stated in the contract documents or pay to the Owner the damages resulting from the failure to timely complete the work as set out within Article 5.4.

#### ARTICLE 5.2 -- PROJECT CONSTRUCTION

A. Each Contractor shall submit for the Owner's approval, in reproducible form, a progress schedule showing the rate of progress and the order of the work proposed to carry on various phases of the project. The schedule shall be in conformance

- with the requirements outlined in Section 013200 Schedules.
- B. Contractor shall employ and supply a sufficient force of workers, material, and equipment and shall pay when due, any worker, subcontractor or supplier and otherwise prosecute the work with such diligence so as to maintain the rate of progress indicated on the progress schedule, prevent work stoppage, and insure completion of the project within the time specified.

#### **ARTICLE 5.3 -- PROJECT COMPLETION**

- A. Substantial Completion. A Project is substantially complete when construction is essentially complete and work items remaining to be completed can be done without interfering with the Owner's ability to use the Project for its intended purpose.
  - Once the Contractor has reached what they believe is Substantial Completion, the Contractor shall notify the Designer and the Construction Representative of the following:
    - That work is essentially complete with the exception of certain listed work items.
       The list shall be referred to as the "Contractor's Punch."
    - That all Operation and Maintenance Manuals have been assembled and submitted in accordance with Article 3.5A.
    - c. That the Work is ready for inspection by the Designer and Construction Representative. The Owner shall be entitled to a minimum of ten working days notice before the inspection shall be performed.
  - 2. If the work is acceptable, the Owner shall issue a Certificate of Substantial Completion, which shall set forth the responsibilities of the Owner and the Contractor for utilities, security, maintenance, damage to the work and risk of loss. The Certificate shall also identify those remaining items of work to be performed by the Contractor. All such work items shall be complete within 30 working days of the date of the Certificate, unless the Certificate specifies a different time. If the Contractor shall be required to perform tests that must be delayed due to climatic conditions, it is understood that such tests and affected equipment will be identified on the Certificate and shall be accomplished by the Contractor at the earliest possible date. Performance of the tests may not be required before Substantial Completion can be issued. The date of the issuance of the Certificate of

- Substantial Completion shall determine whether or not the work was completed within the contract time and whether or not Liquidated Damages are due.
- 3. If the work is not acceptable, and the Owner does not issue a Certificate of Substantial Completion, the Owner shall be entitled to charge the Contractor with the Designer's and Owner's costs of re-inspection, including time and travel.
- B. Partial Occupancy. Contractor agrees that the Owner shall be permitted to occupy and use any completed or partially completed portions of the Project, when such occupancy and use is in the Owner's best interest. Owner shall notify Contractor of its desire and intention to take Partial Occupancy as soon as possible but at least ten (10) working days before the Owner intends to occupy. If the Contractor believes that the portion of the work the Owner intends to occupy is not ready for occupancy, the Contractor shall notify the Owner immediately. The Designer shall inspect the work in accordance with the procedures above. If the Contractor claims increased cost of the project or delay in completion as a result of the occupancy, he shall notify the Owner immediately but in all cases before occupancy occurs.
- C. Final Completion. The Project is finally complete when the Certificate of Substantial Completion has been issued and all work items identified therein as incomplete have been completed, and when all administrative items required by the contract have been completed. Final Completion entitles the Contractor to payment of the outstanding balance of the contract amount including all change orders and retainage. Within five (5) working days of the date of the Certificate of Substantial Completion, the Contractor shall identify the cost to complete any outstanding items of work. The Designer shall review the Contractor's estimate and either approve it or provide an independent estimate for all such items. If the Contractor fails to complete the remaining items within the time specified in the Certificate, the Owner may terminate the contract and go to the surety for project completion in accordance with Article 7.2 or release the contract balance to the Contractor less 150% of the approved estimate to complete the outstanding items. Upon completion of the outstanding items, when a final cost has been established, any monies remaining shall be paid to the Contractor. Failure to complete items of work does not relieve the Contractor from the obligation to complete the administrative requirements of the contract, such as the provisions of Article 5.3 FAILURE TO COMPLETE ALL ITEMS OF WORK UNDER THE CONTRACT SHALL BE CONSIDERED A

- DEFAULT AND BE GROUNDS FOR CONTRACT TERMINATION AND DEBARMENT.
- D. Liquidated Damages. Contractor agrees that the Owner may deduct from the contract price and retain as liquidated damages, and not as penalty or forfeiture, the sum stipulated in this contract for each work day after the Contract Completion Day on which work is not Substantially Complete. Assessment of Liquidated Damages shall not relieve the Contractor or the surety of any responsibility or obligation under the Contract. In addition, the Owner may, without prejudice to any other rights, claims, or remedies the Owner may have including the right to Liquidated Damages, charge the Contractor for all additional expenses incurred by the Owner and/or Designer as the result of the extended contract period through Final Completion. Additional Expenses shall include but not be limited to the costs of additional inspections.
- E. Early Completion. The Contractor has the right to finish the work before the contract completion date; however, the Owner assumes no liability for any hindrances to the Contractor unless Owner caused delays result in a time extension to the contract completion date. The Contractor shall not be entitled to any claims for lost efficiencies or for delay if a Certificate of Substantial Completion is given on or before the Contract Completion Date.

#### ARTICLE 5.4 -- PAYMENT TO CONTRACTOR

- A. Payments on account of this contract will be made monthly in proportion to the work which has been completed. Request for payment must be submitted on the Owner's forms. No other pay request will be processed. Supporting breakdowns must be in the same format as Owner's forms and must provide the same level of detail. The Designer will, within 5 working days from receipt of the contractor's request for payment either issue a Certificate for Payment to the Owner, for such amount as the Designer determines is properly due, or notify the Contractor in writing of reasons for withholding a Certificate. The Owner shall make payment within 30 calendar days after the "Application and Certification for Payment" has been received and certified by the Designer. The following items are to be attached to the contractor's pay request:
  - 1. Updated construction schedule
  - 2. Certified payrolls consisting of name, occupation and craft, number of hours worked and actual wages paid for each individual employee, of the Contractor and all subcontractors working on the project

- B. The Owner shall retain 5 percent of the amount of each such payment application, except as allowed by Article 5.4, until final completion and acceptance of all work covered by this contract.
- C. Each payment made to Contractor shall be on account of the total amount payable to Contractor and all material and work covered by paid partial payment shall thereupon become the sole property of Owner. This provision shall not be construed as relieving Contractor from sole responsibility for care and protection of materials and work upon which payments have been made or restoration of any damaged work or as a waiver of the right of Owner to require fulfillment of all terms of this contract.
- D. Materials delivered to the work site and not incorporated in the work will be allowed in the Application and Certification for Payment on the basis of one hundred (100%) percent of value, subject to the 5% retainage providing that they are suitably stored on the site or in an approved warehouse in accordance with the following requirements:
  - 1. Material has previously been approved through submittal and acceptance of shop drawings conforming to requirements of Article 3.2 of General Conditions.
  - 2. Delivery is made in accordance with the time frame on the approved schedule.
  - 3. Materials, equipment, etc., are properly stored and protected from damage and deterioration and remain so if not, previously approved amounts will be deleted from subsequent pay applications.
  - 4. The payment request is accompanied by a breakdown identifying the material equipment, etc. in sufficient detail to establish quantity and value.
- E. The Contractor shall be allowed to include in the Application and Certification for Payment, one hundred (100%) of the value, subject to retainage, of major equipment and material stored off the site if all of the following conditions are met:
  - The request for consideration of payment for materials stored off site is made at least 15 working days prior to submittal of the Application for Payment including such material. Only materials inspected will be considered for inclusion on Application for Payment requests.
  - 2. Materials stored in one location off site are valued in excess of \$25,000.
  - 3. That a Certificate of Insurance is provided indicating adequate protection from loss, theft

- conversion or damage for materials stored off site. This Certificate shall show the State of Missouri as an additional insured for this loss.
- 4. The materials are stored in a facility approved and inspected, by the Construction Representative.
- 5. Contractor shall be responsible for, Owner costs to inspect out of state facilities, and any delays in the completion of the work caused by damage to the material or for any other failure of the Contractor to have access to this material for the execution of the work.
- F. The Owner shall determine the amount, quality and acceptability of the work and materials which are to be paid for under this contract. In the event any questions shall arise between the parties, relative to this contract or specifications, determination or decision of the Owner or the Construction Representative and the Designer shall be a condition precedent to the right of the Contractor to receive any money or payment for work under this contract affected in any manner or to any extent by such question.
- G. Payments Withheld: The Owner may withhold or nullify in whole or part any certificate to such extent as may be necessary to protect the Owner from loss on account of:
  - 1. Defective work not remedied. When a notice of noncompliance is issued on an item or items, corrective action shall be undertaken immediately. Until corrective action is completed, no monies will be paid and no additional time will be allowed for the item or items. The cost of corrective action(s) shall be borne by the Contractor.
  - 2. A reasonable doubt that this contract can be completed for the unpaid balance.
  - 3. Failure of the Contractor to update as-built drawings monthly for review by the Construction Representative.
  - 4. Failure of the Contractor to update the construction schedule.
    - When the Construction Representative is satisfied the Contractor has remedied above deficiencies, payment shall be released.
- H. Final Payment: Upon receipt of written notice from the Contractor to the Designer and Project Representative that the work is ready for final inspection and acceptance, the Designer and Project Representative, with the Contractor, shall promptly make such inspection. If the work is acceptable and the contract fully performed, the Construction Representative shall complete a final acceptance report and the Contractor will be

directed to submit a final Application and Certification for Payment. If the Owner approves the same, the entire balance shall be due and payable, with the exception of deductions as provided for under Article 5.4.

- 1. Where the specifications provide for the performance by the Contractor of (certain tests for the purpose of balancing and checking the air conditioning and heating equipment and the Contractor shall have furnished and installed all such equipment in accordance with the specifications, but said test cannot then be made because of climatic conditions, such test shall may be considered as required under the provisions of the specifications, Section 013300 and this contract may be substantial Full payment will not be made until the tests have been made and the equipment and system is finally accepted. If the tests are not completed when scheduled, the Owner may deduct 150% of the value of the tests from the final payment.
- 2. The final payment shall not become due until the Contractor delivers to the Construction Representative:
  - a) A complete file of releases, on the standard form included in the contract documents as "Final Receipt of Payment and Release Form", from subcontractors and material suppliers evidencing payment in full for services, equipment and materials, as the case may require, if the Owner approves, or a consent from the Surety to final payment accepting liability for any unpaid amounts.
  - b) An Affidavit of Compliance with Prevailing Wage Law, in the form as included in this contract specifications, properly executed by each subcontractor, and the Contractor
  - c) Certified copies of all payrolls
  - d) As-built drawings
- 3. If any claim remains unsatisfied after all payments are made, the Contractor shall refund to the Owner all monies that the latter may be compelled to pay in discharging such a claim including all costs and a reasonable attorney's fee.
- 4. Missouri statute requires prompt payment from the Owner to the Contractor within thirty calendar days and from the Contractor to his subcontractors within fifteen calendar days. Failure to make payments within the required

- time frame entitles the receiving party to charge interest at the rate of one and one half percent per month calculated from the expiration of the statutory time period until paid.
- 5. The value of all unused unit price allowances and/or 150% of the value of the outstanding work items, and/or liquidated damages may be deducted from the final pay request without executing a Contract Change. Any unit price items which exceed the number of units in the contract may be added by Contract Change.

#### ARTICLE 6 -- INSURANCE AND BONDS

#### ARTICLE 6.1 -- BOND

- A. Contractor shall furnish a performance/payment bond in an amount equal to 100% of the contract price to guarantee faithful performance of the contract and 100% of the contract price to guarantee the payment of all persons performing labor on the project and furnishing materials in connection therewith under this contract as set forth in the standard form of performance and payment bond included in the contract documents. The surety on such bond shall be issued by a surety company authorized by the Missouri Department of Insurance to do business in the state of Missouri.
- B. All Performance/Payment Bonds furnished in response to this provision shall be provided by a bonding company with a rating of B+ or higher as established by A.M. Best Company, Inc. in their most recent publication.

#### **ARTICLE 6.2 – INSURANCE**

A. The successful Contractor shall procure and maintain for the duration of the contract issued a policy or policies of insurance for the protection of both the Contractor and the Owner and their respective officers, officials, agents, consultants and employees. The Owner requires certification of insurance coverage from the Contractor prior to commencing work.

#### B. Minimum Scope and Extent of Coverage

#### 1. General Liability

Commercial General Liability, ISO coverage form number or equivalent CG 00 01 ("occurrence" basis), or I-SO coverage form number CG 00 02, or ISO equivalent.

If ISO equivalent or manuscript general liability coverage forms are used, minimum be coverage will as follows: Premises/Operations; Independent Contractors; Products/Completed Operations; personal Injury; Broad Form Property Damage including Completed Operations; Broad Form Contractual Liability Coverage to include Contractor's obligations under Article 1.11 Indemnification and any other Special Hazards required by the work of the contract.

#### 2. Automobile Liability

Business Automobile Liability Insurance, ISO Coverage form number or equivalent CA 00 01 covering automobile liability, code 1 "ANY AUTO".

3. Workers' Compensation and Employer's Liability

Statutory Workers' Compensation Insurance for Missouri and standard Employer's Liability Insurance, or the authorization to self-insure for such liability from the Missouri Division of Workers' Compensation.

4. Builder's Risk or Installation Floater Insurance

Insurance upon the work and all materials, equipment, supplies, temporary structures and similar items which may be incident to the performance of the work and located at or adjacent to the site, against loss or damage from fire and such other casualties as are included in extended coverage in broad "All Risk" form, including coverage for Flood and Earthquake, in an amount not less than the replacement cost of the work or this contact price, whichever is greater, with loss payable to Contractor and Owner as their respective interests may appear.

Contractor shall maintain sufficient insurance to cover the full value of the work and materials as the work progresses, and shall furnish Owner copies of all endorsements. If Reporting-Builder's Risk Form Endorsement is used. Contractor shall make all reports as required therein so as to keep in force an amount of insurance which will equal the replacement cost of the work, materials, equipment, supplies, temporary structures, and other property covered thereby; and if, as a result of Contractor's failure to make any such report, the amount of insurance so recoverable shall be less than such replacement cost. Contractor's interest in the proceeds of such insurance, if any, shall be subordinated to Owner's interest to the end that Owner may receive full reimbursement for its loss.

#### C. Minimum Limits of Insurance

1. General Liability

Contractor

\$2,000,000 combined single limit per occurrence for bodily injury, personal injury, and

personal injury, property damage

\$2,000,000 annual aggregate

2. Automobile Liability

\$2,000,000 combined single limit per occurrence for bodily injury and property damage

3. Workers' Compensation and Employers Liability

Workers' Compensation limits as required by applicable State Statutes (generally unlimited) and minimum of \$1,000,000 limit per accident for Employer's Liability.

General Liability and Automobile Liability insurance may be arranged under individual policies for the full limits required or by a combination of underlying policies with the balance provided by a form-following Excess or Umbrella Liability policy.

#### D. Deductibles and Self-Insured Retentions

All deductibles, co-payment clauses, and self-insured retentions must be declared to and approved by the Owner. The Owner reserves the right to request the reduction or elimination of unacceptable deductibles or self-insured retentions, as they would apply to the Owner, and their respective officers, officials, agents, consultants and employees. Alternatively, the Owner may request Contractor to procure a bond guaranteeing

payment of losses and related investigations, claims administration, and defense expenses.

#### E. Other Insurance Provisions and Requirements

The respective insurance policies and coverage, as specified below, must contain, or be endorsed to contain the following conditions or provisions:

#### 1. General Liability

The Owner, and its respective commissioners, officers, officials, agents, consultants and employees shall be endorsed as additional insured's by ISO form CG 20 26 Additional Insured - Designated Person or Organization. As additional insured's, they shall be covered as to work performed by or on behalf of the Contractor or as to liability which arises out of Contractor's activities or resulting from the performance of services or the delivery of goods called for by the Contract.

Contractor's insurance coverage shall be primary with respect to all additional insured's. Insurance of self-insurance programs maintained by the designated additional -insured's shall be excess of the Contractor's insurance and shall not contribute with it.

Additionally, the Contractor and Contractor's general liability insurer shall agree to waive all rights of subrogation against the Owner and any of their respective officers, officials, agents, consultants or employees for claims, losses, or expenses which arise out of Contractor's activities or result from the performance of services or the delivery of goods called for by the Contract.

Contractor's failure to comply with the terms and conditions of these insurance policies shall not affect or abridge coverage for the Owner, or for any of their officers, officials, agents, consultants or employees.

#### 2. Automobile Insurance

The Owner, and their respective officers, officials, agents, consultants and employees shall be endorsed as additional insured's by ISO form CG 20 26 - Additional Insured Designated Person or Organization. As additional insured's, they shall be covered as to work performed by or on behalf of the Contractor or as to liability which arises out of Contractor's activities or resulting from the performance of services or the delivery of goods called for by the Contract.

Contractor's insurance coverage shall be primary with respect to all additional insured's. Insurance or self-insurance

programs maintained by the designated additional insured's shall be in excess of the Contractor's insurance and shall not contribute with it

Additionally, the Contractor and Contractor's automobile insurer shall agree to waive all rights of subrogation against the Owner and any of their respective officers, officials, agents, consultants or employees for claims, losses, or expenses which arise out of Contractor's activities or result from the performance of services or the delivery of goods called for by the Contract.

Contractor's failure to comply with the terms and conditions of these insurance policies shall not affect or abridge coverage for the Owner or for any of its officers, officials, agents, consultants or employees.

#### 3. Workers' Compensation/Employer's Liability

Contractor's workers' compensation insurance shall be endorsed with NCCI form WC 00 03 01 A - Alternative Employer Endorsement. The Alternative Employer Endorsement shall designate the Owner as "alternate employers."

#### 4. All Coverages

Each insurance policy required by this section of the Contract shall contain a stipulation, endorsed if necessary, that the Owner will receive a minimum of a thirty (30) calendar day advance notice of any policy cancellation. Ten (10) calendar days advance notice is required for policy cancellation due to non-payment of premium.

#### F. Insurer Qualifications and Acceptability

Insurance required hereunder shall be issued by an A.M. Best, "B+" rated, Class IX insurance company approved to conduct insurance business in the state of Missouri.

#### G. Verification of Insurance Coverage

Prior to Owner issuing a Notice to Proceed, the Contractor-shall furnish the Owner with Certificate(s) of Insurance and with any applicable original endorsements evidencing the required insurance coverage. The insurance certificates and endorsements are to be signed by a person authorized by that insurer to bind coverage on its behalf. All certificates and endorsements received by the Owner are subject to review and approval by the Owner. The Owner reserves the right to require certified copies of all required policies at any time. If the scope of this contract will exceed one (1) year - or, if any of Contractor's applicable insurance coverage expires prior to completion of the work or services required under this contract -

the Contractor will provide a renewal or replacement certificate before continuing work or services hereunder. If the Contractor fails to provide documentation of required insurance coverage, the Owner may issue a stop work order and no additional contract completion time and/or compensation shall be granted as a result thereof.

### ARTICLE 7 – SUSPENSION OR TERMINATION OF CONTRACT

#### **ARTICLE 7.1 - FOR SITE CONDITIONS**

When conditions at the site of the proposed work are considered by the Owner to be unsatisfactory for prosecution of the work, the Contractor may be ordered in writing to suspend the work or any part thereof until reasonable conditions exist. When such suspension is not due to fault or negligence of the Contractor, time allowed for completion of such suspended work will be extended by a period of time equal to that lost due to delay occasioned by ordered suspension. This will be a no cost time extension.

#### **ARTICLE 7.2 - FOR CAUSE**

- A. Termination or Suspension for Cause:
  - If the Contractor shall file for bankruptcy, or should make a general assignment for the benefit of the creditors, or if a receiver should be appointed on account of insolvency, or if contractor should persistently or repeatedly refuse or fail to supply enough properly skilled workers or proper materials, or if the contractor should fail to make prompt payment to subcontractors or for material or labor, or persistently disregard laws, ordinances or the instructions of the Owner, or otherwise be guilty of a substantial violation of any provision of this contract, then the Owner may serve notice on the Contractor and the surety setting forth the violations and demanding compliance with this contract. Unless within ten (10) consecutive calendar days after serving such notice, such violations shall cease and satisfactory arrangements for correction be made, the Owner may suspend the Contractor's right to proceed with the work or terminate this contract.
  - 2. In the event the Owner suspends Contractor's right to proceed with the work or terminates the contract, the Owner may demand that the Contractor's surety take over and complete the work on this contract, after the surety submits a written proposal to the Owner and receives written approval and upon the surety's failure or refusal to do so within ten (10) consecutive

- calendar days after demand therefore, the Owner may take over the work and prosecute the same to completion by bid or negotiated contract, or the Owner may elect to take possession of and utilize in completing the work such materials, supplies, appliances and plant as may be on the site of the work, and all subcontractors, if the Owner elects, shall be bound to perform their contracts.
- B. The Contractor and its surety shall be and remain liable to the Owner for any excess cost or damages occasioned to the Owner as a result of the actions above set forth.
- C. The Contractor in the event of such suspension or termination shall not be entitled to receive any further payments under this contract until the work is wholly finished. Then if the unpaid balance under this contract shall exceed all expenses of the Owner as certified by the Director, such excess shall be paid to the Contractor; but, if such expenses shall exceed the unpaid balance as certified by the Director, the Contractor and their surety shall be liable for and shall pay the difference and any damages to the Owner.
- D. In exercising Owner's right to secure completion of the work under any of the provisions hereof, the Director shall have the right to exercise Owner's sole discretion as to the manner, methods and reasonableness of costs of completing the work.
- E. The rights of the Owner to suspend or terminate as herein provided shall be cumulative and not exclusive and shall be in addition to any other remedy provided by law.
- The Contractor in the event of such suspension or termination may be declared ineligible for Owner contracts for a minimal period of twelve (12) months. Further, no contract will be awarded to any Contractor who lists in their bid form any subcontractor whose prior performance has contributed, as determined by the Owner, to a breach of a contract. In order to be considered for state-awarded contracts after this period, the Contractor/subcontractor will be required to forward acceptance reports to the Owner regarding successful completion of non-state projects during the intervening twelve (12) months from the date of default. No contracts will be awarded to a subcontractor/Contractor until the ability to perform responsibly in the private sector has been proven to the Owner.

#### **ARTICLE 7.3 -- FOR CONVENIENCE**

A. The Owner may terminate or suspend the Contract or any portion of the Work without cause at any time, and at the Owner's convenience. Notification of a termination or suspension shall be in writing

and shall be given to the Contractor and their surety. If the Contract is suspended, the notice will contain the anticipated duration of the suspension or the conditions under which work will be permitted to resume. If appropriate, the Contractor will be requested to demobilize and re-mobilize and will be reimbursed time and costs associated with the suspension.

- B. Upon receipt of notification, the Contractor shall:
  - 1. Cease operations when directed.
  - 2. Take actions to protect the work and any stored materials.
  - Place no further subcontracts or orders for material, supplies, services or facilities except as may be necessary to complete the portion of the Contract that has not been terminated. No claim for payment of materials or supplies ordered after the termination date shall be considered.
  - 4. Terminate all existing subcontracts, rentals, material, and equipment orders.

- 5. Settle all outstanding liabilities arising from termination with subcontractors and suppliers.
- 6. Transfer title and deliver to the Owner, work in progress, completed work, supplies and other material produced or acquire for the work terminated, and completed or partially completed plans, drawings information and other property that, if the Contract had been completed, would be required to be furnished to the Owner.
- C. For termination without cause and at the Owner's convenience, in addition to payment for work completed prior to date of termination, the Contractor may be entitled to payment of other documented costs directly associated with the early termination of the contract. Payment for anticipated profit and unapplied overhead will not be allowed.

#### SECTION 007300 - SUPPLEMENTARY CONDITIONS

#### 1.0 GENERAL:

A. These Supplementary General Conditions clarify, add, delete, or otherwise modify standard terms and conditions of DIVISION 0, BIDDING AND CONTRACTING REQUIREMENTS.

#### 2.0 CONTACTS:

Designer: Brad M. Schaefer

State of Missouri Office of Administration Division of Facilities

Management Design And Construction

301 West High Street Jefferson City, MO 65101 Telephone: 573-526-0136 Email: Brad.Schaefer@oa.mo.gov

Construction Representative: Carl Haley

Division of Facilities Management, Design and Construction

709 Missouri Blvd (Upper Level) Jefferson City, MO 65109 Telephone: 573-526-0473 Email: Carl.Haley@oa.mo.gov

Project Manager: Andy Carroll

Division of Facilities Management, Design and Construction

301 West High Street, Room 730 Jefferson City, Missouri 65101 Telephone: 573-751-8913 Email: Andy.Carroll@oa.mo.gov

Contract Specialist: Mandy Roberson

Division of Facilities Management, Design and Construction

301 West High Street, Room 730 Jefferson City, Missouri 65101 Telephone: 573-230-6724

Email: mandy.roberson@oa.mo.gov

# 3.0 NOTICE: ALL BID MATERIALS ARE DUE AT THE TIME OF BID SUBMITTAL. THERE IS NO SECOND SUBMITTAL FOR THIS PROJECT.

#### 4.0 FURNISHING CONSTRUCTION DOCUMENTS:

- A. The Owner will furnish the Contractor with approximately 3 complete sets of drawings and specifications at no charge.
- B. The Owner will furnish the Contractor with approximately 3 sets of explanatory or change drawings at no charge.
- C. The Contractor may make copies of the documents as needed with no additional cost to the Owner.

#### 5.0 SAFETY REQUIREMENTS

Contractor and subcontractors at any tier shall comply with RSMo 292.675 and Article 1.3, E, of Section 007213, General Conditions.

# Missouri Division of Labor Standards

WAGE AND HOUR SECTION



MICHAEL L. PARSON, Governor

# Annual Wage Order No. 31

Section 026
COLE COUNTY

In accordance with Section 290.262 RSMo 2000, within thirty (30) days after a certified copy of this Annual Wage Order has been filed with the Secretary of State as indicated below, any person who may be affected by this Annual Wage Order may object by filing an objection in triplicate with the Labor and Industrial Relations Commission, P.O. Box 599, Jefferson City, MO 65102-0599. Such objections must set forth in writing the specific grounds of objection. Each objection shall certify that a copy has been furnished to the Division of Labor Standards, P.O. Box 449, Jefferson City, MO 65102-0449 pursuant to 8 CSR 20-5.010(1). A certified copy of the Annual Wage Order has been filed with the Secretary of State of Missouri.

Original Signed by

Todd Smith, Director Division of Labor Standards

Filed With Secretary of State: March 8, 2024

Last Date Objections May Be Filed: April 8, 2024

Prepared by Missouri Department of Labor and Industrial Relations

	**Prevailing	
OCCUPATIONAL TITLE	Hourly	
OCCOPATIONAL TITLE	Rate	
Ashastas Warker	\$62.47	
Asbestos Worker Boilermaker		
Bricklayer-Stone Mason	\$30.53*	
	\$54.17 \$50.84	
Carpenter	\$50.84	
Lather		
Linoleum Layer		
Millwright		
Pile Driver		
Cement Mason	\$43.74	
Plasterer		
Communication Technician	\$57.89	
Electrician (Inside Wireman)	\$58.31	
Electrician Outside Lineman	\$30.53*	
Lineman Operator		
Lineman - Tree Trimmer		
Groundman		
Groundman - Tree Trimmer		
Elevator Constructor	\$30.53*	
Glazier	\$56.48	
Ironworker	\$68.93	
Laborer	\$43.22	
General Laborer		
First Semi-Skilled		
Second Semi-Skilled		
Mason	\$30.53*	
Marble Mason	·	
Marble Finisher		
Terrazzo Worker		
Terrazzo Finisher		
Tile Setter		
Tile Finisher		
Operating Engineer	\$67.64	
Group I		
Group II		
Group III		
Group III-A		
Group IV		
Group V		
Painter	\$42.11	
Plumber	\$70.54	
Pipe Fitter	Ψ7 0.04	
Roofer	\$54.75	
Sheet Metal Worker	\$57.54	
Sprinkler Fitter	\$52.79	
Truck Driver	\$30.53*	
Truck Control Service Driver	Ψου.σο	
Group I		
Group II		
Group III		
Group IV		
Oroup IV	<u> </u>	

<sup>\*</sup>The Division of Labor Standards received fewer than 1,000 reportable hours for this occupational title. The public works contracting minimum wage is established for this occupational title using data provided by Missouri Economic Research and Information Center.

\*\*The Prevailing Hourly Rate includes any applicable fringe benefit amounts for each occupational title as defined in RSMo Section 290.210.

OCCUPATIONAL TITLE	**Prevailing
OCCUPATIONAL TITLE	Hourly
	Rate
Carpenter	\$55.19
Millwright	
Pile Driver	
Electrician (Outside Lineman)	\$80.11
Lineman Operator	
Lineman - Tree Trimmer	
Groundman	
Groundman - Tree Trimmer	
Laborer	\$48.42
General Laborer	
Skilled Laborer	
Operating Engineer	\$63.82
Group I	
Group II	
Group III	
Group IV	
Truck Driver	\$48.68
Truck Control Service Driver	
Group I	
Group II	
Group III	
Group IV	

Use Heavy Construction Rates on Highway and Heavy construction in accordance with the classifications of construction work established in 8 CSR 30-3.040(3).

Use Building Construction Rates on Building construction in accordance with the classifications of construction work established in 8 CSR 30-3.040(2).

If a worker is performing work on a heavy construction project within an occupational title that is not listed on the Heavy Construction Rate Sheet, use the rate for that occupational title as shown on the Building Construction Rate Sheet.

<sup>\*</sup>The Division of Labor Standards received fewer than 1,000 reportable hours for this occupational title. Public works contracting minimum wage is established for this occupational title using data provided by Missouri Economic Research and Information Center.

<sup>\*\*</sup>The Prevailing Hourly Rate includes any applicable fringe benefit amounts for each occupational title.

# OVERTIME and HOLIDAYS

#### **OVERTIME**

For all work performed on a Sunday or a holiday, not less than twice (2x) the prevailing hourly rate of wages for work of a similar character in the locality in which the work is performed or the public works contracting minimum wage, whichever is applicable, shall be paid to all workers employed by or on behalf of any public body engaged in the construction of public works, exclusive of maintenance work.

For all overtime work performed, not less than one and one-half (1½) the prevailing hourly rate of wages for work of a similar character in the locality in which the work is performed or the public works contracting minimum wage, whichever is applicable, shall be paid to all workers employed by or on behalf of any public body engaged in the construction of public works, exclusive of maintenance work or contractual obligation. For purposes of this subdivision, "overtime work" shall include work that exceeds ten hours in one day and work in excess of forty hours in one calendar week; and

A thirty-minute lunch period on each calendar day shall be allowed for each worker on a public works project, provided that such time shall not be considered as time worked.

#### **HOLIDAYS**

January first;
The last Monday in May;
July fourth;
The first Monday in September;
November eleventh;
The fourth Thursday in November; and December twenty-fifth;

If any holiday falls on a Sunday, the following Monday shall be considered a holiday.

#### SECTION 011000 SUMMARY OF WORK

#### **PART 1 GENERAL**

#### 1.01 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract including General and Supplementary Conditions and Division 1 Specification Sections apply to this Section.

#### 1.02 WORK COVERED BY CONTRACT DOCUMENTS

- A. The Project consists of Howerton Interior Renovation Project.
  - 1. Project Location: Howerton State Office Building, First and Second Floor, 615 Howerton Court, Jefferson City, Missouri, 65109.
  - 2. Owner: State of Missouri, Office of Administration, Division of Facilities Management, Design and Construction, Harry S Truman State Office Building, Post Office Box 809, 301 West High Street, Jefferson City, Missouri 65102.
- B. Contract Documents, dated 12/13/2024 were prepared for the Project by Interior Design Unit: 301 West High Street, Jefferson City, MO 65102.
- C. The Work consists of the Base Bid of Howerton Interior Renovation Project.
  - 1. The Work includes restroom updates, paint, door replacements, first and second floor lobby modifications and updates, as well as creating a new conference room and two storage rooms.
  - 2. The Work includes selective demolition and renovation of fire sprinkler system.
  - 3. The Work includes replacement and integration of ceiling mounted fire alarm strobes and smoke detectors into the existing fire protection system.
  - 4. The Work includes replacement of restroom plumbing fixtures and adjustment of water supply inlet for urinal and water closet installation.
  - 5. The Work includes replacement of air devices and modification of any associated duct.
  - 6. The Work includes replacement of lighting fixtures and extension of lighting circuit, installation of new feature light, and replacement of all wiring devices located within area of work.
  - 7. The Work includes replacement of ADA door operators and associated push plates.
- D. The Work will be constructed under a single prime contract.

#### 1.03 CONTRACTOR USE OF PREMISES

- A. General: During the construction period the Contractor shall have full use of the premises for construction operations, including use of the site. The Contractor's use of the premises limited only by the Owner's right to perform work or to retain other contractors on portions of the Project.
- B. Use of the Site: Limit use of the premises to work in areas indicated. Confine operations to areas within contract limits indicated. Do not disturb portions of the site beyond the areas in which the Work is indicated.
  - 1. Owner Occupancy: Allow for Owner occupancy and use by the public.
  - 2. Driveways and Entrances: Keep driveways and entrances serving the premises clear and available to the Owner, the Owner's employees, and emergency vehicles at all times. Do not use these areas for parking or storage of materials. Schedule deliveries to minimize space and time requirements for storage of materials and equipment on-site.
- C. Use of the Existing Building: Maintain the existing building in a weathertight condition throughout the construction period. Repair damage cause by construction operations. Take all precautions necessary to protect the building and its occupants during the construction period.

#### 1.04 OCCUPANCY REQUIREMENTS

A. Full Owner Occupancy: The Owner will occupy the site and existing building during the entire construction period. Cooperate with the Owner during construction operations to minimize conflicts and facilitate owner usage. Perform the Work so as not to interfere with the Owner's operations.

- B. Partial Owner Occupancy: The Owner reserves the right to occupy and to place and install equipment in completed areas of the building prior to Substantial Completion, provided such occupancy does not interfere with completion of the Work. Such placing of equipment and partial occupancy shall not constitute acceptance of the total Work.
  - 1. The Designer will prepare a Certificate of Partial Occupancy for each specific portion of the Work to be occupied prior to substantial completion.
  - 2. Prior to partial Owner occupancy, mechanical and electrical systems shall be fully operational. Required inspections and tests shall have been successfully completed. Upon occupancy, the Owner will operate and maintain mechanical and electrical systems serving occupied portions for the building.
  - 3. Upon occupancy, the Owner will assume responsibility for maintenance and custodial service for occupied portions for the building.

1.05 MISCELLANEOUS PROVISIONS
PART 2 PRODUCTS (NOT APPLICABLE)
PART 3 EXECUTION
3.01 SCHEDULE OF PRODUCTS ORDERED IN ADVANCE
END OF SECTION

#### SECTION 012600 CONTRACT MODIFICATION PROCEDURES

#### **PART 1 GENERAL**

#### 1.01 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract including General and Supplementary Conditions and other Division 1 Specification Sections apply to this Section.

#### 1.02 SUMMARY

- A. This Section specifies administrative and procedural requirements for handling and processing Contract Modifications.
- B. Related Sections include the following:
  - Division 1, Section 012100 "Allowances" for procedural requirements for handling and processing Allowances.
  - 2. Division 1, Section 012200 "Unit Prices" for administrative requirements for using Unit Prices.
  - 3. Division 1, Section 013115 "Project Management Communications" for administrative requirements for communications.
  - 4. Division 0, Section 007213, Article 3.1 "Acceptable Substitutions" for administrative procedures for handling Requests for Substitutions made after Contract award.
  - 5. Division 0, Section 007213, Article 4.0 "Changes in the Work" for Change Order requirements.

#### 1.03 REQUESTS FOR INFORMATION

- A. In the event that the Contractor or Subcontractor, at any tier, determines that some portion of the Drawings, Specifications, or other Contract Documents requires clarification or interpretation, the Contractor shall submit a "Request for Information" (RFI) in writing to the Designer. A RFI may only be submitted by the Contractor and shall only be submitted on the RFI forms provided by the Owner. The Contractor shall clearly and concisely set forth the issue for which clarification or interpretation is sought and why a response is needed. In the RFI, the Contractor shall set forth an interpretation or understanding of the requirement along with reasons why such an understanding was reached.
- B. Responses to RFI shall be issued within ten (10) working days of receipt of the Request from the Contractor unless the Designer determines that a longer time is necessary to provide an adequate response. If a longer time is determined necessary by the Designer, the Designer will, within five (5) working days of receipt of the request, notify the Contractor of the anticipated response time. If the Contactor submits a RFI on a time sensitive activity on the current project schedule, the Contractor shall not be entitled to any time extension due to the time it takes the Designer to respond to the request provided that the Designer responds within the ten (10) working days set forth above.
- C. Responses from the Designer will not change any requirement of the Contract Documents. In the event the Contractor believes that a response to a RFI will cause a change to the requirements of the Contract Document, the Contractor shall give written notice to the Designer requesting a Change Order for the work. Failure to give such written notice within ten (10) working days, shall waive the Contractor's right to seek additional time or cost under Article 4, "Changes in the Work" of the General Conditions.

#### 1.04 MINOR CHANGES IN THE WORK

A. Designer will issue supplemental instructions authorizing Minor Changes in the Work, not involving adjustment to the Contract Amount or the Contract Time, on "Designer's Supplemental Instructions" (DSI).

#### 1.05 PROPOSAL REQUESTS

A. The Designer or Owner Representative will issue a detailed description of proposed Changes in the Work that may require adjustment to the Contract Amount or the Contract Time. The proposed Change Description will be issued using the "Request for Proposal" (RFP) form. If necessary, the description will include supplemental or revised Drawings and Specifications.

- 1. Proposal Requests issued by the Designer or Owner Representative are for information only. Do not consider them instructions either to stop work in progress or to execute the proposed change.
- Within ten (10) working days after receipt of Proposal Request, submit a proposal for the cost adjustments to the Contract Amount and the Contract Time necessary to execute the Change. The Contractor shall submit his proposal on the appropriate Change Order Detailed Breakdown form. Subcontractors may use the appropriate Change Order Detailed Breakdown form or submit their proposal on their letterhead provided the same level of detail is included. All proposals shall include:
  - a. A detailed breakdown of costs per Article 4.1 of the General Conditions.
  - b. If requesting additional time per Article 4.2 of the General Conditions, include an updated Contractor's Construction Schedule that indicates the effect of the Change including, but not limited to, changes in activity duration, start and finish times, and activity relationship.

#### 1.06 CHANGE ORDER PROCEDURES

A. On Owner's approval of a Proposal Request, the Designer or Owner Representative will issue a Change Order for signatures of Owner and Contractor on the "Change Order" form.

PART 2 PRODUCTS (NOT USED)
PART 3 EXECUTION (NOT USED)

**END OF SECTION** 

#### SECTION 013100 COORDINATION

#### **PART 1 GENERAL**

#### 1.01 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract including General and Supplementary Conditions and other Division 1 Specification Sections apply to this Section.

#### 1.02 SUMMARY

- A. This Section includes administrative provisions for coordinating construction operations on Projects including, but not limited to, the following:
  - 1. Coordination Drawings.
  - 2. Administrative and supervisory personnel.
  - 3. Project meetings.
- B. Each Contractor shall participate in coordination requirements. Certain areas of responsibility will be assigned to a specific Contractor.
- C. Related Sections include the following:
  - Division 1, Section 013200 "Schedules" for preparing and submitting Contractor's Construction Schedule.
  - 2. Articles 1.8.B and 1.8.C of Section 007213 "General Conditions" for coordinating meetings onsite.
  - 3. Article 5.4.H of Section 007213 "General Conditions" for coordinating Closeout of the Contract.

#### 1.03 COORDINATION

- A. Coordination: Coordinate construction operations included in different Sections of the Specifications to ensure efficient and orderly installation of each part of the Work. Coordinate construction operations included in different Sections, which depend on each other for proper installation, connection, and operation.
- B. Coordination: Each Contractor shall coordinate its construction operations with those of other contractors and entities to ensure efficient and orderly installation of each part of the Work. Each Contractor shall coordinate its operations with operations included in different Sections that depend on each other for proper installation, connection, and operation.
  - 1. Schedule construction operations in sequence required to obtain the best results where installation of one part of the Work depends on installation of other components, before or after its own installation.
  - 2. Coordinate installation of different components with other Contractors to ensure maximum accessibility for required maintenance, service, and repair.
  - 3. Make adequate provisions to accommodate items scheduled for later installation.
  - 4. Where availability of space is limited, coordinate installation of different components to ensure maximum performance and accessibility for required maintenance, service, and repair of all components including mechanical and electrical.
- C. Prepare memoranda for distribution to each party involved outlining special procedures required for coordination. Include such items as required notices, reports, and list of attendees at meetings.
  - 1. Prepare similar memoranda for Owner and separate Contractors if coordination of their Work is required.
- D. Administrative Procedures: Coordinate scheduling and timing of required administrative procedures with other construction activities and activities of other Contractors to avoid conflicts and to ensure orderly progress of the Work. Such administrative activities include, but are not limited to, the following:
  - 1. Preparation of Contractor's Construction Schedule.
  - 2. Preparation of the Schedule of Values.
  - 3. Installation and removal of temporary facilities and controls.
  - 4. Delivery and processing of submittals.

- 5. Progress meetings.
- 6. Preinstallation conferences.
- 7. Startup and adjustment of systems.
- 8. Project Closeout activities.
- E. Conservation: Coordinate construction activities to ensure that operations are carried out with consideration given to conservation of energy, water, and materials.
  - 1. Salvage materials and equipment involved in performance of, but not actually incorporated into, the Work. Refer to other Sections for disposition of salvaged materials that are designated as Owner's property.

#### 1.04 SUBMITTALS

- A. Coordination Drawings: Prepare Coordination Drawings if limited space availability necessitates maximum utilization of space for efficient installation of different components or if coordination is required for installation of products and materials fabricated by separate entities.
- B. Key Personnel Names: Within fifteen (15) work days of starting construction operations, submit a list of key personnel assignments including superintendent and other personnel in attendance at Project site. Identify individuals and their duties and responsibilities; list addresses and telephone numbers including home and office telephone numbers. Provide names, addresses, and telephone numbers of individuals assigned as standbys in the absence of individuals assigned to Project.
  - 1. Post copies of list in Project meeting room, in temporary field office, and by each temporary telephone. Keep list current at all times.

#### 1.05 PROJECT MEETINGS

- A. The Owner's Construction Representative will schedule a Pre-Construction Meeting prior to beginning of construction. The date, time, and exact place of this meeting will be determined after Contract Award and notification of all interested parties. The Contractor shall arrange to have the Job Superintendent and all prime Subcontractors present at the meeting. During the Pre-Construction Meeting, the construction procedures and information necessary for submitting payment requests will be discussed and materials distributed along with any other pertinent information.
  - 1. Minutes: Designer will record and distribute meeting minutes.
- B. Progress Meetings: The Owner's Construction Representative will conduct Monthly Progress Meetings as stated in Articles 1.8.B and 1.8.C of Section 007213 "General Conditions".
  - 1. Minutes: Designer will record and distribute to Contractor the meeting minutes.
- C. Preinstallation Conferences: Contractor shall conduct a preinstallation conference at Project site before each construction activity that requires coordination with other construction.
  - Attendees: Installer and representatives of Manufacturers and Fabricators involved in or affected by the installation and its coordination or integration with other materials and installations that have preceded or will follow, shall attend the meeting. Advise Designer and Construction Representative of scheduled meeting dates.
  - 2. Agenda: Review progress of other construction activities and preparations for the particular activity under consideration including requirements for the following:
    - a. Contract Documents
    - b. Options
    - c. Related RFIs
    - d. Related Change Orders
    - e. Purchases
    - f. Deliveries
    - g. Submittals
    - h. Review of mockups
    - i. Possible conflicts
    - j. Compatibility problems
    - k. Time schedules

- l. Weather limitations
- m. Manufacturer's written recommendations
- n. Warranty requirements
- o. Compatibility of materials
- p. Acceptability of substrates
- q. Temporary facilities and controls
- r. Space and access limitations
- s. Regulations of authorities having jurisdiction
- t. Testing and inspecting requirements
- u. Installation procedures
- v. Coordination with other Work
- w. Required performance results
- x. Protection of adjacent Work
- y. Protection of construction and personnel
- 3. Contractor shall record significant conference discussions, agreements, and disagreements including required corrective measures and actions.
- 4. Reporting: Distribute minutes of the meeting to each party present and to parties who should have been present.
- 5. Do not proceed with installation if the conference cannot be successfully concluded. Initiate whatever actions are necessary to resolve impediments to performance of the Work and reconvene the conference at earliest feasible date.
- 6. Revise paragraph below if Project requires holding progress meetings at different intervals. Insert special intervals such as "every third Tuesday" to suit special circumstances.
- 7. Project name
- 8. Name and address of Contractor
- 9. Name and address of Designer
- 10. RFI number including RFIs that were dropped and not submitted
- 11. RFI description
- 12. Date the RFI was submitted
- 13. Date Designer's response was received
- 14. Identification of related DSI or Proposal Request, as appropriate

#### **PART 2 PRODUCTS (NOT USED)**

#### **PART 3 EXECUTION (NOT USED)**

#### **END OF SECTION**

# SECTION 013115 PROJECT MANAGEMENT COMMUNICATIONS

#### **PART 1 GENERAL**

#### 1.01 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract including General and Supplementary Conditions, Bid Form, and other Division 1 Specification Sections apply to this Section.
- B. Division 1, Section 013300 Submittals
- C. Division 1, Section 012600 Contract Modification Procedures

#### 1.02 SUMMARY

- A. Project Management Communications: The Contractor shall use the Internet web based project management communications tool, E-Builder® ASP software, and protocols included in that software during this project. The use of project management communications as herein described does not replace or change any contractual responsibilities of the participants.
  - 1. Project management communications is available through E-Builder® as provided by "e-Builder®" in the form and manner required by the Owner.
  - 2. The project communications database is on-line and fully functional. User registration, electronic and computer equipment, and Internet connections are the responsibility of each project participant. The sharing of user accounts is prohibited
- B. Support: E-Builder® will provide on-going support through on-line help files.
- C. Copyrights and Ownership: Nothing in this specification or the subsequent communications supersedes the parties' obligations and rights for copyright or document ownership as established by the Contract Documents. The use of CAD files, processes or design information distributed in this system is intended only for the project specified herein.
- D. Purpose: The intent of using E-Builder® is to improve project work efforts by promoting timely initial communications and responses. Secondly, to reduce the number of paper documents while providing improved record keeping by creation of electronic document files
- E. Authorized Users: Access to the web site will be by individuals who are authorized users.
  - 1. Individuals shall complete the E-Builder New Company/User Request Form located at the following web site: https://oa.mo.gov/facilities/vendor-links/contractor-forms. Completed forms shall be emailed to the following email address: OA.FMDCE-BuilderSupport@oa.mo.gov.
  - 2. Authorized users will be contacted directly and assigned a temporary user password.
  - 3. Individuals shall be responsible for the proper use of their passwords and access to data as agents of the company in which they are employed.
- F. Administrative Users: Administrative users have access and control of user licenses and all posted items. DO NOT POST PRIVATE OR YOUR COMPANY CONFIDENTIAL ITEMS IN THE DATABASE! Improper or abusive language toward any party or repeated posting of items intended to deceive or disrupt the work of the project will not be tolerated and will result in deletion of the offensive items and revocation of user license at the sole discretion of the Administrative User(s).
- G. Communications: The use of fax, email and courier communication for this project is discouraged in favor of using E-Builder® to send messages. Communication functions are as follows:
  - 1. Document Integrity and Revisions:
    - a. Documents, comments, drawings and other records posted to the system shall remain for the project record. The authorship time and date shall be recorded for each document submitted to the system. Submitting a new document or record with a unique ID, authorship, and time stamp shall be the method used to make modifications or corrections.
    - b. The system shall make it easy to identify revised or superseded documents and their predecessors.

c. Server or Client side software enhancements during the life of the project shall not alter or restrict the content of data published by the system. System upgrades shall not affect access to older documents or software.

#### 2. Document Security:

a. The system shall provide a method for communication of documents. Documents shall allow security group assignment to respect the contractual parties communication except for Administrative Users. DO NOT POST PRIVATE OR YOUR COMPANY CONFIDENTIAL ITEMS IN THE DATABASE!

#### 3. Document Integration:

a. Documents of various types shall be logically related to one another and discoverable. For example, requests for information, daily field reports, supplemental sketches and photographs shall be capable of reference as related records.

#### 4. Reporting:

a. The system shall be capable of generating reports for work in progress, and logs for each document type. Summary reports generated by the system shall be available for team members.

#### 5. Notifications and Distribution:

a. Document distribution to project members shall be accomplished both within the extranet system and via email as appropriate. Project document distribution to parties outside of the project communication system shall be accomplished by secure email of outgoing documents and attachments, readable by a standard email client.

#### 6. Required Document Types:

- a. RFI, Request for Information.
- b. Submittals, including record numbering by drawing and specification section.
- c. Transmittals, including record of documents and materials delivered in hard copy.
- d. Meeting Minutes.
- e. Application for Payments (Draft or Pencil).
- f. Review Comments.
- g. Field Reports.
- h. Construction Photographs.
- i. Drawings.
- j. Supplemental Sketches.
- k. Schedules.
- 1. Specifications.
- m. Request for Proposals
- n. Designer's Supplemental Instructions
- o. Punch Lists
- H. Record Keeping: Except for paper documents, which require original signatures and large format documents (greater than  $8\frac{1}{2}$  x 11 inches), all other  $8\frac{1}{2}$  x 11 inches documents shall be submitted by transmission in electronic form to the E-Builder® web site by licensed users.
  - 1. The Owner and his representatives, the Designer and his consultants, and the Contractor and his Sub Contractors and suppliers at every tier shall respond to documents received in electronic form on the web site, and consider them as if received in paper document form.
  - 2. The Owner and his representatives, the Designer and his consultants, and the Contractor and his Sub Contractors and suppliers at every tier reserves the right to and shall reply or respond by transmissions in electronic form on the web site to documents actually received in paper document form.
  - 3. The Owner and his representatives, the Designer and his consultants, and the Contractor and his Sub Contractors and suppliers at every tier reserves the right to and shall copy any paper document into electronic form and make same available on the web site.

- I. Minimum Equipment and Internet Connection: In addition to other requirements specified in this Section, the Owner and his representatives, the Construction Manager and his representatives, the Architect and his consultants, and the Contractor and his sub-contractors and suppliers at every tier required to have a user license(s) shall be responsible for the following:
  - 1. Providing suitable computer systems for each licensed user at the users normal work location with high-speed Internet access, i.e. DSL, local cable company's Internet connection, or T1 connection.
    - a. The normal work location is the place where the user is assigned for more than one-half of his time working on this project.
  - 2. Each of the above referenced computer systems shall have the following minimum system and software requirements:
    - a. The minimum system herein will not be sufficient for many tasks and may not be able to process all documents and files stored in the E-Builder® Documents area.
    - b. Desktop configuration (Laptop configurations are similar and should be equal to or exceed desktop system.)
      - 1) Operating System: Windows XP or newer
      - 2) Internet Browser: Internet Explorer 6.01SP2+ (Recommend IE7.0+)
      - 3) Minimum Recommend Connection Speed: 256K or above
      - 4) Processor Speed: 1 Gigahertz and above
      - 5) RAM: 512 mb
      - 6) Operating system and software shall be properly licensed.
      - 7) Internet Explorer version 7 (current version is a free distribution for download). This specification is not intended to restrict the host server or client computers provided that industry standard HTTP clients may access the published content.
      - 8) Adobe Acrobat Reader (current version is a free distribution for download).
      - 9) Users should have the standard Microsoft Office Suite (current version must be purchased) or the equivalent.

PART 2 PRODUCTS (NOT APPLICABLE)
PART 3 EXECUTION (NOT APPLICABLE.)

END OF SECTION

#### SECTION 013200 SCHEDULE – BAR CHART

#### **PART 1 GENERAL**

#### 1.01 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract including General and Supplementary Conditions, Bid Form, and other Division 1 Specification Sections apply to this Section.

#### 1.02 SUMMARY

A. This Section includes requirements for a Bar Chart Schedule for the project construction activities, schedule of submittals, and schedule for testing.

#### PART 2 PRODUCTS – (NOT APPLICABLE)

#### **PART 3 EXECUTION**

#### 3.01 SUBMITTAL PROCEDURES

- A. The Contractor shall submit to the Designer, within ten (10) working days following the Notice to Proceed, a Progress Schedule including Schedule of Values showing the rate of progress the Contractor agrees to maintain and the order in which he proposed to carry out the various phases of Work. No payments shall be made to the Contractor until the Progress Schedule has been approved by the Owner.
  - 1. The Schedule of Values must have the following line items included with the value of the item as indicated below:
    - a. O&M's (Owner's Manual)
      - 1) \$1,000,000.00 (One million) and under -2% of the total contract amount
      - 2) Over \$1,000,000.00 (One million) 1% of the total contract amount
    - b. Close Out Documents
      - 1) \$1,000,000.00 (One million) and under -2% of the total contract amount
      - 2) Over \$1,000,000.00 (One million) 1% of the total contract amount
    - c. General Conditions
      - 1) No more than 10%
- B. The Contractor shall submit an updated Schedule for presentation at each Monthly Progress Meeting. The Schedule shall be updated by the Contractor as necessary to reflect the current Schedule and its relationship to the original Schedule. The updated Schedule shall reflect any changes in the logic, sequence, durations, or completion date. Payments to the Contractor shall be suspended if the Progress Schedule is not adequately updated to reflect actual conditions.
- C. The Contractor shall submit Progress Schedules to Subcontractors to permit coordinating their Progress Schedules to the general construction Work. The Contractor shall coordinate preparation and processing of Schedules and reports with performance of other construction activities.

#### 3.02 CONSTRUCTION PROGRESS SCHEDULE – BAR CHART SCHEDULE

- A. Bar-Chart Schedule: The Contractor shall prepare a comprehensive, fully developed, horizontal bar chart-type Contractor's Construction Schedule. The Contractor for general construction shall prepare the Construction Schedule for the entire Project. The Schedule shall show the percentage of work to be completed at any time, anticipated monthly payments by Owner, as well as significant dates (such as completion of excavation, concrete foundation work, underground lines, superstructure, rough-ins, enclosure, hanging of fixtures, etc.) which shall serve as check points to determine compliance with the approved Schedule. The Schedule shall also include an activity for the number of "bad" weather days specified in Section 012100 Allowances.
  - 1. The Contractor shall provide a separate time bar for each significant construction activity. Provide a continuous vertical line to identify the first working day of each week.
    - a. If practical, use the same Schedule of Values breakdown for schedule time bars.

- 2. The Contractor shall provide a base activity time bar showing duration for each construction activity. Each bar is to indicate start and completion dates for the activity. The Contractor is to place a contrasting bar below each original schedule activity time for indicating actual progress and planned remaining duration for the activity.
- 3. The Contractor shall prepare the Schedule on a minimal number of separate sheets to readily show the data for the entire construction period.
- 4. Secure time commitments for performing critical elements of the Work from parties involved. Coordinate each element on schedule with other construction activities. Include minor elements involved in the overall sequence of the Work. Show each activity in proper sequence. Indicate graphically the sequences necessary for completion of related portions of the Work.
- 5. Coordinate the Contractor's Construction Schedule with the Schedule of Values, list of subcontracts, Submittal Schedule, progress reports, payment requests, and other required schedules and reports.
- 6. Indicate the Intent to Award and the Contract Substantial Completion dates on the schedule.
- B. Phasing: Provide notations on the schedule to show how the sequence of the Work is affected by the following:
  - 1. Requirement for Phased completion
  - 2. Work by separate Contractors
  - 3. Work by the Owner
  - 4. Pre-purchased materials
  - 5. Coordination with existing construction
  - 6. Limitations of continued occupancies
  - 7. Un-interruptible services
  - 8. Partial Occupancy prior to Substantial Completion
  - 9. Site restrictions
  - 10. Provisions for future construction
  - 11. Seasonal variations
  - 12. Environmental control
- C. Work Stages: Use crosshatched bars to indicate important stages of construction for each major portion of the Work. Such stages include, but are not necessarily limited to, the following:
  - 1. Subcontract awards
  - 2. Submittals
  - 3. Purchases
  - 4. Mockups
  - 5. Fabrication
  - 6. Sample testing
  - 7. Deliveries
  - 8. Installation
  - 9. Testing
  - 10. Adjusting
  - 11. Curing
  - 12. Startup and placement into final use and operation
- D. Area Separations: Provide a separate time bar to identify each major area of construction for each major portion of the Work. For the purposes of this Article, a "major area" is a story of construction, a separate building, or a similar significant construction element.
  - 1. Indicate where each construction activity within a major area must be sequenced or integrated with other construction activities to provide for the following:
    - a. Structural completion.
    - b. Permanent space enclosure
    - c. Completion of mechanical installation
    - d. Completion of the electrical portion of the Work

e. Substantial Completion

#### 3.03 SCHEDULE OF SUBMITTALS

- A. Upon acceptance of the Construction Progress Schedule, prepare and submit a complete schedule of submittals. Coordinate the submittal schedule with Section 013300 SUBMITTALS, the approved Construction Progress Schedule, list of subcontracts, Schedule of Values and the list of products.
- B. Prepare the schedule in chronological order. Provide the following information
  - 1. Scheduled date for the first submittal
  - 2. Related Section number
  - 3. Submittal category
  - 4. Name of the Subcontractor
  - 5. Description of the part of the Work covered
  - 6. Scheduled date for resubmittal
  - 7. Scheduled date for the Designer's final release or approval
- C. Distribution: Following the Designer's response to the initial submittal schedule, print and distribute copies to the Designer, Owner, subcontractors, and other parties required to comply with submittal dates indicated.
  - 1. Post copies in the Project meeting room and temporary field office.
  - 2. When revisions are made, distribute to the same parties and post in the same locations. Delete parties from distribution when they have completed their assigned part of the Work and are no longer involved in construction activities.
- D. Schedule Updating: Revise the schedule after each meeting or other activity where revisions have been recognized or made. Issue the updated schedule concurrently with the report of each meeting.

#### 3.04 SCHEDULE OF INSPECTIONS AND TESTS

- A. Prepare a schedule of inspections, tests, and similar services required by the Contract Documents. Submit the schedule with (15) days of the date established for commencement of the Contract Work. The Contractor is to notify the testing agency at least (5) working days in advance of the required tests unless otherwise specified.
- B. Form: This schedule shall be in tabular form and shall include, but not be limited to, the following:
  - 1. Specification Section number
  - 2. Description of the test
  - 3. Identification of applicable standards
  - 4. Identification of test methods
  - 5. Number of tests required
  - 6. Time schedule or time span for tests
  - 7. Entity responsible for performing tests
  - 8. Requirements for taking samples
  - 9. Unique characteristics of each service
- C. Distribution: Distribute the schedule to the Owner, Architect, and each party involved in performance of portions of the Work where inspections and tests are required.

#### END OF SECTION

#### SECTION 013300 SUBMITTALS

#### **PART 1 GENERAL**

#### 1.01 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract including General and Supplementary Conditions, Bid Form, and other Division 1 Specification Sections apply to this Section.
- B. Division 1, Section 013115 "Project Management Communications" for administrative requirements for communications.

#### 1.02 SUMMARY

- A. This Section includes administrative and procedural requirements for submittals required for performance of the Work including the following:
  - 1. Shop Drawings
  - 2. Product Data
  - 3. Samples
  - 4. Quality Assurance Submittals
  - 5. Construction Photographs
  - 6. Operating and Maintenance Manuals
  - 7. Warranties
- B. Administrative Submittals: Refer to General and Supplementary Conditions other applicable Division 1 Sections and other Contract Documents for requirements for administrative submittals. Such submittals include, but are not limited to, the following:
  - 1. Construction Progress Schedule including Schedule of Values
  - 2. Performance and Payment Bonds
  - 3. Insurance Certificates
  - 4. Applications for Payment
  - 5. Certified Payroll Reports
  - 6. Partial and Final Receipt of Payment and Release Forms
  - 7. Affidavit Compliance with Prevailing Wage Law
  - 8. Record Drawings
  - 9. Notifications, Permits, etc.
- C. The Contractor is obliged and responsible to check all shop drawings and schedules to assure compliance with contract plans and specifications. The Contractor is responsible for the content of the shop drawings and coordination with other contract work. Shop drawings and schedules shall indicate, in detail, all parts of an Item or Work including erection and setting instructions and integration with the Work of other trades.
- D. The Contractor shall at all times make a copy, of all approved submittals, available on site to the Construction Representative.

#### 1.03 SUBMITTAL PROCEDURES

- A. The Contractor shall comply with the General and Supplementary Conditions and other applicable sections of the Contract Documents. The Contractor shall submit, with such promptness as to cause no delay in his work or in that of any other contractors, all required submittals indicated in Part 3.1 of this section and elsewhere in the Contract Documents. Coordinate preparation and processing of submittals with performance of construction activities. Transmit each submittal sufficiently in advance of performance of related construction activities to avoid delay.
  - 1. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activity.
  - 2. Coordinate transmittal of different types of submittals for related elements of the Work so processing will not be delayed by the need to review submittals concurrently for coordination.

- a. The Designer reserves the right to withhold action on a submittal requiring coordination with other submittals until all related submittals are received.
- B. Each drawing and/or series of drawings submitted must be accompanied by a letter of transmittal giving a list of the titles and numbers of the drawings. Each series shall be numbered consecutively for ready reference and each drawing shall be marked with the following information:
  - 1. Date of Submission
  - 2. Name of Project
  - 3. Location
  - 4. Section Number of Specification
  - 5. State Project Number
  - 6. Name of Submitting Contractor
  - 7. Name of Subcontractor
  - 8. Indicate if Item is submitted as specified or as a substitution

#### 1.04 SHOP DRAWINGS

- A. Comply with the General Conditions, Article 3.2.
- B. The Contractor shall submit newly prepared information drawn accurately to scale. Highlight, encircle, or otherwise indicate deviations from the Contract Documents. Do not reproduce Contract Documents or copy standard information as the basis of Shop Drawings. Standard information prepared without specific reference to the Project is not a Shop Drawing.
- C. Shop Drawings include fabrication and installation drawings, setting diagrams, schedules, patterns, templates, and similar drawings including the following information:
  - 1. Dimensions
  - 2. Identification of products and materials included by sheet and detail number
  - 3. Compliance with specified standards
  - 4. Notation of coordination requirements
  - 5. Notation of dimensions established by field measurement
  - 6. Sheet Size: Except for templates, patterns and similar full-size Drawings, submit Shop Drawings on sheets at least 8½"x11" but no larger than 36"x48".

#### 1.05 PRODUCT DATA

- A. The Contractor shall comply with the General Conditions, Article 3.2.
- B. The Contractor shall collect Product Data into a single submittal for each element of construction or system. Product Data includes printed information, such as manufacturer's installation instructions, catalog cuts, standard color charts, roughing-in diagrams and templates, standard wiring diagrams, and performance curves.
  - 1. Mark each copy to show applicable choices and options. Where printed Product Data includes information on several products that are not required, mark copies to indicate the applicable information including the following information:
    - a. Manufacturer's printed recommendations
    - b. Compliance with Trade Association standards
    - c. Compliance with recognized Testing Agency standards
    - d. Application of Testing Agency labels and seals
    - e. Notation of dimensions verified by field measurement
    - f. Notation of coordination requirements
  - 2. Do not submit Product Data until compliance with requirements of the Contract Documents has been confirmed.

#### 1.06 SAMPLES

A. The Contractor shall comply with the General Conditions, Article 3.2.

- B. The Contractor shall submit full-size, fully fabricated samples, cured and finished as specified, and physically identical with the material or product proposed. Samples include partial sections of manufactured or fabricated components, cuts or containers of materials, color range sets, and swatches showing color, texture, and pattern.
  - 1. The Contractor shall mount or display samples in the manner to facilitate review of qualities indicated. Prepare samples to match the Designer's sample including the following:
    - a. Specification Section number and reference
    - b. Generic description of the Sample
    - c. Sample source
    - d. Product name or name of the Manufacturer
    - e. Compliance with recognized standards
    - f. Availability and delivery time
  - 2. The Contractor shall submit samples for review of size, kind, color, pattern, and texture. Submit samples for a final check of these characteristics with other elements and a comparison of these characteristics between the final submittal and the actual component as delivered and installed.
    - a. Where variation in color, pattern, texture, or other characteristic is inherent in the material or product represented, submit at least three (3) multiple units that show approximate limits of the variations.
    - b. Refer to other Specification Sections for requirements for samples that illustrate workmanship, fabrication techniques, details of assembly, connections, operation, and similar construction characteristics.
    - c. Refer to other Sections for samples to be returned to the Contractor for incorporation in the Work. Such samples must be undamaged at time of use. On the transmittal, indicate special requests regarding disposition of sample submittals.
    - d. Samples not incorporated into the Work, or otherwise designated as the Owner's property, are the property of the Contractor and shall be removed from the site prior to Substantial Completion.
  - 3. Field samples are full-size examples erected onsite to illustrate finishes, coatings, or finish materials and to establish the Project standard.
    - a. The Contractor shall comply with submittal requirements to the fullest extent possible. The Contractor shall process transmittal forms to provide a record of activity.

#### 1.07 QUALITY ASSURANCE DOCUMENTS

- A. The Contractor shall comply with the General Conditions, Article 3.2
- B. The Contractor shall submit quality control submittals including design data, certifications, manufacturer's instructions, manufacturer's field reports, and other quality-control submittals as required under other Sections of the Specifications.
- C. Certifications: Where other Sections of the Specifications require certification that a product, material, or installation complies with specified requirements, submit a notarized certification from the Manufacturer certifying compliance with specified requirements.
  - 1. Signature: Certification shall be signed by an officer of the Manufacturer or other individual authorized to contractually bind the Company.
- D. Inspection and Test Reports: The Contractor shall submit the required inspection and test reports from independent testing agencies as specified in this Section and in other Sections of the Contract Documents.
- E. Construction Photographs: The Contractor shall submit record construction photographs as specified in this Section and in other Sections of the Contract Documents.
  - 1. The Contractor shall submit digital photographs. The Construction Administrator shall determine the quantity and naming convention at the preconstruction meeting.
  - 2. The Contractor shall identify each photograph with project name, location, number, date, time, and orientation.

- 3. The Contractor shall submit progress photographs monthly unless specified otherwise. Photographs shall be taken one (1) week prior to submitting.
- 4. The Contractor shall take four (4) site photographs from differing directions and a minimum of five (5) interior photographs indicating the relative progress of the Work.

#### 1.08 OPERATING AND MAINTENANCE MANUALS AND WARRANTIES

A. The Contractor shall submit all required manufacturer's operating instructions, maintenance/service manuals, and warranties in accordance with the General Conditions, Article 3.5, and Supplementary Conditions along with this and other Sections of the Contract Documents.

#### PART 2 PRODUCTS (NOT APPLICABLE)

#### **PART 3 EXECUTION**

#### 3.01 REQUIRED SUBMITTALS

A. Contractor shall submit the information for materials and equipment to be provided under this contract, as noted on the following page

SPEC SECTION	TITLE	CATEGORY
013200	Schedules	Construction Schedule
013200	Schedules	Schedule of Values
013200	Schedules	List of Subcontractors
013200	Schedules	Major Material Suppliers
051200	Structural Steel Framing	Product Data
051200	Structural Steel Framing	Shop Drawings
051200	Structural Steel Framing	Certification
051200	Structural Steel Framing	Test Report
055000	Metal Fabrications	Shop Drawings
061000	Rough Carpentry	Certification
064200	Stacked Wood Wall Panels	Product Data
064200	Stacked Wood Wall Panels	Sample
064200	Stacked Wood Wall Panels	Operation / Maintenance Manual
064200	Stacked Wood Wall Panels	Warranty
079200	Joint Sealants	Test Report
079200	Joint Sealants	Warranty
081113	Hollow Metal Doors and Frames	Product Data
081113	Hollow Metal Doors and Frames	Shop Drawings
081113	Hollow Metal Doors and Frames	Sample
081416	Flush Wood Doors	Product Data
081416	Flush Wood Doors	Shop Drawings
081416	Flush Wood Doors	Sample
081416	Flush Wood Doors	Warranty
084313	Aluminum-Framed Storefronts	Product Data
084313	Aluminum-Framed Storefronts	Shop Drawings
084313	Aluminum-Framed Storefronts	Certification
084313	Aluminum-Framed Storefronts	Warranty

SPEC SECTION	TITLE	CATEGORY
087100	Door Hardware	Product Data
087100	Door Hardware	Shop Drawings
087100	Door Hardware	Sample
087100	Door Hardware	Operation / Maintenance Manual
087100	Door Hardware	Warranty
087113	Power Door Operators	Product Data
087113	Power Door Operators	Operation / Maintenance Manual
088000	Glazing	Product Data
088000	Glazing	Certification
088000	Glazing	Warranty
092116	Gypsum Board Assemblies	Product Data
092216	Non-Structural Metal Framing	Product Data
092216	Non-Structural Metal Framing	Certification
092226.23	Metal Suspension Systems	Product Data
092226.23	Metal Suspension Systems	Certification
092226.23	Metal Suspension Systems	Warranty
093000	Tiling	Product Data
093000	Tiling	Sample
093000	Tiling	Operation / Maintenance Manual
095100	Acoustical Ceilings	Product Data
095100	Acoustical Ceilings	Sample
095100	Acoustical Ceilings	Operation / Maintenance Manual
099123	Interior Painting	Product Data
099123	Interior Painting	Sample
099123	Interior Painting	Mock up
099123	Interior Painting	Operation / Maintenance Manual
102113.19	Plastic Toilet Compartments	Product Data
102113.19	Plastic Toilet Compartments	Shop Drawings
102113.19	Plastic Toilet Compartments	Sample
102113.19	Plastic Toilet Compartments	Operation / Maintenance Manual
102800	Toilet, Bath, and Laundry Accessories	Product Data
102800	Toilet, Bath, and Laundry Accessories	Operation / Maintenance Manual
123600	Countertops	Product Data
123600	Countertops	Shop Drawings

SPEC SECTION	TITLE	CATEGORY
123600	Countertops	Sample
123600	Countertops	Operation / Maintenance Manual
211300	Fire-Suppression Sprinkler Systems	Shop Drawings
211300	Fire-Suppression Sprinkler Systems	Operation / Maintenance Manual
221006	Plumbing Piping Specialties	Product Data
224000	Plumbing Fixtures	Product Data
230593	Testing, Adjusting, and Balancing for HVAC	Certification
230593	Testing, Adjusting, and Balancing for HVAC	Test Report
230713	Duct Insulation	Product Data
233100	HVAC Ducts and Casings	Product Data
233300	Air Duct Accessories	Product Data
233700	Air Outlets and Inlets	Product Data
262726	Wiring Devices	Product Data
262726	Wiring Devices	Operation / Maintenance Manual
265100	Interior Lighting	Product Data
265100	Interior Lighting	Operation / Maintenance Manual
284600	Fire Detection and Alarm	Certification

#### **END OF SECTION**

#### SECTION 013513.10 SITE SECURITY AND HEALTH REQUIREMENTS (OA)

#### **PART 1 GENERAL**

#### 1.01 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract including General and Supplementary Conditions, Bid Form, and other Division 1 Specification Sections apply to this Section.

#### 1.02 SUBMITTALS

- A. List of required submittals:
  - 1. Materials Safety Data Sheets for all hazardous materials to be brought onsite.
  - 2. Schedule of proposed shutdowns, if applicable.
  - 3. A list of the names of all employees who will submit fingerprints for a background check, and the signed privacy documents identified below for each employee.

#### PART 2 PRODUCTS (NOT APPLICABLE)

#### **PART 3 EXECUTION**

#### 3.01 ACCESS TO THE SITE

- A. The Contractor shall arrange with Facility Representatives to establish procedures for the controlled entry of workers and materials into the work areas at the Facility.
- B. The Contractor shall establish regular working hours with Facility Representatives. The Contractor must report changes in working hours or overtime to Facility Representatives and obtain approval twenty-four (24) hours ahead of time. The Contractor shall report emergency overtime to Facility Representatives as soon as it is evident that overtime is needed. The Contractor must obtain approval from Facility Representatives for all work performed after dark.
- C. The Contractor shall provide the name and phone number of the Contractor's employee or agent who is in charge onsite; this individual must be able to be contacted in case of emergency. The Contractor must be able to furnish names and address of all employees upon request.
- D. All construction personnel shall visibly display issued identification cards.

#### 3.02 FIRE PROTECTION, SAFETY, AND HEALTH CONTROLS

- A. The Contractor shall take all necessary precautions to guard against and eliminate possible fire hazards.
  - 1. Onsite burning is prohibited.
  - 2. The Contractor shall store all flammable or hazardous materials in proper containers located outside the buildings or offsite, if possible.
  - 3. The Contractor shall provide and maintain, in good order, during construction fire extinguishers as required by the National Fire Protection Association. In areas of flammable liquids, asphalt, or electrical hazards, 15-pound carbon dioxide or 20-pound dry chemical extinguishers shall be provided.
- B. The Contractor shall not obstruct streets or walks without permission from the Owner's Construction Representative and Facility Representatives.
- C. The Contractor's personnel shall not exceed the speed limit of 15 mph while at the Facility unless otherwise posted.
- D. The Contractor shall take all necessary, reasonable measures to reduce air and water pollution by any material or equipment used during construction. The Contractor shall keep volatile wastes in covered containers, and shall not dispose of volatile wastes or oils in storm or sanitary drains.
- E. The Contractor shall keep the project site neat, orderly, and in a safe condition at all times. The Contractor shall immediately remove all hazardous waste, and shall not allow rubbish to accumulate. The Contractor shall provide onsite containers for collection of rubbish and shall dispose of it at frequent intervals during the progress of the Work.

#### SITE SECURITY AND HEALTH REQUIREMENTS

(OA)

- F. Fire exits, alarm systems, and sprinkler systems shall remain fully operational at all times, unless written approval is received from the Owner's Construction Representative and the appropriate Facility Representative at least twenty-four (24) hours in advance. The Contractor shall submit a written time schedule for any proposed shutdowns.
- G. For all hazardous materials brought onsite, Material Safety Data Sheets shall be on site and readily available upon request at least a day before delivery.
- H. Alcoholic beverages or illegal substances shall not be brought upon the Facility premises. The Contractor's workers shall not be under the influence of any intoxicating substances while on the Facility premises.

## 3.03 SECURITY CLEARANCES AND RESTRICTIONS

## A. FMDC CONTRACTOR BACKGROUND AND ID BADGE PROCESS

- 1. All employees of an OA/FDMC contractor (or subcontractor performing work under an OA/FMDC contract) are required to submit a fingerprint check through the Missouri State Highway Patrol (MSHP) and the FBI enabling OA/FMDC to obtain state and national criminal background checks on the employees, unless stated otherwise in the Contractor's contract.
- 2. FMDC reserves the right to prohibit any employee of the Contractor from performing work in or on the premises of any facility owned, operated, or utilized by the State of Missouri for any reason.
- 3. The Contractor shall ensure all of its employees submit fingerprints to the Missouri State Highway Patrol and pay for the cost of such background checks. The Contractor shall submit to FMDC via email to FMDCSecurity@oa.mo.gov a list of the names of the Contractor's employees who will be fingerprinted and a signed OA/FMDC Authorization for Release of Information Confidentiality Oath for each employee. All employees of the Contractor approved by FMDC to work at a State facility must obtain a contractor ID badge from FMDC prior to beginning work on-site, unless the Director of FMDC, at the Director's discretion, waives the requirement for a contractor ID badge. The Contractor and its employees must comply with the process for background checks and contractor ID badges found on FMDC's website at: https://oa.mo.gov/facilities/facilities-operations/security-information/fmdc-contractor-background-and-id-badge
- 4. Fingerprints and Authorization for Release of Information Confidentiality Oath form are valid for one (1) year and must be renewed annually. Changing or adding locations may result in additional required documentation. Certain employees may be required to be fingerprinted more frequently. OA/FMDC reserves the right to request additional background checks at any time for any reason.
- 5. The Contractor shall notify FMDC via email to FMDCSecurity@oa.mo.gov within 48 hours of anyone severing employment with their company.

### 3.04 DISRUPTION OF UTILITIES

- A. The Contractor shall give a minimum of seventy-two (72) hours written notice to the Construction Representative and the Facility Representative before disconnecting electric, gas, water, fire protection, or sewer service to any building.
- B. The Contractor shall give a minimum of seventy-two (72) hours written notice to the Construction Representative and Facility Representative before closing any access drives, and shall make temporary access available, if possible. The Contractor shall not obstruct streets, walks, or parking.

# 3.05 PROTECTION OF PERSONS AND PROPERTY

A. SAFETY PRECAUTIONS AND PROGRAMS

- 1. The Contractor shall at all times conduct operations under this Contract in a manner to avoid the risk of bodily harm to persons or risk of damage to any property. The Contractor shall promptly take precautions which are necessary and adequate against conditions created during the progress of the Contractor's activities hereunder which involve a risk of bodily harm to persons or a risk of damage to property. The Contractor shall continuously inspect Work, materials, and equipment to discover and determine any such conditions and shall be solely responsible for discovery, determination, and correction of any such conditions. The Contractor shall comply with applicable safety laws, standards, codes, and regulations in the jurisdiction where the Work is being performed, specifically, but without limiting the generality of the foregoing, with rules regulations, and standards adopted pursuant to the Williams-Steiger Occupational Safety and Health Act of 1970 and applicable amendments.
- 2. All contractors, subcontractors and workers on this project are subject to the Construction Safety Training provisions 292.675 RSMo.
- 3. In the event the Contractor encounters on the site, material reasonably believed to be asbestos, polychlorinated biphenyl (PCB), lead, mercury, or other material known to be hazardous, which has not been rendered harmless, the Contractor shall immediately stop Work in the area affected and report the condition to the Owner's Representative and the Architect in writing. The Work in the affected area shall not thereafter be resumed except by written agreement of the Owner's Representative and Contractor if in fact the material is asbestos or polychlorinated biphenyl (PCB) and has not been rendered harmless. The Work in the affected area shall be resumed in the absence of asbestos or polychlorinated biphenyl (PCB), or when it has been rendered harmless by written agreement of the Owner's Representative and the Contractor. "Rendered Harmless" shall mean that levels of such materials are less than any applicable exposure standards, including but limited to OSHA regulations.

### B. SAFETY OF PERSONS AND PROPERTY

- 1. The Contractor shall take reasonable precautions for safety of, and shall provide protection to prevent damage, injury, or loss to:
  - a. clients, staff, the public, construction personnel, and other persons who may be affected thereby;
  - b. the Work and materials and equipment to be incorporated therein, whether in storage on or off the site, under care, custody, or control of the Contractor or the Contractor's Subcontractors of any tier; and
  - c. other property at the site or adjacent thereto, such as trees, shrubs, lawns, walks, pavements, roadways, structures, and utilities not designated for removal, relocation, or replacement in the course of construction.
- 2. The Contractor shall give notices and comply with applicable laws, standards, codes, ordinances, rules, regulations, and lawful orders of public authorities bearing on safety of persons or property or their protection from damage, injury, or loss.
- 3. The Contractor shall erect and maintain, as required by existing conditions and performance of the Contract, safeguards for safety and protection, including, but not limited to, posting danger signs and other warnings against hazards, promulgating safety regulations, and notifying owners and users of adjacent sites and utilities.
- 4. When use or storage of explosives or other hazardous materials or equipment or unusual methods are necessary for execution of the Work, the Contractor shall exercise the highest degree of care and carry on such activities under supervision of properly qualified personnel.

- 5. The Contractor shall promptly remedy damage and loss (other than damage or loss insured under property insurance required by the Contract Documents) to property referred to in this Section caused in whole or in part by the Contractor, a Subcontractor of any tier, or anyone directly or indirectly employed by any of them, or by anyone for whose acts they may be liable, and for which the Contractor is responsible under this Section, except damage or loss attributable solely to acts or omissions of Owner or the Architect or anyone directly or indirectly employed by either of them, or by anyone for whose acts either of them may be liable, and not attributable to the fault or negligence of the Contractor. The foregoing obligations of the Contractor are in addition to the Contractor's other obligations stated elsewhere in the Contract.
- 6. The Contractor shall designate a responsible member of the Contractor's organization at the site whose duty shall be the prevention of accidents, and the maintaining, enforcing and supervising of safety precautions and programs. This person shall be the Contractor's superintendent unless otherwise designated by the Contractor in writing to the Owner's Representative and Architect. The Contractor shall hold regularly scheduled safety meetings to instruct Contractor personnel on safety practices, accident avoidance and prevention, and the Project Safety Program. The Contractor shall furnish safety equipment and enforce the use of such equipment by its employees and its subcontractors of any tier.
- 7. The Contractor shall not load or permit any part of the construction or site to be loaded so as to endanger its safety.
- 8. The Contractor shall promptly report in writing to the Owner all accidents arising out of or in connection with the Work which cause death, lost time injury, personal injury, or property damage, giving full details and statements of any witnesses. In addition, if death, serious personal injuries, or serious property damages are caused, the accident shall be reported immediately.
- 9. The Contractor shall promptly notify in writing to the Owner of any claims for injury or damage to personal property related to the work, either by or against the Contractor.
- 10. The Owner assumes no responsibility or liability for the physical condition or safety of the Work site or any improvements located on the Work site. The Contractor shall be solely responsible for providing a safe place for the performance of the Work. The Owner shall not be required to make any adjustment in either the Contract Sum or Contract Time concerning any failure by the Contractor or any Subcontractor to comply with the requirements of this Paragraph.
- 11. In no event shall the Owner have control over, charge of, or any responsibility for construction means, methods, techniques, sequences or procedures or for safety precautions and programs in connection with the Work, notwithstanding any of the rights and authority granted the Owner in the Contract Documents.
- 12. The Contractor shall maintain at his own cost and expense, adequate, safe and sufficient walkways, platforms, scaffolds, ladders, hoists and all necessary, proper, and adequate equipment, apparatus, and appliances useful in carrying on the Work and which are necessary to make the place of Work safe and free from avoidable danger for clients, staff, the public and construction personnel, and as may be required by safety provisions of applicable laws, ordinances, rules regulations and building and construction codes.

# SECTION 015000 CONSTRUCTION FACILITIES AND TEMPORARY CONTROLS

## **PART 1 GENERAL**

### 1.01 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract including General and Supplementary Conditions, Bid Form, and other Division 1 Specification Sections apply to this Section.

#### 1.02 SUMMARY

- A. This Section includes requirements for construction facilities and temporary controls including temporary utilities, support facilities, security, and protection.
- B. Temporary utilities include, but are not limited to, the following:
  - 1. Water service and distribution
  - 2. Temporary electric power and light
  - 3. Temporary heat
  - 4. Ventilation
  - 5. Sanitary facilities, including drinking water
- C. Support facilities include, but are not limited to, the following:
  - 1. Field offices and storage sheds
  - 2. Temporary enclosures
  - 3. Temporary project identification signs and bulletin boards
  - 4. Waste disposal services
  - 5. Construction aids and miscellaneous services and facilities
- D. Security and protection facilities include, but are not limited to, to following:
  - 1. Temporary fire protection
  - 2. Barricades, warning signs, and lights
  - 3. Environmental protection

## 1.03 SUBMITTALS

- A. Temporary Utilities: Submit reports of tests, inspections, meter readings, and similar procedures performed on temporary utilities.
- B. Implementation and Termination Schedule: Within (15) days of the date established for commencement of the Work, submit a schedule indicating implementation and termination of each temporary utility.

## 1.04 QUALITY ASSURANCE

- A. Regulations: Comply with industry standards and applicable laws and regulations including, but not limited to, the following:
  - 1. Building code requirements
  - 2. Health and safety regulations
  - 3. Utility company regulations
  - 4. Police, fire department, and rescue squad rules
  - 5. Environmental protection regulations
- B. Standards: Comply with NFPA 241 "Standard for Safeguarding Construction, Alterations, and Demolition Operations". ANSI A10 Series standards for "Safety Requirements for Construction and Demolition", and NECA Electrical Design Library "Temporary Electrical Facilities".
  - 1. Electrical Service: Comply with NEMA, NECA, and UL standards and regulations for temporary electric service. Install service in compliance with NFPA 70 "National Electric Code".
- C. Inspections: Arrange for authorities having jurisdiction to inspect and test each temporary utility before use. Obtain required certifications and permits.

### 1.05 PROJECT CONDITIONS

- A. Temporary Utilities: Prepare a schedule indicating dates for implementation and termination of each temporary utility. At the earliest feasible time, when acceptable to the Owner, change over from use of temporary service to use of permanent service.
- 3. Conditions of Use: Keep temporary services and facilities clean and neat in appearance. Operate in a safe and efficient manner. Relocate temporary services and facilities as the Work progresses. Do not overload facilities or permit them to interfere with progress. Take necessary fire-prevention measures. Do not allow hazardous, dangerous, or unsanitary conditions, or public nuisances to develop or persist onsite.

## **PART 2 PRODUCTS**

## 2.01 MATERIALS

- A. General: Provide new materials. If acceptable to the Designer, the Contractor may use undamaged, previously used materials in serviceable condition. Provide materials suitable for use intended.
- B. Water: Provide potable water approved by local health authorities.

# 2.02 EQUIPMENT

- A. General: Provide new equipment. If acceptable to the Designer, the Contractor may use undamaged, previously used equipment in serviceable condition. Provide equipment suitable for use intended.
- B. Water Hoses: Provide ¾" (19mm), heavy-duty, abrasion-resistant, flexible rubber hoses 100' (30m) long, with pressure rating greater than the maximum pressure of the water distribution system. Provide adjustable shutoff nozzles at hose discharge.
- C. Electrical Outlets: Provide properly configured, NEMA-polarized outlets to prevent insertion of 110 to 120V plugs into higher voltage outlets. Provide receptacle outlets equipped with ground-fault circuit interrupters, reset button, and pilot light for connection of power tools and equipment.
- D. Electrical Power Cords: Provide grounded extension cords. Use hard-service cords where exposed to abrasion and traffic. Provide waterproof connectors to connect separate lengths of electric cords if single lengths will not reach areas where construction activities are in progress. Do not exceed safe lengthvoltage rating.
- E. Lamps and Light Fixtures: Provide general service incandescent lamps of wattage required for adequate illumination. Provide guard cages or tempered-glass enclosures where exposed to breakage. Provide exterior fixture where exposed to moisture.
- F. Temporary Offices: Provide prefabricated or mobile units or similar job-built construction with lockable entrances, operable windows, and serviceable finishes. Provide heated and air-conditioned units on foundations adequate for normal loading.
- G. Temporary Toilet Units: Provide self-contained, single-occupant toilet units of the chemical, aerated recirculation, or combustion type. Provide units properly vented and fully enclosed with a glass-fiber-reinforced polyester shell or similar nonabsorbent material.
- H. Fire Extinguishers: Provide hand-carried, portable, UL-rated, Class A fire extinguishers for temporary offices and similar spaces. In other locations, provide hand-carried, portable, UL-rated, Class ABC, drychemical extinguishers, or a combination of extinguishers of NFPA-recommended classes for the exposures.
  - 1. Comply with NFPA 10 and NFPA 241 for classification, extinguishing agent, and size required by location and class of fire exposure.

### **PART 3 EXECUTION**

# 3.01 INSTALLATION

A. Use qualified personnel for installation of temporary facilities. Locate facilities where they will serve the Project adequately and result in minimum interference with performance of the Work. Relocate and modify facilities as required.

CONSTRUCTION FACILITIES AND TEMPORARY CONTROLS

O2339-01-Howerton State Office Building-Renovate Lobby and Restrooms, 1st and 2nd Floor

B. Provide each Facility ready for use when needed to avoid delay. Maintain and modify as required. Do not remove until facilities are no longer needed or are replaced by authorized use of completed permanent facilities.

## 3.02 TEMPORARY UTILITY INSTALLATION

- A. General: Engage the appropriate local utility company to install temporary service or connect to existing service. Where company provides only part of the service, provide the remainder with matching, compatible materials and equipment. Comply with company recommendations.
  - 1. Arrange with company and existing users for a time when service can be interrupted, if necessary, to make connections for temporary services.
  - 2. Provide adequate capacity at each stage of construction. Prior to temporary utility availability, provide trucked-in services.
  - 3. Obtain easements to bring temporary utilities to the site where the Owner's easements cannot be used for that purpose.
  - 4. Use Charges: Cost or use charges for temporary facilities are not chargeable to the Owner or Designer. Neither the Owner nor Designer will accept cost or use charges as a basis of claims for Change Order.
- B. Temporary Water Service: The Owner will provide water for construction purposes from the existing building system. All required temporary extensions shall be provided and removed by the Contractor. Connection points and methods of connection shall be designated and approved by the Construction Representative.
- C. Temporary Electric Power Service: The Owner will provide electric power for construction lighting and power tools. Contractors using such services shall pay all costs of temporary services, circuits, outlet, extensions, etc.
- D. Temporary Lighting: When overhead floor or roof deck has been installed, provide temporary lighting with local switching.
  - 1. Install and operate temporary lighting that will fulfill security and protection requirements without operating the entire system. Provide temporary lighting that will provide adequate illumination for construction operations and traffic conditions.
- E. Temporary Heating and Cooling: The normal heating and/or cooling system of the building shall be maintained in operation during the construction. Should the Contractor find it necessary to interrupt the normal HVAC service to spaces, which have not been vacated for construction, such interruptions shall be pre-scheduled with the Construction Representative.
- F. Temporary Toilets: Install self-contained toilet units. Use of pit-type privies will not be permitted. Comply with regulations and health codes for the type, number, location, operation, and maintenance of fixtures and facilities. Install where facilities will best serve the Project's needs.
  - 1. Shield toilets to ensure privacy.
  - 2. Provide separate facilities for male and female personnel.
  - 3. Provide toilet tissue materials for each facility.
- G. Temporary Toilets: Use of the Owner's existing toilet facilities will be permitted, so long as facilities are cleaned and maintained in a condition acceptable to the Owner. All construction personnel will be allowed access only to those specific facilities designed by the Construction Representative. At substantial completion, restore these facilities to the condition prevalent at the time of initial use.
- H. Wash Facilities: The Owner will provide wash facilities within the building. All construction personnel will be allowed access only to those specific facilities designated by the Construction Representative.
- I. Drinking-Water Facilities: The Owner will provide drinking water facilities within the building. All construction personnel will be allowed access only to those specific facilities designated by the Construction Representative.

### 3.03 SUPPORT FACILITIES INSTALLATION

- A. General: Locate field offices, storage sheds, and other temporary construction and support facilities for easy access.
  - 1. Maintain support facilities until near Substantial Completion. Remove prior to Substantial Completion. Personnel remaining after Substantial Completion will be permitted to use permanent facilities, under conditions acceptable to the Owner.
- B. Field Offices: Provide insulated, weathertight temporary offices of sufficient size to accommodate required office personnel at the Project site. Keep the office clean and orderly for use for small progress meetings. Furnish and equip office as follows:
  - 1. Furnish with a desk and chairs, a 4-drawer file cabinet, plan table, plan rack, and a 6-shelf bookcase.
  - 2. Equip with a water cooler and private toilet complete with water closet, lavatory, and medicine cabinet unit with a mirror.
- C. Storage Facilities: The Owner will provide storage onsite as designated by the Facility Representative or the Construction Representative. Areas for use by the Contractor for storage will be identified at the Pre-Bid Meeting.
- D. Storage Facilities: No areas for storage of building materials can be made available onsite. The Contractor shall provide for all storage offsite. All off-site storage locations shall be approved by the Construction Representative. The Contractor shall provide his own security as he finds necessary. The Construction Representative shall have access to the off-site storage at all times.
- E. Construction Parking: Parking at the site will be provided in the areas designated at the Pre-Construction Meeting.
- F. Temporary Enclosures: Provide temporary enclosures for protection of construction, in progress and completed, from exposure, foul weather, other construction operations, and similar activities.
  - 1. Where heat is needed and the permanent building enclosure is not complete, provide temporary enclosures where there is no other provision for containment of heat. Coordinate enclosure with ventilating and materials drying or curing requirements to avoid dangerous conditions and effects.
  - 2. Install tarpaulins securely with incombustible wood framing and other materials. Close openings of 25SqFt (2.3SqM) or less with plywood or similar materials.
  - 3. Close openings through floor or roof decks and horizontal surfaces with load-bearing, wood-framed construction.
  - 4. Where temporary wood or plywood enclosure exceeds 100SqFt (9.2SqM) in area, use UL-labeled, fire-retardant-treated material for framing and main sheathing.
- G. Temporary Elevator Use: The Owner will allow use of elevators within the building. All construction personnel will be allowed access only to those specific elevators designated by the Construction Representative.
- H. Project Identification and Temporary Signs: Prepare project identification and other signs of size indicated. Install signs where indicated to inform the public and persons seeking entrance to the Project. Support on posts or framing of preservative-treated wood or steel. Do not permit installation of unauthorized signs.
  - 1. Project Identification Signs: Engage an experienced sign painter to apply graphics. Comply with details indicated.
  - 2. Temporary Signs: Prepare signs to provide directional information to construction personnel and visitors.

I. Collection and Disposal of Waste: Collect waste from construction areas and elsewhere daily. Comply with requirements of NFPA 241 for removal of combustible waste material and debris. Enforce requirements strictly. Do not hold materials more than seven (7) days during normal weather or three (3) days when the temperature is expected to rise above 80°F (27°C). Handle hazardous, dangerous, or unsanitary waste materials separately from other waste by containerizing properly. Dispose of material lawfully.

### 3.04 SECURITY AND PROTECTION FACILITIES INSTALLATION

- A. Except for use of permanent fire protection as soon as available, do not change over from use of temporary security and protection facilities to permanent facilities until Substantial Completion, or longer, as requested by the Designer.
- B. Temporary Fire Protection: Until fire-protection needs are supplied by permanent facilities, install and maintain temporary fire-protection facilities of the types needed to protect against reasonable predictable and controllable fire losses. Comply with NFPA 10 "Standard for Portable Fire Extinguishers" and NFPA 241 "Standard for Safeguarding Construction, Alterations, and Demolition Operations".
  - 1. Locate fire extinguishers where convenient and effective for their intended purpose, but not less than one (1) extinguisher on each floor at or near each usable stairwell.
  - 2. Store combustible materials in containers in fire-safe locations.
  - Maintain unobstructed access to fire extinguishers, fire hydrants, temporary fire-protection facilities, stairways, and other access routes for fighting fires. Prohibit smoking in hazardous fireexposure areas.
  - 4. Provide supervision of welding operations, combustion-type temporary heating units, and similar sources of fire ignition.
- C. Permanent Fire Protection: At the earliest feasible date in each area of the Project complete installation of the permanent fire-protection facility including connected services and place into operation and use. Instruct key personnel on use of facilities.
- D. Barricades, Warning Signs, and Lights: Comply with standards and code requirements for erection of structurally adequate barricades. Paint with appropriate colors, graphics, and warning signs to inform personnel and the public of the hazard being protected against. Where appropriate and needed, provide lighting including flashing red or amber lights.
- E. Security Enclosure and Lockup: Install substantial temporary enclosure of partially completed areas of construction. Provide locking entrances to prevent unauthorized entrance, vandalism, theft, and similar violations of security.
  - 1. Storage: Where materials and equipment must be stored and are of value or attractive for theft, provide a secure lockup. Enforce discipline in connection with the installation and release of material to minimize the opportunity for theft and vandalism.
- F. Environmental Protection: Provide protection, operate temporary facilities, and conduct construction in ways and by methods that comply with environmental regulations and minimize the possibility that air, waterways, and subsoil might be contaminated or polluted or that other undesirable effects might result. Avoid use of tools and equipment that produce harmful noise. Restrict use of noisemaking tools and equipment to hours that will minimize complaints from persons or firms near the site.

# 3.05 OPERATION, TERMINATION AND REMOVAL

- A. Supervision: Enforce strict discipline in use of temporary facilities. Limit availability of temporary facilities to essential and intended uses to minimize waste and abuse.
- B. Maintenance: Maintain facilities in good operating condition until removal. Protect from damage by freezing temperatures and similar elements.
  - 1. Maintain operation of temporary enclosures, heating, cooling, humidity control, ventilation, and similar facilities on a 24-hour basis where required to achieve indicated results and to avoid possibility of damage.

- 2. Protection: Prevent water-filled piping from freezing. Maintain markers for underground lines. Protect from damage during excavation operations.
- C. Termination and Removal: Unless the Designer requests that it be maintained longer, remove each temporary facility when the need has ended, when replaced by authorized use of a permanent facility, or no later than Substantial Completion. Complete or, if necessary, restore permanent construction that may have been delayed because of interference with the temporary facility. Repair damaged Work, clean exposed surfaces, and replace construction that cannot be satisfactorily repaired.
  - 1. Materials and facilities that constitute temporary facilities are the Contractor's property. The Owner reserves the right to take possession of project identification signs.
  - 2. Remove temporary paving not intended for or acceptable for integration into permanent paving. Where the area is intended for landscape development, remove soil and aggregate fill that do not comply with requirements for fill or subsoil in the area. Remove materials contaminated with road oil, asphalt and other petrochemical compounds, and other substances that might impair growth of plant materials or lawns. Repair or replace street paving, curbs, and sidewalks at the temporary entrances as required by the governing authority.
  - 3. At Substantial Completion, clean and renovate permanent facilities used during the construction period including, but not limited to, the following:
    - a. Replace air filters and clean inside of ductwork and housing.
    - b. Replace significantly worn parts and parts subject to unusual operating conditions.
    - c. Replace lamps burned out or noticeably dimmed by hours of use.

## SECTION 017400 CLEANING

## **PART 1 GENERAL**

### 1.01 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract including General and Supplementary Conditions, Bid Form, and other Division 1 Specification Sections apply to this Section.

#### 1.02 SUMMARY

- A. This Section includes administrative and procedural requirements for cleaning during the Project.
- B. Environmental Requirements: Conduct cleaning and waste-disposal operations in compliance with local laws and ordinances. Comply fully with federal and local environmental and anti-pollution regulations.
  - 1. Do not dispose of volatile wastes such as mineral spirits, oil, or paint thinner in storm or sanitary drains.
  - 2. Burning or burying of debris, rubbish, or other waste material on the premises is not permitted.

## **PART 2 PRODUCTS**

### 2.01 MATERIALS

A. Cleaning Agents: Use cleaning materials and agents recommended by the manufacturer or fabricator for the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.

### **PART 3 EXECUTION**

### 3.01 PROGRESS CLEANING

#### A. General

- 1. Retain all stored items in an orderly arrangement allowing maximum access, not impending drainage or traffic, and providing the required protection of materials.
- 2. Do not allow the accumulation of scrap, debris, waste material, and other items not required for construction of this Work.
- 3. At least once each month, and more often if necessary, completely remove all scrap, debris, and waste material from the jobsite.
- 4. Provide adequate storage for all items awaiting removal from the jobsite, observing all requirements for fire protection and protection of the ecology.

### B. Site

- 1. Daily, inspect the site and pick up all scrap, debris, and waste material. Remove all such items to the place designated for their storage.
- 2. Weekly, inspect all arrangements of materials stored onsite. Re-stack, tidy, or otherwise service all material arrangements.
- 3. Maintain the site in a neat and orderly condition at all times.

#### C. Structures

- 1. Daily, inspect the structures and pick up all scrap, debris, and waste material. Remove all such items to the place designated for their storage.
- 2. Weekly, sweep all interior spaces clean. "Clean" for the purposes of this paragraph, shall be interpreted as meaning free from dust and other material capable of being removed by use of reasonable effort and handheld broom.
- 3. In preparation for installation of succeeding materials, clean the structures or pertinent portions thereof to the degree of cleanliness recommended by the manufacturer of the succeeding material, using all equipment and materials required to achieve the required cleanliness.

4. Following the installation of finish floor materials, clean the finish floor daily while work is being performed in the space in which finish materials have been installed. "Clean" for the purposes of this subparagraph, shall be interpreted as meaning free from all foreign material which, in the opinion of the Construction Representative, may be injurious to the finish of the finish floor material.

#### 3.02 FINAL CLEANING

- A. General: Provide final cleaning operations when indicated. Employ experienced workers or professional cleaners for final cleaning. Clean each surface or unit of Work to the condition expected from a commercial building cleaning and maintenance program. Comply with manufacturer's instructions.
- B. Complete the following cleaning operations before requesting inspection for certification of Substantial Completion for the entire Project or a portion of the Project.
  - 1. Clean the Project Site, yard and grounds, in areas disturbed by construction activities including landscape development areas, of rubbish, waste material, litter, and foreign substances.
  - Sweep paved areas broom clean. Rake grounds that are neither planted nor paved to a smooth, even-textured surface.
  - 3. Remove petrochemical spills, stains, and other foreign deposits.
  - 4. Remove tools, construction equipment, machinery, and surplus material from the site.
  - 5. Remove snow and ice to provide safe access to the building.
  - 6. Clean exposed exterior and interior hard-surfaced finishes to a dirt-free condition, free of stains, films, and similar foreign substances. Avoid disturbing natural weathering of exterior surfaces. Restore reflective surfaces to their original condition.
  - 7. Remove debris and surface dust from limited access spaces, including roofs, plenums, shafts, trenches, equipment vaults, manholes, attics, and similar spaces.
  - 8. Broom clean concrete floors in unoccupied spaces.
  - 9. Vacuum clean carpet and similar soft surfaces removing debris and excess nap. Shampoo, if required.
  - 10. Clean transparent material, including mirrors and glass in doors and windows. Remove glazing compounds and other substances that are noticeable vision-obscuring materials. Replace chipped or broken glass and other damaged transparent materials. Polish mirrors and glass, taking care not to scratch surfaces.
  - 11. Remove labels that are not permanent labels.
  - 12. Touch up and otherwise repair and restore marred, exposed finishes and surfaces. Replace finishes and surfaces that cannot be satisfactorily repaired or restored or that already show evidence of repair or restoration.
    - a. Do not paint over "UL" and similar labels, including mechanical and electrical nameplates.
  - 13. Wipe surfaces of mechanical and electrical equipment, elevator equipment, and similar equipment. Remove excess lubrication, paint and mortar droppings, and other foreign substances.
  - 14. Clean plumbing fixtures to a sanitary condition free of stains, including stains resulting from water exposure.
  - 15. Replace disposable air filters and clean permanent air filters. Clean exposed surfaces of diffusers, registers, and grills.
  - 16. Clean ducts, blowers, and coils if units were operated without filters during construction
  - 17. Clean food-service equipment to a sanitary condition, ready and acceptable for its intended use.
  - 18. Clean light fixtures, lamps, globes, and reflectors to function with full efficiency. Replace burnedout bulbs and defective and noisy starters in fluorescent and mercury vapor fixtures.
  - 19. Leave the Project clean and ready for occupancy.
- C. Pest Control: Engage an experienced, licensed exterminator to make a final inspection and rid the Project of rodents, insects, and other pests. Comply with regulations of local authorities.
- D. Removal of Protection: Remove temporary protection and facilities installed during construction to protect previously completed installations during the remainder of the construction period.

- E. Compliances: Comply with governing regulations and safety standards for cleaning operations. Remove waste materials from the site and dispose of lawfully.
  - 1. Where extra materials of value remain after Final Acceptance by the Owner, they become the Owner's property.

## SECTION 024119 SELECTIVE DEMOLITION

## **PART 1 GENERAL**

### 1.01 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.02 SUMMARY

- A. Section Includes:
  - 1. Demolition and removal of selected portions of interior building elements and materials.
- B. Related Requirements:
  - . Section 011000 "Summary of Work" for restrictions on the use of the premises, Owner-occupancy requirements, and phasing requirements.

### 1.03 DEFINITIONS

- A. Remove: Detach items from existing construction and legally dispose of them off-site unless indicated to be removed and salvaged or removed and reinstalled.
- B. Remove and Salvage: Carefully detach from existing construction, in a manner to prevent damage, and deliver to Owner.
- C. Remove and Reinstall: Detach items from existing construction, prepare for reuse, and reinstall where indicated.
- D. Existing to Remain: Existing items of construction that are not to be permanently removed and that are not otherwise indicated to be removed, removed and salvaged, or removed and reinstalled.

### 1.04 MATERIALS OWNERSHIP

A. Except for items or materials indicated to be reused, salvaged, reinstalled, or otherwise indicated to remain the Owner's property, demolished materials shall become the Contractor's property and shall be removed from the site with further disposition at the Contractor's option.

## 1.05 PREINSTALLATION MEETINGS

- A. Pre demolition Conference: Conduct conference at Project site
  - 1. Inspect and discuss condition of construction to be selectively demolished.
  - 2. Review and finalize selective demolition schedule and verify availability of materials, demolition personnel, equipment, and facilities needed to make progress and avoid delays.
  - 3. Review requirements of work performed by other trades that rely on substrates exposed by selective demolition operations.
  - 4. Review areas where existing construction is to remain and requires protection.
  - 5. Review Project Phasing for Scope of Work.

### 1.06 SUBMITTALS

- A. Proposed Protection Measures: Submit report, including drawings, that indicates the measures proposed for protecting individuals and property for dust control and for noise control. Indicate proposed locations and construction of barriers.
- B. Schedule of Selective Demolition Activities: Indicate the following:
  - 1. Detailed sequence of selective demolition and removal work, with starting and ending dates for each activity. Ensure Owner's on-site operations are uninterrupted.
  - 2. Interruption of utility services. Indicate how long utility services will be interrupted.
  - 3. Coordination for shutoff, capping, and continuation of utility services.
  - 4. Use of elevator and stairs.
  - 5. Coordination of Owner's continuing occupancy of portions of existing building.

- 6. Locations of proposed dust and noise control temporary partitions and means of egress, including for other tenants affected by selective demolition operations.
- 7. Means of protection for items to remain and items in path of waste removal from building.
- C. Inventory: After selective demolition is complete, submit a list of items that have been removed and salvaged and provide to Owner.
- D. Pre demolition Photographs: Show existing conditions of adjoining construction and site improvements, including finish surfaces that might be misconstrued as damage caused by selective demolition operations. Submit before Work begins.
- E. Project Closeout Submittals:
  - 1. Inventory: Submit a list of items that have been removed and salvaged
  - 2. Record drawings at Project closeout indication as-built conditions.
  - 3. Identify and accurately locate capped utilities and other subsurface structural, electrical, or mechanical conditions.

## 1.07 QUALITY ASSURANCE

- A. Regulatory Requirements: Comply with governing EPA notification regulations before beginning selective demolition. Comply with hauling and disposal regulations of authorities having jurisdiction.
- B. Standards: Comply with ANSI A10.6 and NFPA 241.
- C. Pre-demolition Conference: Conduct conference at Project site. Review methods and procedures related to selective demolition including, but not limited to, the following:
  - 1. Inspect and discuss condition of construction to be selectively demolished.
  - 2. Review and finalize selective demolition schedule and verify availability of materials, demolition personnel, equipment, and facilities needed to make progress and avoid delays.
  - 3. Review requirements of work performed by other trades that rely on substrates exposed by selective demolition operations.

#### 1.08 FIELD CONDITIONS

- A. Owner will occupy portions of building adjacent to selective demolition area. Conduct selective demolition so Owner's operations will not be disrupted.
- B. Owner assumes no responsibility for condition of areas to be selectively demolished.
  - 1. Conditions existing at time of inspection for bidding purpose will be maintained by Owner as far as practical.
- C. Notify Architect of discrepancies between existing conditions and Drawings before proceeding with selective demolition.
- D. Storage or sale of removed items or materials on-site is not permitted.
- E. Utility Service: Maintain existing utilities indicated to remain in service and protect them against damage during selective demolition operations.
  - 1. Maintain fire-protection facilities in service during selective demolition operations.

## 1.09 SCHEDULING

A. Arrange selective demolition schedule so as not to interfere with Owner's on site operations.

#### 1.10 WARRANTY

A. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during selective demolition, by methods and with materials so as not to void existing warranties.

## **PART 2 PRODUCTS**

### 2.01 PEFORMANCE REQUIREMENTS

- A. Regulatory Requirements: Comply with governing EPA notification regulations before beginning selective demolition. Comply with hauling and disposal regulations of authorities having jurisdiction.
- B. Standards: Comply with ANSI/ASSE A10.6 and NFPA 241.

### 2.02 REPAIR MATERIALS

- A. Use repair materials identical to existing materials.
  - 1. If identical materials are unavailable or cannot be used for exposed surfaces, use materials that visually match existing adjacent surfaces to the fullest extent possible.
  - 2. Use materials whose installed performance equals or surpasses that of existing materials.
- B. Comply with material and installation requirements specified in individual Specification Sections.

### **PART 3 EXECUTION**

# 3.01 EXAMINATION

- A. Verify that utilities have been disconnected and capped before starting selective demolition operations.
- B. Survey existing conditions and correlate with requirements indicated to determine extent of selective demolition required.
- C. When unanticipated mechanical, electrical, or structural elements that conflict with intended function or design are encountered, investigate and measure the nature and extent of conflict. Promptly submit a written report to Architect.
- D. Survey of Existing Conditions: Record existing conditions by use of preconstruction photographs.
  - 1. Inventory and record the condition of items to be removed and salvaged. Provide photographs of conditions that might be misconstrued as damage caused by salvage operations.
  - 2. Before selective demolition or removal of existing building elements that will be reproduced or duplicated in final Work, make permanent record of measurements, materials, and construction details required to make exact reproduction.

## 3.02 UTILITY SERVICES AND MECHANICAL/ELECTRICAL SYSTEMS

- A. Existing Services/Systems to Remain: Maintain services/systems indicated to remain and protect them against damage.
  - Comply with requirements for existing services/systems interruptions specified in Section 011000
    "Summary of Work."
- B. Existing Services/Systems to Be Removed, Relocated, or Abandoned: Locate, identify, disconnect, and seal or cap off indicated utility services and mechanical/electrical systems serving areas to be selectively demolished.
  - 1. Arrange to shut off indicated utilities with utility companies.
  - 2. If services/systems are required to be removed, relocated, or abandoned, provide temporary services/systems that bypass area of selective demolition and that maintain continuity of services/systems to other parts of building.
  - 3. Conduit to Be Removed: Remove portion of conduit / piping as necessary for floor restoration and cap or plug remaining piping not to be reused with same or compatible piping material.
  - 4. Equipment to Be Removed: Disconnect and cap services and remove equipment.

### 3.03 PREPARATION

- A. Site Access and Temporary Controls: Conduct selective demolition and debris-removal operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.
- B. Temporary Facilities: Provide temporary barricades and other protection required to prevent injury to people and damage to adjacent buildings and facilities to remain.
  - 1. Provide protection to ensure safe passage of people around selective demolition area and to and from occupied portions of building.
  - 2. Protect walls, ceilings, floors, and other existing finish work that are to remain or that are exposed during selective demolition operations.
  - 3. Cover and protect furniture, furnishings, and equipment that have not been removed.

## 3.04 SELECTIVE DEMOLITION, GENERAL

- A. General: Demolish and remove existing construction only to the extent required by new construction and as indicated. Use methods required to complete the Work within limitations of governing regulations and as follows:
  - 1. Proceed with selective demolition systematically, from higher to lower level.
  - 2. Neatly cut openings and holes plumb, square, and true to dimensions required. Use cutting methods least likely to damage construction to remain or adjoining construction. Use hand tools or small power tools designed for sawing or grinding, not hammering and chopping, to minimize disturbance of adjacent surfaces. Temporarily cover openings to remain.
  - 3. Cut or drill from the exposed or finished side into concealed surfaces to avoid marring existing finished surfaces.
  - 4. Do not use cutting torches.
  - 5. Maintain adequate ventilation.
  - 6. Locate selective demolition equipment and remove debris and materials so as not to impose excessive loads on supporting walls, floors, or framing.
  - 7. Dispose of demolished items and materials promptly.

## B. Removed and Salvaged Items:

- 1. Clean salvaged items.
- 2. Pack or crate items after cleaning. Identify contents of containers.
- 3. Store items in a secure area until delivery to Owner.
- 4. Transport items to Owner's storage area on-site as designated by Owner.
- 5. Protect items from damage during transport and storage.

## C. Removed and Reinstalled Items:

- 1. Clean and repair items to functional condition adequate for intended reuse.
- 2. Pack or crate items after cleaning and repairing. Identify contents of containers.
- 3. Protect items from damage during transport and storage.
- 4. Reinstall items in locations indicated. Comply with installation requirements for new materials and equipment. Provide connections, supports, and miscellaneous materials necessary to make item functional for use indicated.
- D. Existing Items to Remain: Protect construction indicated to remain against damage and soiling during selective demolition. When permitted by Architect, items may be removed to a suitable, protected storage location during selective demolition and reinstalled in their original locations after selective demolition operations are complete.

## 3.05 SELECTIVE DEMOLITION PROCEDURES FOR SPECIFIC MATERIALS

A. Floor Coverings: Remove floor coverings and adhesive according to industry standard recommendations. Do not use methods requiring solvent-based adhesive strippers.

# 3.06 PATCHING AND REPAIRS

- A. General: Promptly repair damage to adjacent construction caused by selective demolition operations.
- Repairs: Where repairs to existing surfaces are required, patch to produce surfaces suitable for new materials.
  - 1. Completely fill holes and depressions in existing walls that are to remain with an approved patching material applied according to manufacturer's written recommendations.
- C. Finishes: Restore exposed finishes of patched areas and extend restoration into adjoining construction in a manner that eliminates evidence of patching and refinishing.
- D. Floors and Walls: Provide an even surface of uniform finish color, texture, and appearance. Remove existing floor and wall coverings as required for defined Scope of Work and, if necessary, patch or repair deteriorated areas to achieve uniform color and appearance where materials are to remain exposed.
  - 1. Provide materials and comply with installation requirements specified in other Sections of these Specifications.

## SELECTIVE DEMOLITION

- 2. Where patching occurs in a painted surface, apply primer and intermediate paint coats over patch and apply final paint coat over entire unbroken surface containing patch. Provide additional coats until patch blends with adjacent surfaces.
- E. Ceilings: Patch or repair existing ceilings as necessary to provide an even-plane surface of uniform appearance.

## 3.07 DISPOSAL OF DEMOLISHED MATERIALS

- A. General: Except for items or materials indicated to be recycled, reused, salvaged, reinstalled, or otherwise indicated to remain Owner's property, remove demolished materials from Project site and legally dispose of them in an EPA-approved landfill.
  - 1. Do not allow demolished materials to accumulate on-site.
  - 2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.
  - 3. Remove debris from elevated portions of building by chute, hoist, or other device that will convey debris to grade level in a controlled descent.
- B. Burning: Do not burn demolished materials.
- C. Disposal: Transport demolished materials off Owner's property and legally dispose of them.

## 3.08 CLEANING

A. Clean adjacent surfaces and improvements of dust, dirt, and debris caused by selective demolition operations. Return adjacent areas to condition existing before selective demolition operations began.

# SECTION 051200 STRUCTURAL STEEL FRAMING

## PART 1 GENERAL

### 1.01 SECTION INCLUDES

- A. Structural steel framing members.
- B. Base plates, shear stud connectors.
- C. Grouting under base plates.

### 1.02 REFERENCE STANDARDS

- A. AISC (MAN) Steel Construction Manual; 2023.
- B. AISC 303 Code of Standard Practice for Steel Buildings and Bridges; 2022.
- C. ASTM A36/A36M Standard Specification for Carbon Structural Steel; 2019.
- D. ASTM A123/A123M Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products; 2017.
- E. ASTM A563/A563M Standard Specification for Carbon and Alloy Steel Nuts (Inch and Metric); 2021a.
- F. ASTM F436/F436M Standard Specification for Hardened Steel Washers Inch and Metric Dimensions; 2019.
- G. ASTM F959/F959M Standard Specification for Compressible-Washer-Type Direct Tension Indicators for Use with Structural Fasteners, Inch and Metric Series; 2017a.
- H. ASTM F3125/F3125M Standard Specification for High Strength Structural Bolts and Assemblies, Steel and Alloy Steel, Heat Treated, Inch Dimensions 120 ksi and 150 ksi Minimum Tensile Strength, and Metric Dimensions 830 MPa and 1040 MPa Minimum Tensile Strength; 2023.
- IAS AC172 Accreditation Criteria for Fabricator Inspection Programs for Structural Steel AC172; 2019.
- J. RCSC (HSBOLT) Specification for Structural Joints Using High-Strength Bolts; Research Council on Structural Connections; 2020.
- K. SSPC-SP 3 Power Tool Cleaning; 2018.

### 1.03 COORDINATION

- A. Coordinate selection of shop primers with topcoats to be applied over them. Comply with paint and coating manufacturers' written recommendations to ensure that shop primers and topcoats are compatible with one another.
- B. Coordinate installation of anchorage items to be ebedded in or attached to other construction without delaying the Work. Provide setting diagrams, sheet metal templates, instructions, and directions for installation.

### 1.04 PREINSTALLTION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

## 1.05 ACTION SUBMITTALS

- A. See Section 013300 Submittals, for submittal procedures.
- B. Product Data:
  - 1. Structural -steel materials.
  - 2. High-strength, bolt-nut-washer assemblies.
  - 3. Anchor rods.
  - 4. Shop primer.
  - 5. Shrinkage-resistant grout.
- C. Shop Drawings: Show fabrication of structural-steel components.

Structural Steel Framing

- 1. Include details of cuts, connections, splices, camber, holes, and other pertinent data.
- 2. Include embedment Drawings.
- 3. Indicate type, size, and length of bolts, distinguising between shop and field bolts. Identify pretensioned and slip-critical, high-strength bolted connections.
- 4. Identify members not to be shop primed.
- D. Delegated Design Submittal: For structural-steel connections indicated on Drawings to comply with design loads, include analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

## 1.06 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer and fabricator.
- B. Paint Compatibility Certifications: From manufacturers of topcoats applied over shop primers, certifying that shop primers are compatible with topcoats.
- C. Mill test reports for structural-steel materials, including chemical and physical properties.
- D. Product Test Reports: For the following:
  - 1. Bolts, nuts, and washers, including mechanical properties and chemical analysis.
  - 2. Direct-tension indicators.
  - 3. Tension-control, high-strength, blot-nut-washer assemblies.
- E. Survey of existing conditions.
- F. Source quality-control reports.
- G. Field quality-control reports.

### 1.07 QUALITY ASSURANCE

- A. Fabricate structural steel members in accordance with AISC (MAN) "Steel Construction Manual."
- B. Fabricator Qualifications: A qualified steel fabricator that is accredited by the International Accreditation Service (IAS) Fabricator Inspection Program for Structural Steel in accordance with IAS AC172.
- C. Installer Qualifications: A qualified Installer who participates in the AISC Quality Certification Program and is designated an AISC-Certified Erector.
- D. Shop-Painting Applicator Qualifications: Qualified in accordance with AISC's Sophisticated Paint.

## 1.08 DELIVERY, STORAGE, AND HANDLING

- A. Store materials to permit easy access for inspection and identification. Keep steel members off ground and spaced by using pallets, dunnage, or other supports and spacers. Protect steel members and packaged materials from corrosion and deterioration.
  - 1. Do not store materials on structure in a manner that might cause distortion, damage, or overload to members or supporting structures. Repair or replace damaged materials or structures as directed.
- B. Store fasteners in a protected place in sealed containers with manufacturer's label intact.
  - 1. Fasteners may be repackaged provided Owner's testing and inspecting agency observes repackaging and seals containers.
  - 2. Clean and relubricate bolts and nuts that become dry or rusty before use.
  - 3. Comply with manufacturers' written recommendations for cleaning and lubricating ASTM F3125/F3125M, Grade F1852 bolt assemblies and for retesting bolt assemblies after lubrication.

### PART 2 PRODUCTS

# 2.01 PERFORMANCE REQUIREMENTS

- A. Comply with applicable provisions of the following specifications and documents.
  - 1. ANSI/AISC 303.
  - 2. ANSI/AISC 341.
  - 3. ANSI/AISC 360.

Structural Steel Framing

- 4. RCSC's "Specification for Structural Joints Using High-Strength Bolts."
- B. Connection Design Information:
  - 1. Option 3 and 3B: Design connections and final configuration of member reinforcements at connections in accordance with ANSI/AISC 303 by fabricator's qualified professional engineer.
    - a. Use Allowable Stress Design; data are given at service-load level.
- C. Moment Connections: Type FR, fully restrained.
- D. Construction: Braced frame.

### 2.02 MATERIALS

- A. Steel Tubing: ASTM A501/A501M hot-formed structural tubing.
- B. Steel Angles, Channels, and M Shapes: ASTM A36/A36M.
- C. High-Strength Structural A325 Bolts, Nuts, and Washers: ASTM F3125/F3125M, Type 1, Grade A325, heavey-hex structural bolts; with matching compatible ASTM A563/A563M, Grade DH, heavy-hex carbon steel nuts; and ASTM F436/F436M, Type 1, hardened carbon-steel washers; all with plain finish.
- D. Direct-Tension Indicators: ASTM F959/F959M, Type 325-1, compressible-washer type with plain finish.
- E. Steel Primer: Comply with Section 099123 "Interior Painting."
- F. Faricator's Standard lead- and chromate-free, nonasphaltic, rust-inhibiting primer complying with MPI#79 and compatible with topcoat.
- G. Metallic, Shrinkage-Resistant Grout: ASTM C1107/C1107M; factory-packaged, metallic aggregate grout, mixed with water to consistency suitable for application and a 30-minute working time.
  - 1. Minimum Compressive Strength at 48 Hours: 2,000 pounds per square inch.
  - 2. Minimum Compressive Strength at 28 Days: 7,000 pounds per square inch.

### 2.03 FABRICATION

- A. Structural Steel: Fabricate and assemble in shop to greatest extent possible. Fabricate in accordance with ANSI/AISC303 and to ANSI/AISC 360.
  - 1. Camber structural-steel members where indicated.
  - 2. Fabricate beams with rolling camber up.
  - 3. Identify high-strength structural steel in accordance with ASTM A6/A6M and maintain markings until structural-steel framing has been erected.
  - 4. Mark and match-mark materials for field assembly.
  - 5. Complete structural-steel assembles, including welding of units, before starting shop-priming operations.
- B. Thermal Cutting: Perform thermal cutting by machine to greatest extend possible.
  - 1. Plane thermally cut edges to be welded to comply with requirements in AWS D1.1/D1.1M.
- C. Bolt Holes: Cut, drill, or punch standard bolt holes perpendicular to metal surfaces.
- D. Finishing: Accurately finish ends of columns and other members transmitting bearing loads.
- E. Cleaning: Clean and prepare steel surfaces that are to remain upainted in accordance with SSPC-SP1. SSPC-SP 2. SSPC-SP 3.

### 2.04 SHOP CONNECTIONS

- A. High-Strength Bolts: Shop install high-strength bolts in accordance with RCSC's "Specification for Structural Joints Using High-Strength Bolts" for type of bolt and type of joint specified.
  - 1. Joint Type: Snug Tightened.

## 2.05 SHOP PRIMING

- A. Shop prime steel surfaces, except the following:
  - 1. Surfaces embedded in concrete or mortar. Extend priming of partially embedded members to a depth of 2 inches.
  - 2. Surfaces to be field welded.

Structural Steel Framing

- 3. Surfaces of high-strength bolted, slip-critical connections.
- 4. Galvanized surfaces unless indicated to be painted.
- 5. Corrosion-resisting (weathering) steel surfaces
- 6. Surfaces enclosed in interior construction.
- B. Surface Preparation of Steel: Clean surfaces to be painted. Remove loose rust and mill scale and spatter, slag, or flux deposits. Prepare surfaces in accordance with the following specifications and standards.
  - 1. SSPC-SP 2.
  - SSPC-SP 3.
  - 3. SSPC-SP 7 (WAB)/NACE WAB-4.
  - 4. SSPC-SP 14 (WAB)/NACE WAB-8.
  - SSPC-SP
  - 6. SSPC-SP 6 (WAB)/NACE WAB-3.
  - 7. SSPC-SP 10 (WAB)/NACE WAB-2.
  - 8. SSPC-SP 5 (WAB)/NACE WAB-1.
  - 9. SSPC-SP 8.
- C. Surface Preparation of Galvanized Steel: Prepare galvanized-steel surfaces for shop priming by thoroughly cleaning steel of grease, dirt, oil, flux, and other foreign matter, and treating with etching cleaner or in accordance with SSPC-SP 16.
- D. Priming: Immediately after surface preparation, apply primer in accordance with manufacturer's written instructions and at rate recommended by SSPC to provide a minimum dry film thickness of 1.5 mils. Use priming methods that result in full coverage of joints, corners, edges, and exposed surfaces.
  - 1. Stripe paint corners, crevices, bolts, welds, and sharp edges.
  - Apply two coats of shop paint to surfaces that are inaccessible after assembly or erection. Change color of second coat to distinguish it from first.

### **2.06 FINISH**

- A. Prepare structural component surfaces in accordance with SSPC-SP 3.
- B. Galvanize structural steel members to comply with ASTM A123/A123M. Provide minimum 1.7 oz/sq ft galvanized coating.

## 2.07 SOURCE QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to perform shop tests and inspections.
  - 1. Allow testing agency access to places where structural-steel work is being faricated or produced to perform tests and inspections.
- B. Bolt Connections: Inspect shop-bolted connections in accordance with RCSC (HSBOLT) "Specification for Structural Joints Using High-Strength Bolts."
- C. Prepare test and inspection reports.

## PART 3 EXECUTION

### 3.01 EXAMINATION

- A. Verify, with certified steel erector present, elevations of concrete- and masonry-bearing surfaces and locations of anchor rods, bearing plates, and other embedments for compliance with requirements.
  - 1. Prepare a certified survey of existing conditions. Include bearing surfaces, anchor rods, bearing plates, and other embedments showing dimensions, locations, angles, and elevations.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.
- C. Verify that conditions are appropriate for erection of structural steel and that the work may properly proceed.

### 3.02 PREPARATION

- A. Provide temporary shores, guys, braces, and other supports during erection to keep structural steel secure, plumb, and in alignment against temporary construction loads and loads equal in intensity to design loads. Remove temporary supports when permanent structural-steel, connections, and bracing are in place unless otherwise indicated on Drawings.
  - Do not remove temporary shoring supporting composite deck construction and structural-steel framing until cast-in-place concrete has attained its design compressive strength.

### 3.03 ERECTION

- A. Set structural steel acurately in locations and to elevations indicated and in accordance with ANSI/AISC 303 and ANSI/AISC/AISC 360.
- B. Baseplates, Bearing Plates, and Leveling Plates: Clean concrete- and masonry-bearing surfaces of bond-reducing materials, roughen surfaces prior to setting plates. Clean bottom surfaces of plates.
  - 1. Set plates for structural members on wedges, shims, or setting nuts as required.
  - 2. Weld plate washers to top of baseplate.
  - 3. Snut-tighten anchor rods after supported members have been positioned and plumbed. Do not remove wedges or shims but, if protruding, cut off flush with edge of plate before pasking with grout.
  - 4. Promptly pack shrinkage-resistant grout solidaly between bearing surfaces and plates, so no voids remain. Neatly finish exposed surfaces; protect grout and allow to cure. Comply with manufacturer's written installation instructions for grouting.
- C. Maintain erection tolerances of structural steel within ANSI/AISC 303.
- D. Align and adjust various members that form part of complete frame or structure before permanently fastening. Before assembly, clean bearing surfaces and other surfaces that are in permanent contact with members. Perform necessary adjustaments to compensate for discrepancies in elevations and alignment.
  - 1. Level and plumb individual members of structure. Slope roof framing members to slops indicated in Drawings.
  - 2. Make allowances for difference between temperature at time of erection and mean temperature when structure is completed and in service.
- E. Do not use thermal cutting during erection unless approved by Architect. Finish thermally cut sections within smoothness limits in AWS D1.1/D1.1M.
- F. Do not enlarge unfair holes in members by burning or using drift pins. Ream holes that must be enlarged to admit bolts.

### 3.04 FIELD CONNECTIONS

- A. High-Strength Bolts: Install high-strength bolts in accordance with RCSC's "Specification for Structural Joints Using High-Strength Bolts" for bolt and joint type specified.
  - 1. Joint Type: Snug tightened.

### 3.05 REPAIR

- A. Galvanized Surfaces: Cleann areas where galvanizing is damaged or missing, and repair galvanizing to comply with ASTM A780/A780M.
- B. Touchup Painting:
  - 1. Immediately after erection, clean exposed areas where primer is damaged or missing, and paint with the same material as used for shop painting to comply with SSPC-PA 1 for touching up shopprimed surfaces.
    - a. Clean and prepare surfaces by SSPC-SP 2 hand-tool cleaning of SSPC-SP 3 power-tool cleaning.
  - 2. Cleaning and touchup painting are specified in Section 099123 "Interior Painting."

## 3.06 FIELD QUALITY CONTROL

A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.

Structural Steel Framing

O2339-01-Howerton State Office Building-Renovate

B.	High-Strength Bolts: Provide testing and verification of field-bolted connections in accordance with RCSC (HSBOLT) "Specification for Structural Joints Using High-Strength Bolts."
	END OF SECTION

# SECTION 055000 METAL FABRICATIONS

## PART 1 GENERAL

## 1.01 SECTION INCLUDES

A. Shop fabricated steel items, including: Toilet partition suspension members.

### 1.02 RELATED REQUIREMENTS

- A. Section 051200 Structural Steel Framing.
- B. Section 102113.19 Plastic Toilet Compartments: Ceiling-hung toilet partitions.

## 1.03 REFERENCE STANDARDS

- A. ASTM A36/A36M Standard Specification for Carbon Structural Steel; 2019.
- B. ASTM A123/A123M Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products; 2017.
- C. AWS A2.4 Standard Symbols for Welding, Brazing, and Nondestructive Examination; 2020.
- D. AWS D1.1/D1.1M Structural Welding Code Steel; 2020, with Errata (2023).
- E. AWS D1.2/D1.2M Structural Welding Code Aluminum; 2014, with Errata (2020).
- F. IAS AC172 Accreditation Criteria for Fabricator Inspection Programs for Structural Steel AC172; 2019.
- G. SSPC-Paint 20 Zinc-Rich Coating (Type I Inorganic, and Type II Organic); 2019.

#### 1.04 SUBMITTALS

- A. See Section 013300 Submittals, for submittal procedures.
- B. Shop Drawings: Indicate profiles, sizes, connection attachments, reinforcing, anchorage, size and type of fasteners, and accessories. Include erection drawings, elevations, and details where applicable.
  - 1. Indicate welded connections using standard AWS A2.4 welding symbols. Indicate net weld lengths.
  - 2. Design data: Submit drawings and supporting calculations, signed and sealed by a qualified professional structural engineer.
    - a. Include the following, as applicable:
      - 1) Design criteria.
      - 2) Engineering analysis depicting stresses and deflections.
      - 3) Member sizes and gauges.
      - 4) Details of connections.
      - 5) Support reactions.
      - 6) Bracing requirements.
- C. Designer's Qualification Statement.
- D. Fabricator's Qualification Statement: Provide documentation showing steel fabricator is accredited under IAS AC172.

## 1.05 QUALITY ASSURANCE

- A. Design under direct supervision of a Professional Structural Engineer experienced in design of this work and licensed in the State in which the Project is located.
- B. Welder Qualifications: Welding processes and welding operators qualified in accordance with AWS D1.1/D1.1M and AWS D1.2/D1.2M and dated no more than 12 months before start of scheduled welding work.
- C. Fabricator Qualifications: A qualified steel fabricator that is accredited by IAS AC172.

### PART 2 PRODUCTS

### 2.01 MATERIALS - STEEL

- A. Steel Sections: ASTM A36/A36M.
- B. Touch-Up Primer for Galvanized Surfaces: SSPC-Paint 20, Type I Inorganic, complying with VOC limitations of authorities having jurisdiction.

### 2.02 FABRICATION

- A. Fit and shop assemble items in largest practical sections, for delivery to site.
- B. Fabricate items with joints tightly fitted and secured.
- C. Grind exposed joints flush and smooth with adjacent finish surface. Make exposed joints butt tight, flush, and hairline. Ease exposed edges to small uniform radius.
- D. Exposed Mechanical Fastenings: Flush countersunk screws or bolts; unobtrusively located; consistent with design of component, except where specifically noted otherwise.
- E. Furnish components required for anchorage of fabrications. Fabricate anchors and related components of same material and finish as fabrication, except where specifically noted otherwise.

## 2.03 FABRICATED ITEMS

A. Toilet Partition Suspension Members: Steel channel sections; mill finish.

### 2.04 FINISHES - STEEL

A. Galvanizing of Structural Steel Members: Galvanize after fabrication to ASTM A123/A123M requirements. Provide minimum 1.7 oz/sq ft galvanized coating.

### 2.05 FABRICATION TOLERANCES

- A. Squareness: 1/8 inch maximum difference in diagonal measurements.
- B. Maximum Offset Between Faces: 1/16 inch.
- C. Maximum Misalignment of Adjacent Members: 1/16 inch.
- D. Maximum Bow: 1/8 inch in 48 inches.
- E. Maximum Deviation From Plane: 1/16 inch in 48 inches.

### PART 3 EXECUTION

## 3.01 EXAMINATION

A. Verify that field conditions are acceptable and are ready to receive work.

## 3.02 INSTALLATION

- A. Install items plumb and level, accurately fitted, free from distortion or defects.
- B. Provide for erection loads, and for sufficient temporary bracing to maintain true alignment until completion of erection and installation of permanent attachments.
- C. Obtain approval prior to site cutting or making adjustments not scheduled.

## 3.03 TOLERANCES

- A. Maximum Variation From Plumb: 1/4 inch per story, non-cumulative.
- B. Maximum Offset From True Alignment: 1/4 inch.
- C. Maximum Out-of-Position: 1/4 inch.

# SECTION 061000 ROUGH CARPENTRY

## **PART 1 GENERAL**

### 1.01 SUMMARY

- A. Section Includes:
  - 1. Framing with dimension lumber.
  - 2. Wood blocking and nailers.
  - 3. Wood furring.
  - 4. Plywood backing panels.

### 1.02 DEFINITIONS

- A. Boards or Strips: Lumber is less than 2 inches nominal (38 mm actual) size in least dimension.
- B. Dimension Lumber: Lumber of 2 inches nominal (38 actual) size or greater but less than 5 inches nominal (114 actual) size in least dimension.
- C. Exposed Framing: Framing not concealed by other construction.

## 1.03 INFORMATIONAL SUBMITTALS

- A. Material Certificates:
  - 1. For dimension lumber specified to comply with minimum allowable unit stresses. Indicate species and grade selected for each use and design values approved by ALSC Board of Review.
- B. Reports: For the following, from ICC-ES:
  - 1. Fire-retardant-treated wood.
  - 2. Power-driven fasteners.
- C. Qualification Statements: For testing agency providing classification marking for fire-retardant treated material, an inspection agency acceptable to authorities having juridiction that periodically performs inspections to verfiy that the material bearing the classification marking is representative of the material tested.

## 1.04 DELIVERY, STORAGE, AND HANDLING

- A. Stack wood products flat with spacers beneath and between each bundle to provide air circulation. Protect wood products from weather by covering with waterproof sheeting, securely anchored. Provide for air circulation around stacks and under coverings.
- B. REFERENCE STANDARDS
- C. AWPA U1 Use Category System: User Specification for Treated Wood; 2024.
- D. PS 20 American Softwood Lumber Standard; 2021.

# PART 2 PRODUCTS

## 2.01 WOOD PRODUCTS, GENERAL

- A. Dimension Lumber: Comply with DOC PS 20 and requirements of specified grading agencies.
  - 1. If no species is specified, provide species graded by the agency specified; if no grading agency is specified, provide lumber graded by grading agency meeting the specified requirements.
  - 2. Grading Agency: Grading agency whose rules are approved by the Board of Review, American Lumber Standard Committee at www.alsc.org, and who provides grading service for the species and grade specified; provide lumber stamped with grade mark unless otherwise indicated.
  - 3. Maximum Moisture Content of Lumber:
    - a. Boards: 19 percent
    - b. Dimension Lumber: 15 percent for 2-inch nominal (38-mm actual) thickness or less; 19 percent for more than 2-inch nominal (38-mm actual) thickness unless otherwise indicated.

### 2.02 FIRE-RETARDANT TREATMENT

- A. General: Where fire-retardant-treated materials are indicated, materials shall comply with requirements in this article, that are acceptable to authorities having jurisdiction, and with fire-test-response characteristics specified as determined by testing identical products per test method indicated by a qualified testing agency.
- B. Fire-Retardant-Treated Lumber and Plywood by Pressure Process: Products with a flame-spread index of 25 or less when tested according to ASTM E84, and with no evidence of significant progressive combustion when the test is extended an additional 20 minutes, and with the flame front not extending more than 10.5 feet (3.2 m) beyond the centerline of the burners at any time during the text.
  - 1. Treatment shall not promote corrosion of metal fasteners.
  - 2. Interior Type A: Treated materials shall have a moisture content of 28 percent or less when tested according to ASTM D3201/D3201M at 92 percent relative humidity. Use where exterior type is not indicated.
  - 3. Design Value Adjustment Factors: Treated lumber shall be tested according to ASTM D5664 and design value adjustment factors shall be calculated according to ASTM D6841.
- C. Kiln-dry lumber treatment to maximum moisture content of 19 percent.
- D. Identify fire-retardent-treated wood with appropriate classification marking of qualified testing agency.
  - 1. For exposed lumber indicated to receive a stained or natural finish, mark end or back of each piece.
- E. Application: Treat all rough carpentry unless otherwise indicated.
  - 1. Concealed blocking.
  - 2. Plywood backing panels.

### 2.03 DIMENSION LUMBER FRAMING

- A. Non-Load-Bearing Interior Partitions by Grade: Standard, Stud, or No. 3 grade.
  - 1. Application: All interior partitions
  - 2. Species:
    - a. Hen-fir (north); NLGA.
    - b. Southern pine or mixed southern pine; SPIB.
    - c. Spruce-pine-fir; NGLA.
    - d. Hem-fir; WCLIB, or WWPA.
    - e. Spruce-pine-fir (south); NeLMA, WCLIB, or WWPA.

### 2.04 MISCELLANEOUS LUMBER

- A. Provide miscellaneous lumber indicated and lumber for support or attachement of other construction, including the following:
  - 1. Blocking.
  - 2. Nailers.
  - 3. Furring
- B. Dimension Lumber Items: Standard, Stud, or No. 3 grade lumber of any of the following species:
  - 1. Hen-fir (north); NLGA.
  - 2. Mixed southern pine or southern pine; SPIB.
  - 3. Spruce-pine-fir; NLGA.
  - 4. Hem-fir; WCLIB or WWPA.
  - 5. Spruce-pine-fir (south); NeLMA, WCLIB, or WWPA.
- C. Concealed Boards: 19 percent maximum moisutre content and any of the following species and grades:
  - 1. Mixed southern pinee or southern pine; No. 3 grade; SPIB
  - 2. Hem-fir or hem-fir (north); Standard or No. 3 Common grade; NLGA, WCLIB, or WWPA.
  - 3. Spruce-pine-fir (south) or spruce-pine-fir; Standard or No. 3 Common grade; NeLMA, NLGA, WCLIB, or WWPA.

- D. For blocking not used for attachment of other construction, Utility, Stud, or No. 3 grade lumber of any species may be used provided that it is cut and selected to elminate defects that will interfere with its attachement and purpose.
- E. For blocking and nailers used for other construction, select and cut lumber to eliminate knots and other defects that will interfere with attachment of other work.
- F. For furring strips for installing plywood or hardboard paneling, select boards with no knots capable of producing bent-over nails and damage to paneling.

## 2.05 PLYWOOD BACKING PANELS

A. Equipment Backing Panels: Plywood, DOC PS 1, fire-retardant treated, in thickness indicated or, if not indicated, not less than 1/2-inch (13-mm) nominal thickness.

### 2.06 FASTENERS

- A. General: Fasteners shall be of size and type indicated and shall comply with requirements specified in this article for material and manufacture. Provide nails or screws, in sufficient length, to penetrate not less than 1-1/2 inches (38 mm) into wood substrate.
- B. Nails, Brads, Staples: ASTM F1667.
- C. Power-Driven Fasteners: Fasteners systems with an evaluation report acceptable to authorities having jurisdiction, based on ICC-ES AC70.
- D. Post-Installed Anchors: Fasteners systems with an evaluation report acceptable to authorities having jurisdication, based on ICC-ES AC01, ICC-ES AC58, ICC-ES AC193 or ICC-ES AC308 as appropriate for the substrate.

### 2.07 METAL FRAMING ANCHORS

- A. Allowable design loads, as published by manufacturer, shall meet or exceed those of products of manufacturers listed. Manufacturer's published values shall be determined from empirical data or by rational engineering analysis and demonstrated by comprehesive testing performed by a qulified independent testing agency. Framing anchors shall be punched for fasteners adequate to withstand same loads as framing anchors.
  - 1. Cleveland Steel Speciality
  - 2. KC Metal Products
  - 3. Phoenix Metal Products
  - 4. Simpson Strong-Toe
  - 5. USP Structural Connectors, Inc
- B. Galvanized-Steel Sheet: Hot-dip, zinc-coated steel sheet complying with ASTM A653/A653M, G60 (Z180) coating designation.
  - 1. Use for interior locations unless otherwise indicated.
- C. Hot-Dip, Heavy-Galvanized Steel Sheet: ASTM A653/A653M; structural steel (SS), high strength low-alloy steel Type A (HSLAS Type A), or high-strength low-alloy steel Type B (HSLAS Type B); G185 (Z550) coating designation; and not less than 0.036 inch (0.9 mm) thick.
  - 1. Use for wood-preservative-treated lumber and where indicated.
    - a. Treated Lumber and Plywood: Comply with requirements of AWPA U1 Use Category System for wood treatments determined by use categories, expected service conditions, and specific applications.

### PART 3 EXECUTION

### 3.01 INSTALLATION - GENERAL

- A. Framing Standard: Comply with AF&PA's WCD 1, "Details for conventional Wood Frame Construction, "unless otherwise indicated."
- B. Framing with Engineered Wood Products: Install engineered wood products to comply with manufacturer's written instructions.

- C. Set work to required levels and lines, with members plumb, true to line, cut, and fitted. Fit rough carpentry accurately to other construction. Locate furring, nailers, blocking, grounds, and similar supports to comply with requirements for attaching other construction.
- D. Install plywood backing panels by fastening to studs; coordinate locations with utilites requiring backing panels. Install fire-retardant-treated plywood backing panels with calssifcation marking of testing agency exposed to view.
- E. Install shear wall panels to comply with manufacturer's written instructions.
- F. Install metal framing anchors to comply with manufacturer's written instructions. Install fasteners through each fasteners hole.
- G. Provide, blocking and framing as indicated and as required to support facing materials, fixtures, speciality items, and trim.
  - 1. Provide metal clips for fastening gypsum board or lath at corners and intersections where framing or blocking does not provide a surface for fastening edges of panels. Space clips not more than 16 inches (406 mm) o.c.
- H. Sort and select lumber so that natural characteristics do not interfere with installation or with fastening other materials to lumber. Do not use materials with defects that interfere with function of member or pieces that are too small to use with minimum number of joints or optimum joint arrangement.
- Comply with AWPA M4 for applying field treatment to cut surfaces of preservative-treated lumber.
  - 1. Use inorganic boron for items that are continuously preotected from liquid water.
  - 2. Use copper naphthenate for items not continuously protected from liquid water.
- J. Where wood-preservative-treated lumber is installed adjacent to metal decking, install continuous flexible flashing separator between wood and metal decking.
- K. Securely attach rough carpentry work to substrate by anchoring and fastening as indicated, complying with the following:
  - 1. Table 2304.9.1, "Fastening Schedule," in ICC's International Building Code (IBC).
  - 2. ICC-ES evaluation report for fastener.
- L. Use steel common nails unless otherwise indicated. Select fasteners of size that will not fully penetrate members where opposite side will be exposed to view or will receive finish materials. Make tight connections between members. Install fasteners without splitting wood. Drive nails snug but do not countersink nail heads unless otherwise indicated.
- M. For exposed work, arrange fasteners in straight rows parallel with edges of members, with fasteners evenly spaced, and with adjacent rows staggered.
  - 1. Comply with approved fastener patterns where applicable.
  - 2. Use common nails unless otherwise indicated. Drive nails snug do not countersink nail heads.

## 3.02 INSTALLATION OF WOOD BLOCKING AND NAILERS

- A. Install where indicated and where required for attaching other work. Form to shapes indicated and cut as required for true line and level of attached work. Coordinate locations with other work involved.
- B. Attach items to substrates to support applied loading. Recess bolts and nuts flush with surfaces unless otherwide indicated.

## 3.03 INSTALLATION OF WOOD FURRING

- A. Instal level and plumb with closure strips at edges and openings. Shim wood as required for tolerance of finish work.
- B. Furring to Receive Plywood or Hardboard Paneling: Install 1-by-3-inch nominal- (19-by-63-mm actual-) size furring horizontally and vertically at 24 inches (610) o.c.
- C. Furring to Receive Gypsum Board: Install 1-by-2-inch nominal- (19-by-38-mm actual-) size furring vertically at 16 inches (406 mm) o.c.
- D. Select material sizes to minimize waste.

- E. Reuse scrap to the greatest extent possible; clearly separate scrap for use on site as accessory components, including: shims, bracing, and blocking.
- F. Where treated wood is used on interior, provide temporary ventilation during and immediately after installation sufficient to remove indoor air contaminants.

# SECTION 064200 STACKED WOOD WALL PANELS

## PART 1 – GENERAL

## 1.01 QUALITY ASSURANCE

- A. Installer Qualifications:
  - 1. a. Minimum 2 years of work with the installation of products in this section.

### 1.02 DELIVERY, STORAGE, AND HANDLING

- A. Deliver wall paneling to project site. Leave the box flat on the floor in its original wrapping until installation.
- B. Environmental Requirements: Maintain following conditions in building for minimum 7 days prior to installation of panels. These conditions must be respected during and after the installation to ensure the lifelong performance.
  - 1. Temperature: 60 to 72 degrees F (16 to 22 degrees C)
  - 2. Humidity: 35 to 55 percent

## 1.03 SUBMITTALS

- A. Product Data: Provide manufacturer's data sheets. Include installation instructions.
- B. Samples: Provide samples for initial selection of patterna and color.
- Maintenance Data: Include recommended cleaning methods, cleaning materials, and stain removal methods.
- D. Maintenance Materials: Furnish extra 5 percent of wood wall panels.
- E. Warranty: Provide manufacturer warranty.

#### 1.04 WARRANTY

- A. Stacked Wood Structural Warranty: 5 years against delamination or separation as a result of a manufacturing defect when maintained in accordance with manufacturer's installation instructions.
- B. Stacked Wood Surface Finish Warranty: 3 years under normal conditions.

## **PART 2 – PRODUCTS**

## 2.01 WOOD PANELING

- A. Basis of Design Product:
  - 1. Finium, USA; Stacked Wood, Geometry Collection, Rhombus Play, HDR 4422
- B. Other Acceptable Manufacturers:
  - 1. Finium, USA.
  - 2. The Wood Veneer Hub
  - 3. Wood Panel Wall, USA

## 2.02 BASIS OF DESIGN MATERIALS

- A. Stacked Wood Walls:
  - 1. Geometry Rhombus Play
- B. Size:
  - 1. Geometry: 14" x 48.5"
- C. Construction:
  - 1. Stacked Wood wall panel made of decorative placed wood strips laminated onto a birch plywood substrate.
- D. Moisture content:
  - 1. Approx. 6 percent at maximum.
- E. Finish:

## STACKED WOOD WALL PANELS

- 1. Natural Oil.
- F. Flammability: per ASTM E8
  - 1. Flame Spread = 75 and Smoke Developed = 185
- G. Accessories
  - 1. Contour Molding: Size: approx. 55" x 1-1/4" x 90"
  - 2. Corner trim: Size approx. 3/4" x 3/4" x 90"
  - 3. Electric Outlet Frames: Single size: approx. 2.75" x 4.5"

## **PART 3 - EXECUTION**

#### 3.01 EXAMINATION

- A. Examine components and/or surface to which Stacked Wood wall panels will be mounted on, or fabricated with, ensuring components are clean, dry, flat, and free of contaminates that could potentially interfere with adhesive bond.
- B. Verify that HVAC system is operating and maintaining occupancy level temperature and humidity conditions.
- C. If either of the above needs attendance, coordinate with responsible entity to correct unsatisfactory conditions prior to the beginning of the installation.

### 3.02 3.02 PREPARATION

A. Acclimatization: Ensure that all Stacked Wood wall panels products are acclimated for a minimum of 2 days.

#### 3.03 INSTALLATION

- A. Install in accordance with manufacturer's installation instructions.
  - 1. Set paneling plumb, rigid and level
    - a. Ensure all penetrations and obstructions are accounted for in the layout
  - 2. Install panels using adhesives and fasteners
    - a. Ensure 1/8" gap around the perimeter and penetrations to allow for expansion/contraction.
  - 3. If applicable, install moldings and frames at desired locations
  - 4. Comply with manufcaturer installation instructions.

## 3.04 CLEANING AND MAINTENANCE

A. Dust free using the soft end of the vacuum. For oiled products, natural oil can be reapplied to enhance the color of the wood.

# SECTION 079200 JOINT SEALANTS

## PART 1 GENERAL

### 1.01 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specifications Sections, apply to this Section.

#### 1.02 SUMMARY

- A. This Section includes jopint sealers for the following locations:
  - 1. Sealant A:
    - For interior joints in vertical surfaces and horizontal non-traffic surfaces as indicated below use one of the specified acrylic emulsion sealants, except as otherwise specified.
    - b. Perimeter interior joints of exterior openings.
    - c. Vertical control joints on exposed surfaces of interior unit masonry walls and partitions.
    - d. Perimeter joints between interior wall surfaces and frames of interior doors, windows, and borrowed lights.
  - 2. Sealant B:
    - a. Toilet Rooms: For perimeter joints of toilet fixtures, urinals, and lavatories; use one of the specified mildew-resistant silicone sealants.
  - 3. Sealant C:
    - a. Sealing concealed perimeter joints of gypsum drywall partitions to reduce sound transmission characteristics.

### 1.03 INFORMATION SUBMITTALS

- A. Qualification Data: For qualified testing agency.
- B. Product Test Reports: For each kind of joint sealant, for tests performed by a qualified testing agency.
- C. Preconstruction Laboratory Test Schedule: Include the following information for each joint sealant and substrate material to be tested. Joint-sealant location and designation.Manufacturer and product name. Type of substrate material. Proposed test. Number of samples required. Preconstruction Laboratort Test Reports: From sealant manufacturer, indicating the following: Materials forming joint substrates and joint-sealant backings have been tested for compatibility and adhesion with joint sealants. Interpretation of test results and written recommendations for primers and substrate preparation are needed for adhesion. Preconstruction Field-Adhesions-Test Reports: Indicate which sealants and joint preparation methods resulted in optimum adhesion to joint substrates based on testing specified in "Pre-construction Testing" Article. Field-Adhesion-Test Reports: For each sealant application tested. Sample Warratities: For special warranties.
  - 1. Joint-sealant location and designation.
  - 2. Manufacturer and product name.
  - 3. Type of substrate material.
  - 4. Proposed test.
  - 5. Number of samples required.
- D. Preconstruction Laboratory Test Reports: From sealant manufacturer, indicating the following:
  - 1. Materials forming joint substrates and joint-sealant backings have been tested for compatibility and adhesion with joint sealants.
  - 2. Interpretation of test results and written recommendations for primers and substrate preparation are needed for adhesion.
- E. Preconstruction Field-Adhesions-Test Reports: Indicate which sealants and joint preparation methods resulted in optimum adhesion to joint substrates based on testing specified in "Pre-construction Testing" Article.
- F. Field-Adhesion-Test Reports: For each sealant application tested.

G. Sample Warratities: For special warranties.

## 1.04 QUALITY ASSURANCE

### 1.05 PRECONSTR5UCTION TESTING

- A. Preconstruction Laboratory Testing: Arrange for sealant manufacturer(s) to test each combination of sealant, substrate, backing, and accessories.
  - 1. Adhesion Testing: In accordance with ASTM C794.
  - 2. Compatibility Testing: In accordance with ASTM C1087.
  - 3. Stain Testing: In accordance with ASTM C1248; required only for stone substrates.
  - 4. Allow sufficient time for testing to avoid delaying the work.
  - 5. Deliver sufficient samples to manufacturer for testing.
  - 6. Report manufacturer's recommended corrective measures, if any, including primers or techniques not indicated in product data submittals.
  - 7. Testing is not required if sealant manufacturer provides data showing previous testing, not older than 24 months, that shows satisfactory adhesion, lack of staining, and compatibility.
- B. Preconstruction Field-Adhesion Testing: Before installing sealants, field test their adhesion to Project joint substrates as follows:
  - 1. Locate test joints where indicated on Project or, if not indicated, as directed by Architect.
  - 2. Conduct field tests for each kind of sealant and joint substrate.
  - 3. Notify Architect seven days in advance of dates and times when joint will be erected.
  - 4. Arrange for tests to take place with joint-sealant manufacturer's technical representative present.
    - a. Test Method: Test joint sealants according to Method A, Field-Applied Sealant Joint Hand Pull Tab, in Appendix X1.1 in ASTM C 1193 or Method A, Tail Procedure, in ASTM C 1521.
      - 1) For joints with dissimilar substrates, verify adhesion to each substrate separately; extend cut along one side, verifying adhesion to opposite side. Repeat procedure for opposite side.
  - 5. Report whether sealant failed to adhere to joint substrates or tore cohesively. Include data on pull distance used to test each kind of product and joint substrate. For sealants that fail adhesively, retest until satisfactory adhesion is obtained.
  - 6. Evaluation of Preconstruction Field-Adhesion-Test Results: Sealants not evidencing adhesive failure from testing, in absence of other indications of noncompliance with requirements, will be considered satisfactory. Do not use sealants that fail to adhere to joint substrates during testing.

### 1.06 FIELD CONDITIONS

- A. Do not proceed with installation of joint sealants under the following conditions:
  - 1. When ambient and substrate temperature conditions are outside limits permitted by joint-sealant manufacturer or are below 40 deg F.
  - 2. When joint substrates are wet.
  - 3. Where joint widths are less than those allowed by joint-sealant manufacturer for applications indicated.
  - 4. Where contaminants capable of interfering with adhesion have not yet been removed from joint substrates.

### 1.07 WARRANTY

- A. See Section 017800 Closeout Submittals for additional warranty requirements.
- B. Special Installer's Warranty: Installer agrees to repair or replace joint sealants that do not comply with performance and other requirements specified in this Section within specified warranty period.
  - 1. Warranty Period: Five years from date of Substantial Completion.
- C. Special warranties specified in this article exclude deterioration or failure of joint sealants from the following:
  - 1. Movement of the structure caused by stresses on the sealant exceeding sealant manufacturer's written specifications for sealant elongation and compression.

- 2. Disintegration of joint substrates from causes exceeding design specifications.
- 3. Mechanical damage caused by individuals, tools, or other outside agents.
- 4. Mechanical damage caused bt individuals, tools, or other outside agent
- 5. Changes in sealant appearance caused by accumulation of dirt or atmospheric contaminants.

## **PART 2 PRODUCTS**

# 2.01 MANUFACTURERS

- A. Nonsag Sealants:
  - 1. Bostik Findley; Chem-Caulk 600. www.bostik-us.com/#sle.
  - 2. Pecora Corporation; AC-20+. www.pecora.com/#sle.
  - 3. Tremco Commercial Sealants & Waterproofing; Tremflex 834. www.tremcosealants.com/#sle.
  - 4. Schnee-Morehead, Inc.; Sm 8200
  - 5. Sonneborn, Division of ChemRex Inc.; Sonolac

### 2.02 JOINT SEALANTS - GENERAL

A. Sealants and Primers: Provide products having lower volatile organic compound (VOC) content than indicated in SCAOMD 1168.

### 2.03 JOINT SEALANTS

- A. Sealant A
  - 1. One-Part Mildew-Resistant Silicone Sealant: ASTM C920, Type: S; Grade NS, Class 25; Use NT; single component, mildew resistant; not expected to withstand continuous water immersion or traffic; formulated with fungicide; intended for sealing interior joints with nonporous substrates and subject to in-service exposure to conditions of high humidity and temperature extremes.
  - 2. Acceptable Products: Provide one of the following:
  - 3. Color: White.
  - 4. Products:
    - a. Dow Corning Corporation; 799
    - b. GE Silicones; UltraGlaze SSG4000
    - c. GE Silicones; UltreGlaze SSG4000AC
    - d. Polymeric Systems Inc.; PSI-631.
    - e. Schnee-Morehead, Inc.; SM5731 Poly-Graze Plus.
    - f. Tremco; Tremsil 600
    - g. Tremco; Tremsil 200

### B. Sealant B

- Acrylic Emulsion Sealant: Manufacturer's standard, one part, nonsag, mildew-resistant, acrylicemulsion sealant complying with ASTM C834, formulated to be paintable and recommended for exposed applications on interior and on protected exterior locations involving joint movement of not more than plus or minus 5 percent.
- 2. Acceptable Product: Provide one of the following:
  - a. Bostik Findley; Chem-Caulk 600.
  - b. Percora Corporation; AC-20+.
  - c. Schnee-Morehead, Inc.; SM8200.
  - d. Sonneborn, Division of ChemRex Inc.; Sonolac
  - e. Tremco; Tremflex 834.

#### C. Sealant C

Acoustical Sealant: Manufacturer's standard nonsag, paintable, nonstaining latex sealant complying
with ASTM C834; for use as acoustical sealant and in firestopping systems for expansion joints
and through penetrations. Product effectively reduces airborne sound transmission through
perimeter joints and openings in building construction as demonstrated by testing representative
assemblies according to ASTME 90.

- a. Product has flame spread and smoke developed ratings of less than 25 per ASTM 84 for fire rated wall application.
- 2. Available Products: Subject to compliance with requirements acoustical joint sealants that may be incorporated in the Work include, but not limited to, the following:
  - a. Acoustical Sealant:
    - 1) "SHEETROCK Acoustical Sealant," United States Gypsum Co.
    - 2) "AC-20 FTR Acoustical and Insulation Sealant," Percora Corp.
    - 3) "SpecSeal Smoke 'N' Sound Sealant," Specified Technologies, Inc.
  - b. Acoustical Sealant for Concealed Joints:
    - 1) "BA-98," Percora Corp.
    - 2) "Tremco Acoustical Sealant," Tremco, Inc.
    - 3) Sealant Sound Control," Grabber Construction Products, Inc.
  - c. Fire Rated System: Complies with UL 263 and ASTM E119 with UL fire resistance classifications.

#### 2.04 MISCELLANEOUS MATERIALS

- A. Primer: Material recommended by joint-sealant manufacturer where required for adhesion of sealant to joint substrates indicated, as determined from preconstruction joint-sealant-substrate tests and field tests.
- B. Cleaners for Nonporous Surfaces: Chemical cleaner acceptable to manufacturers of sealants and sealants backing materials, free of oily residues or other substances capable of staining or harming joint substrates and adjacent nonporous surfaces in any way, and formulated to promote optimum adhesion of sealants to joint substrates.
- C. Masking Tape: Self-adhesive, nonabsorbent, nonstaining, removable without adhesive residue, and compatible with surfaces adjacent to joints and sealants.

### PART 3 EXECUTION

### 3.01 EXAMINATION

- A. Verify that joints are ready to receive work, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.
- C. Verify that backing materials are compatible with sealants.

### 3.02 PREPARATION

- A. Surface Cleaning of joints: Clean out joints immediately before installing joint sealants to comply with joint-sealant manufacturer's written instructions and the following requirements:
  - 1. Remove loose materials and foreign matter that could impair adhesion of sealant.
  - 2. Clean joints, and prime as necessary, in accordance with manufacturer's instructions.
  - 3. Perform preparation in accordance with manufacturer's instructions and ASTM C1193.
  - 4. Mask elements and surfaces adjacent to joints from damage and disfigurement due to sealant work; be aware that sealant drips and smears may not be completely removable.
  - 5. Clean porous joint substrate surfaces by brushing, grinding, mechanical abrading, or a combination of these methods to produce a clean, sound substrate capable of developing optimum bond with joint sealants. Remove loose particles remaining after cleaning operations above by vacuuming or blowing out joints with oil-free compressed air. Porous joint substrates include the following:
    - a. Concrete.
    - b. Masonry.
    - c. Unglazed surfaces of ceramic tile.
    - d. Exterior insulation and finish systems.
  - 6. Remove laitance and form-release agents from concrete.
  - 7. Clean nonporous joint substrate surfaces with chemical cleaners or other means that do not stain, harm substrates, or leave residues capable of interfering with adhesion of joint sealants. Nonporous joint substrates include the following:

### 3.03 INSTALLATION

- A. Install this work in accordance with sealant manufacturer's requirements for preparation of surfaces and material installation instructions, unless more stringent requirements apply.
- B. Provide joint sealant installations complying with ASTM C1193.
- C. Install sealant backings of kind indicated to support sealants during application and at position required to produce cross-sectional shapes and depths of installed sealants relative to joint widths that allow optimum sealant movement capability.
  - 1. Do not leave gaps between ends of sealant backings.
  - 2. Do not stretch, twist, puncture, or tear sealant backings.
  - 3. Remove absorbent sealant backings that have become wet before sealant application, and replace them with dry materials.
- D. Install bond breaker backing tape where backer rod cannot be used.
- E. Install sealants using proven techniques that comply with the following and at the same time backings are installed:
  - 1. Place sealants so they directly contact and fully wet joint substrates.
  - 2. Completely fill recesses in each joint configuration.
  - 3. Produce uniform, cross-sectional shapes and depths relative to joint widths that allow optimum sealant movement capability.
  - 4. Install sealant free of air pockets, foreign embedded matter, ridges, and sags, and without getting sealant on adjacent surfaces.
  - 5. Do not install sealant when ambient temperature is outside manufacturer's recommended temperature range, or will be outside that range during the entire curing period, unless manufacturer's approval is obtained and instructions are followed.
  - Nonsag Sealants: Tool surface concave, unless otherwise indicated; remove masking tape immediately after tooling sealant surface.
  - Provide concave joint profile at locations indicated on Drawings according to Figure 8B in ASTM C 1193.
  - 8. Provide recessed joint configuration of recess depth and at locations indicated on Drawings according to Figure 8C in ASTM C 1193.

### 3.04 FIELD OUALITY CONTROL

- A. Field-Adhesion Testing: Field test joint-sealant adhesion to joint substrates as follows:
  - 1. Extend of Testing: Test completed, and cured sealant joint as follows:
    - a. Perform field quality control inspection/testing as specified in PART 1 under QUALITY ASSURANCE article.
    - b. Perform 10 tests for the first 1000 linear feet of joint length of each kind of sealant and joint substrate
    - c. Perform one test for each 1,000 linear feet of joint length thereafter or one test per each floor per elevation.
  - 2. Test Method: Test joint sealants according to Method A, Field-Applied Sealant Joint Hand Pull Tab, in Appendix X1 in ASTM C 1193 or Method A, Tail Procedure, in ASTM C 1521.
    - a. For joints with dissimilar substrates, verify adhesion to each substrate seperately; extend cut along one side, verifying adhesion to opposite side. Repeat precedure for opposite side.
  - 3. Inspect tested joints and report on the following:
    - a. Whether sealants filled with joint cavities and are free of voids.
    - b. Whether sealant dimensions and configurations comply with specified requirements.
    - c. Whether sealants in joints connected to pulled-out portion failed to adhere to joint substrates or tore cohesively. Include data on pull distance used to test each kind of product and joint substrate. Compare these results to determine if adhesion complies with sealant manufacturer's field-adhesion hand-pull test criteria.

- 4. Record test results in a field-adhesion-test log. Include dates when sealants were installed, names of persons who installed sealants, test dates, test locations, whether joints were primed, adhesion results and percent elongations, sealants material, sealant configuration, and sealant dimensions.
- 5. Repair sealants pulled from test area by applying new sealants following same procedures used originally to seal joints. Ensure that original sealant surfaces are clean and that new sealant contacts original sealant.
- B. Evaluation of Field-Adesion-Test Results: Sealants not evidencing adhesive failure from testing or noncompliance with other indicated requirements will be considered satisfactory. Remove sealants that fail to adhere to joint substrates during testing or to comply with indicated requirements. Retest failed applications until test results prove sealants comply with indicated requirements.

# 3.05 CLEANING

A. Clean off excess sealant or sealant smears adjacent to joints as the Work progresses by methods and with cleaning materials approved in writing by manufacturers of joint sealants and of products in which joint occur.

# 3.06 PROTECTION

- A. Protect joint sealants during and after curing period from contact with contaminating substances and from damage resulting from construction operations or other causes so sealants are without deterioration or damage at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out, remove, and repair damaged or deteriorated joint sealants immediately so installations with repaired areas are indistinguishable from original work.
  - 1. Remove and replace failed portions of sealants using same materials and procedures as indicated for original installation.
  - 2. Repair destructive test location damage immediately after evaluation and recording of results.

# **END OF SECTION**

# SECTION 081113 HOLLOW METAL DOORS AND FRAMES

# PART 1 GENERAL

# 1.01 SECTION INCLUDES

- A. Non-fire-rated hollow metal doors and frames.
- B. Hollow metal frames for wood doors.
- C. Fire-rated hollow metal frames.

## 1.02 DEFINITIONS

A. Minimum Thickness: Minimum thickness of base metal without coatings according to NAAMM-HMMA 803 or SDI A250.8.

### 1.03 COORDINATION

- A. Coordinate anchorage installation for hollow-metal frames. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors. Deliver such items to Project site in time for installation.
- B. Coordinate requirements for installation of door hardware, electrified door hardware, and access control and security systems.

# 1.04 RELATED REQUIREMENTS

- A. Section 087100 Door Hardware.
- B. Section 088000 Glazing: Glass for doors.

### 1.05 REFERENCE STANDARDS

- A. ADA Standards 2010 ADA Standards for Accessible Design; 2010.
- B. ANSI/SDI A250.3 Test Procedure and Acceptance Criteria for Factory Applied Finish Coatings for Steel Doors and Frames; 2019.
- C. ANSI/SDI A250.6 Recommended Practice for Hardware Reinforcing on Standard Steel Doors and Frames; 2020.
- D. ANSI/SDI A250.8 Specifications for Standard Steel Doors and Frames (SDI-100); 2023.
- E. ANSI/SDI A250.10 Test Procedure and Acceptance Criteria for Prime Painted Steel Surfaces for Steel Doors and Frames; 2020.
- F. ASTM A653/A653M Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process; 2023.
- G. ASTM A1008/A1008M Standard Specification for Steel, Sheet, Cold-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, Required Hardness, Solution Hardened, and Bake Hardenable; 2023, with Editorial Revision.
- H. ASTM A1011/A1011M Standard Specification for Steel, Sheet and Strip, Hot-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, and Ultra-High Strength; 2023.
- I. ICC A117.1 Accessible and Usable Buildings and Facilities; 2017.
- J. NAAMM HMMA 840 Guide Specifications For Receipt, Storage and Installation of Hollow Metal Doors and Frames; 2017.
- K. NAAMM HMMA 861 Guide Specifications for Commercial Hollow Metal Doors and Frames; 2014.
- L. NFPA 80 Standard for Fire Doors and Other Opening Protectives; 2022.
- M. SDI 117 Manufacturing Tolerances for Standard Steel Doors and Frames; 2023.

### 1.06 SUBMITTALS

- A. See Section 013300 Submittals, for submittal procedures.
- B. Product Data: For each type of product.
  - 1. Include construction details, material descriptions, fire-resistance ratings, and finishes.
- C. Shop Drawings: Include the following:
  - 1. Elevation of each frame type.
  - 2. Frame details for each frame type, including dimensioned profiles and metal thicknesses.
  - 3. Locations of reinforcement and preparations for hardware.
  - 4. Details of each different wall opening condition.
  - 5. Details of electrical raceway and preparation for electrified hardware, access control systems, and security systems.
  - 6. Details of anchorages, joints, field splices, and connections.
  - 7. Details of accessories.
  - 8. Details of moldings, removable stops, and glazing.
- D. Samples for Initial Selection: For factory-finished doors.
- E. Samples for Verification:
  - 1. Finishes: For each type of exposed finish required, prepared on Samples of not less than 3 by 5 inches.
- F. Product Schedule: For hollow-metal frames, prepared by or under the supervision of supplier, using same reference numbers for details and openings as those on Drawings. Coordinate with final door hadware schedule.
- G. Product Test Reports: For each type of fire-rated hollow-metal frame assembly and fire-rated borrowed-lite assembly for tests performed by a qualified testing asgency indicating compliance with preformance requirements.

# 1.07 QUALITY ASSURANCE

- A. Source Limitations: Obtain flush wood doors and hollow metal frame from single manufacturer.
- B. Maintain at project site copies of reference standards relating to installation of products specified.

# 1.08 DELIVERY, STORAGE, AND HANDLING

- A. Deliver hollow-metal frames palletized, packages, or crated to provide protection during transit and Project-site storage. Do not use nonvented plastic.
  - 1. Provide additional protection to prevent damage to factory-finished units.
- B. Store hollow-metal frames vertically under cover at Project site with head up. Place on minimum 4-inch high wood blocking. Provide minimum 1/4-inch space between each stacked door to permit air circulation.
- C. Comply with NAAMM HMMA 840 or ANSI/SDI A250.8 (SDI-100) in accordance with specified requirements.
- D. Protect with resilient packaging; avoid humidity build-up under coverings; prevent corrosion and adverse effects on factory applied painted finish.

# **PART 2 PRODUCTS**

# 2.01 MANUFACTURERS

- A. Hollow Metal Frames:
  - 1. Ampco, Inc.
  - 2. Buell Door Company Inc.
  - 3. Ceco Door, an Assa Abloy Group company
  - 4. Curries, an Assa Abloy Group company
  - 5. Republic Doors, an Allegion brand

- 6. Steelcraft, an Allegion brand
- 7. Titan Metal Products, Inc

### 2.02 MATERIALS

- A. Frame Anchors: ASTM A 591/A 591M, Commercial Steel (CS), 40Z (12G) coating designation; mill phosphatized.
- B. Inserts, Bolts, and Fasteners: Hot-dip galvanzied according to ASTM A 153/A 153M.
- C. Power-Actuated Fasteners in Concrete: Fasteners system of type suitable for application indicated, fabricated from corrosion-resistant materials, with clips or other accessory devices for attaching hollow metal frames of type indicated.

# 2.03 PERFORMANCE REQUIREMENTS

- A. Requirements for Hollow Metal Doors and Frames:
  - Steel Sheet: Comply with one or more of the following requirements; galvannealed steel
    complying with ASTM A653/A653M, cold-rolled steel complying with ASTM A1008/A1008M, or
    hot-rolled pickled and oiled (HRPO) steel complying with ASTM A1011/A1011M, commercial
    steel (CS) Type B, for each.
  - 2. Accessibility: Comply with ICC A117.1 and ADA Standards.
- B. Combined Requirements: If a particular door and frame unit is indicated to comply with more than one type of requirement, comply with the specified requirements for each type; for instance, an exterior door that is also indicated as being sound-rated must comply with the requirements specified for exterior doors and for sound-rated doors; where two requirements conflict, comply with the most stringent.

# 2.04 FRAME ANCHORS

- A. Jamb Anchors:
  - 1. Stud-Wall Type: Designed to engage stud, welded to back of frames; not less than 0.042 inch thick.
  - 2. Compression Type for Drywall Slip-on Frames: Adjustable compression anchors.

# 2.05 FABRICATION

- A. Fabricate hollow metal work to be rigid and free of defects, warp, or buckle. Accurately form metal to required sizes and profiles, with minimum radius for thickness of metal. Where practical, fit and assemble units in manufacturer's plant. To ensure proper assembly at Project site, clearly identify work that cannot be permanently factory assembled before shipment.
- B. Tolerances: Fabricate hollow metal work to tolerances indicated in [SDI 117] [ANSI/NAAMM-HHAA 861].
- C. Hollow Metal Frames: Where frames are fabricated insections due to shipping or handling limitations, provide alignment plates or angles at each joint, fabricated of same thickness metal as frames.
- Provide countersunk, flat- or oval-head exposed screws and bolts for exposed fasteners unles otherwise indicated.
- E. Grout Guards: Weld guards to frame at back of hardware martises in frames to begrouted.
- F. Jamb Anchors: Provide number and spacing of anchors as follows:
  - 1. Stud-Wall Type: Locate anchors not more than 18 inches from top and bottom of frame. Space anchors not more than 32 inches o.c. and as follows:
    - a. Three anchors per jamb up to 60 inches high.
    - b. Four anchors per jamb 60 to 90 inches high.
    - c. Five anchors per jamb 90 to 96 inches high.
    - d. Five anchors per jamb plus 1 additional anchor per jamb per each 24 inches or fraction therof above 96 inches high.
    - e. Two anchors per head for frames above 42 inches wide and moutned in metal-stud paritions.
  - 2. Compression Type: Not less than two anchors in each jamb.

- G. Fabricate concealed stiffners, edge channels, and hardware reinforcment from either cold-or hot-rolled steel sheet.
- H. Hardware Preparation: Factory prepare hollow metal work to recieve template mortised hardware; include cutouts, reinforcement, mortising, drilling, and tapping according to the Door Hardware Schedule and templates furnished as specified in Division 08 Section "Door Hardware."
  - 1. Locate hardware as indicated, or if not indicated according to [ANSI/SDI A250.8] [ANSI/NAAMM-HMMA 861].
  - 2. Reinforce doors and frames to receive nontemplated, mortised and surface-mounted door hardware.
  - 3. Comply with applicable requirements in ANSI/SDI A250.6 and ANSI/DHI Series specifications for preparation of hollow metal work for hardware.

# 2.06 HOLLOW METAL FRAMES

- A. General: Comply with ANSI/SDI A250.8 and with details indicated for type and profile.
- B. Interior Frames: Fabricated from cold-rolled steel sheet.
  - 1. Fabricate frames with mitered or coped corners.
  - 2. Fabricate frames as knocked down unless otherwise indicated.
- C. Hardware Preparations, Selections and Locations: Comply with NAAMM HMMA 830 and NAAMM HMMA 831 or BHMA A156.115 and ANSI/SDI A250.8 (SDI-100) in accordance with specified requirements.
- D. Comply with standards and/or custom guidelines as indicated for corresponding door in accordance with applicable door frame requirements.
- E. Frame Finish: Factory primed and field finished.
- F. Interior Door Frames, Non-Fire Rated: Full profile/continuously welded type.
- G. Door Frames, Fire-Rated: Full profile/continuously welded type.
  - 1. Fire Rating: Same as door, labeled.
- H. Mullions for Pairs of Doors: Fixed, except where removable is indicated, with profile similar to jambs.
- I. FINISHES
  - 1. Primer: Rust-inhibiting, complying with ANSI/SDI A250.10, door manufacturer's standard.
  - 2. Factory Finish: Complying with ANSI/SDI A250.3, manufacturer's standard coating.
    - a. Color: As selected by Architect from manufacturer's standard range.

# 2.07 STEEL FINISHES

A. Prime Finish: Apply manufacturer's standard primer immediately after cleaning and pre-treating.

# **PART 3 EXECUTION**

# 3.01 EXAMINATION

- A. Verify existing conditions before starting work.
- B. Verify that opening sizes and tolerances are acceptable.
- C. Verify that finished walls are in plane to ensure proper door alignment.
- D. Examine doors and installed door frames before hanging doors.
  - 1. Verify that frames comply with indicated requrements for type, size, location, and swing characteristics and have been installed with level heads and plumb jambs.
  - 2. Reject doors with defects.
- E. Proceed with installation only after nonstisfactory conditions have been corrected.

# 3.02 INSTALLATION

A. Install doors and frames in accordance with manufacturer's instructions and related requirements of specified door and frame standards or custom guidelines indicated.

- B. Job-Fitted Doors: Align and fit doors in frames with uniform clearances and bevels as indicated below; do not trim stiles and rails in excess of limits set by manufacturer or permitted for fire-rated doors. Machine doors for hardware. Seal edges of doors, edges of cutouts, and mortises after fitting and machining.
  - 1. Clearances: Provide 1/8 inch at heads, jambs, and between pairs of doors. Provide 1/8 inch form bottom of door to top of decorative floor finish or covering unless otherwise indicated. Where threshold is shown or scheduled, provide 1/4 inch from bottom of door to top of threshold unless otherwise indicated.
    - a. Comply with NFPA 80 for fire-rated doors.
- C. Bevel non-fire-rated doors 1/8 inch in 2 inches (3-1/2 degrees) at lock and hinges edges.
- D. Bevel fire-rated doors 1/8 inch in 2 inches (3-1/2 degrees) at lock edge; trim stiles and rails only to extent to permitted by labeling agency.
- E. Factory-Fitted Doors: Align in frames for uniform clearnace at each edge.
- F. Factory-Finished Doors: Restore finish before installation if fitting or machining is reqquired at Project site.
- G. Install fire rated units in accordance with NFPA 80.
- H. Coordinate frame anchor placement with wall construction.
- I. Install door hardware as specified in Section 087100.
  - Comply with recommended practice for hardware placement of doors and frames in accordance with ANSI/SDI A250.6 or NAAMM HMMA 861.
- J. Touch up damaged factory finishes.

### 3.03 TOLERANCES

- A. Clearances: Provide 1/8 inch at heads, jambs, and between pairs of doors. Provide 1/8 inch form bottom of door to top of decorative floor finish or covering unless otherwise indicated. Where threshold is shown or scheduled, provide 1/4 inch from bottom of door to top of threshold unless otherwise indicated.
- B. Maximum Diagonal Distortion: 1/16 inch measured with straight edge, corner to corner.

# 3.04 ADJUSTING

- A. Rehang or replace doors that do not swing or operate freely.
- B. Replace doors that are damaged or that do not comply with requirements. Doors may be repaired or refinished if work comples with requirements and shows no evidence of repair or refinishing.
- C. Adjust for smooth and balanced door movement.
- D. Adjust sound control doors so that seals are fully engaged when door is closed.
- E. Test sound control doors for force to close, latch, and unlatch; adjust as necessary in compliance with requirements.

# **END OF SECTION**

# SECTION 081416 FLUSH WOOD DOORS

# **PART 1 GENERAL**

# 1.01 SECTION INCLUDES

A. Solid-core five-ply flush wood veneer-faced doors.

# 1.02 PREINSTALLATION MEETING

A. Preinstallation Conference: Conduct conference at Project site.

# 1.03 RELATED REQUIREMENTS

- A. Section 081113 Hollow Metal Doors and Frames.
- B. Section 087100 Door Hardware.
- C. Section 088000 Glazing.

### 1.04 REFERENCE STANDARDS

- A. NFPA 80 Standard for Fire Doors and Other Opening Protectives; 2022.
- B. NFPA 105 Standard for Smoke Door Assemblies and Other Opening Protectives; 2022.
- C. UL 10C Standard for Positive Pressure Fire Tests of Door Assemblies; Current Edition, Including All Revisions.

### 1.05 ACTION SUBMITTALS

- A. See Section 013300 Submittals, for submittal procedures.
- B. Product Data:
  - 1. Solid-core five-ply flush wood veneer-faced doors.
- C. Shop Drawings: Indicate location, size, and hand of each door; elevation of each type of door; construction details not covered in Product Data; and the following:
  - 1. Door schedule indicating door and frame location, type, size, fire protection rating, and swing.
  - 2. Door elevations, dimensions and locations of hardware.
  - 3. Dimensions and locations of blocking for hardware attachment.
  - 4. Dimensions and locations of mortises and holes for hardware.
  - 5. Clearances and undercuts.
  - 6. Requirements for veneer matching.
  - 7. Doors to be factory finished and application requirements.
  - 8. Apply AWI Quality Certification Program label to Shop Drawings.
- D. Samples: Submit two samples of door veneer, 8 by \_\_\_ inches in size illustrating wood grain, stain color, and sheen.
- E. Warranty, executed in Owner's name.

### 1.06 CLOSEOUT SUBMITTALS

- A. Quality Standard Compliance Certifications: AWI Quality Certification Program certificates.
- B. Record Documents: For fire-rated doors, list of door numbers and applicable room name and number to which door accesses.

### 1.07 QUALITY ASSURANCE

- A. Manufacturer's Certification: Licensed participant in AWI's Quality Certification Program.
- B. Egress Door Inspector Qualifications: Inspector for field-quality-control inspections of egress door assemblies complies with qualifications set forth in NFPA 101, Section 7.2.1.15.4 and following:
  - 1. DHI's Fire and Egress Door Assembly Inspector (FDAI) certification.

# 1.08 DELIVERY, STORAGE, AND HANDLING

- A. Comply with requirements of referenced standard and manufacturer's written instructions.
- B. Package doors individually in plastic bags or cardboard cartons.
- C. Mark each door on top and bottom rail with opening number used on Shop Drawings.
- D. Package, deliver and store doors in accordance with specified quality standard.
- E. Accept doors on site in manufacturer's packaging, and inspect for damage.
- F. Protect doors with resilient packaging sealed with heat shrunk plastic; do not store in damp or wet areas or areas where sunlight might bleach veneer; seal top and bottom edges with tinted sealer if stored more than one week, and break seal on site to permit ventilation.

# 1.09 FIELD CONDITIONS

- A. Environmental Limitations:
  - 1. Do not deliver or install doors until spaces are enclosed and weathertight, wet-work in spaces is complete and dry, and HVAC system is operating and maintaining temperature and relative humdity at levels designed for building occupants for the remainder of construction period.
  - 2. Do not install doors until building is enclosed and weathertight, wet-work is complete, and HVAC system is operating and maintaining temperature between 60 and 90 deg F and relative humidity between 43 and 70 percent during remainder of construction period.

### 1.10 WARRANTY

- A. Special Warranty: Manufactuer agrees to repair or replace doors that fail in materials or workmanship within specified warranty period.
  - 1. Failures include, but not limited to, the following:
    - a. Delamination of veneer.
    - b. Warping (bow, cup, or twist) more than 1/4 inch in a 42-by-84-inch section.
    - c. Telegraphing of core construction in face veneers exceeding 0.01 inch in a 3-inch span.
  - 2. Warranty also includes installation and finishing that may be required due to repair or replacement of defective doors.
- B. Manufacturer Warranty: Provide manufacturer's warranty on interior doors for the life of the installation. Complete forms in Owner's name and register with manufacturer.
  - 1. Include coverage for delamination of veneer, warping beyond specified installation tolerances, defective materials, and telegraphing core construction.

# **PART 2 PRODUCTS**

# 2.01 PERFORMANCE REQUIREMENTS

- A. Fire-Rated Door and Frame Assemblies: Assemblies complying with NFPA 80 that are listed and labeled by a qualified testing agency acceptable to authorities having jurisdiction, for fire-protection ratings indicated on Drawings, based on testing at positive pressure in accordance with UL 10C or NFPA 252.
  - 1. Oversize Fire-Rated Door Assemblies: For units exceeding sizes of tested assemblies, provide certification by a qualified testing agency that doors comply with standard construction requirements for tested and labeled fire-rated door assembles except for size.
  - 2. Temperature-Rise Limit: At vertical exit enclosures and exit passageways, provide doors that have a maximum transmitted temperature end point of not more than 450 deg F above ambient after 30 minutes of standard fire-test exposure.
- B. Smoke- and Draft-Control Door Assemblies: Listed and labeled for smoke and draft control by a qualified testing agency acceptable to authorities having jurisdication, based on testing in accordance with UL 1784 and installed in compliance with NFPA 105.

# 2.02 FLUSH WOOD DOORS, GENERAL

A. Quality Standard: In addition to requirements specified, comply with ANSI/WDMA I.S. 1A.

- Provide labels and certificates from AWI certification program indicating that doors comply with requirements of grades specified.
  - a. Contractor registers the Work under this Section with the AWI Quality Certification Program at www.awiqcp.org or by calling 855-345-0991.
- 2. The Contract Documents contain requirements that are more stringent than the referenced quality standard. Comply with the Contract Documents in addition to those of the referenced quality standard.

# 2.03 MANUFACTURERS

- A. Wood Veneer Faced Doors: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  - 1. Graham Manufacturing Corporation
  - 2. Haley Brothers
  - 3. Krieger Specialty Products
  - 4. Masonite Architectural
  - 5. Oregon Door
  - 6. VT Industries, Inc

# 2.04 WOOD VENEER FACED DOORS

- A. Solid-Core Five-Ply Flush Wood Veneer-Faced Doors
  - 1. Interior Doors, Solid-Core Five-Ply Veneer Faced:
  - 2. Performance Grade: ANSI/WDMA I.S. 1A Extra Heavy Duty, Heavy Duty, Standard Duty.
  - 3. ANSI/WDMA I.S. 1A Quality Grade: Premium.
  - 4. Faces: Single-ply wood veneer not less than 1/50 inch thick.
    - a. Species: Red Oak.
    - b. Cut: Plain Sliced (flat sliced).
    - c. Match between Veneer Leaves: Book match.
    - d. Assembly of Veneer Leaves on Door Faces: Center-balance match.
    - e. Room Match:
      - Match door faces within each seperate room or area of building. Corridor-door faces do not need to match where they are seperated by 10 feet or more.
      - Provide doors faces of compatible color and grain within each seperate room or area of building.
  - 5. Exposed Vertical and Top Edges: Same species as faces Architectural Woodwork Standards edge Type A.
    - a. Fire-Rated Single Soors: Provide edge construction with intumescent seals concealed by outer stile. Comply with specified requirements for exposed vertical edges.
    - b. Mineral-Core Doors: At hinge stiles, provide laminated-edge construction with improved screw-holding capability and split resistance. Comply with specified requirements for exposed edges.
  - 6. Construction: Five plies, hot-pressed bonded (vertical and horizontal edging is bonded to core), with entire unit abrasive planed before veneering.

# 2.05 FABRICATION

- A. Factory fit doors to suit frame opening sizes indicated.
  - Comply with clearance requirements of referenced quality standard for fitting unless otherwise indicated.
  - 2. Comply with NFPA 80 requirements for fire-rated foors.
- B. Factory machine doors for hardware that is not surface applied.
  - 1. Locate hardware to comply with DHI-WDHS-3.
  - 2. Comply with final hardware schedules, door frame Shop Drawings, ANSI/BHMA-156.115-W, and hardware templates.

- 3. Coordinate with hardware mortises in metal frames, to verify dimensions and alignment before factory machining.
- 4. For doors scheduled to receive electrified locksets, provide factory-installed raceway and wiring to accommodate specified hardware.
- Metal Astragals: Factory machine astragals and formed-steel edges for hardware for pairs of firerated doors.

### 2.06 FACTORY FINISHING

- A. Comply with referenced quality standard for factory finishing.
  - 1. Complete fabrication, including fitting doors for openings and machining for hardware that is not surface applied, before finishing.
  - 2. Finish faces, all four edges, edges of cutouts, and mortises.
  - 3. Stains and fillers may be omitted on top and bottom edges, edges of cutouts, and mortises.
- B. Factory finish doors.

### **2.07 DOORS**

- A. Doors: See drawings for locations and additional requirements.
- B. Interior Doors: 1-3/4 inches thick unless otherwise indicated; flush construction.
  - 1. Provide solid core doors at each location.
  - 2. Fire Rated Doors: Tested to 90 minutes in accordance with UL 10C Positive Pressure; Underwriters Laboratories Inc (UL) or Intertek/Warnock Hersey (WHI) labeled without any visible seals when door is open.

### 2.08 DOOR CONSTRUCTION

- A. Fabricate doors in accordance with door quality standard specified.
- B. Glazed Openings: Non-removable stops on non-secure side; sizes and configurations as indicated on drawings.
- C. Factory machine doors for hardware other than surface-mounted hardware, in accordance with hardware requirements and dimensions.
- D. Factory fit doors for frame opening dimensions identified on shop drawings, with edge clearances in accordance with specified quality standard.
- E. Provide edge clearances in accordance with the quality standard specified.

# 2.09 FINISHES - WOOD VENEER DOORS

A. Factory finish doors in accordance with approved sample.

### 2.10 ACCESSORIES

- A. Hollow Metal Door Frames: See Section 081113.
- B. Door Window Frames: Door window frames with glazing securely fastened within door opening.
  - 1. Size: As indicated on drawings.
  - 2. Frame Material: 18 gauge, 0.0478 inch, galvanized steel.
  - 3. Metal Finish: Gray polyester powder coating.
  - 4. Glazing: 1/4 inch thick, wire glass, in compliance with requirements of authorities having jurisdiction.
- C. Glazing Stops: Wood with metal clips for rated doors, butted corners; prepared for countersink style tamper proof screws.
- D. Astragals and Edges for Double Doors: Pairs of doors astragals, and door edge sealing and protection
  - 1. UL listed products in compliance with requirements of authorities having jurisdiction.
  - 2. Material: Aluminum.
- E. Door Hardware: See Section 087100.

### PART 3 EXECUTION

### 3.01 EXAMINATION

- A. Examine doors and installed door frames, with Installer present, before hanging doors.
  - 1. Verify that installed frames comply with indicated requirements for type, size, location, and swing characteristics and have been installed with level heads and plumb jambs.
  - 2. Reject doors with defects.
- B. Proceed with installation only after unstatisfactory conditions have been corrected.
- C. Verify existing conditions before starting work.
- D. Verify that opening sizes and tolerances are acceptable.
- E. Do not install doors in frame openings that are not plumb or are out-of-tolerance for size or alignment.

#### 3.02 INSTALLATION

- A. Hardware: For installation, see Section 087100 "Door Hardware."
- Install doors in accordance with manufacturer's instructions and specified quality standard, and as indicated.
- C. Install frames, level, plumb, true, and straight.
  - 1. Shim as required with concealed shims. Install level and plumb to a tolerance of 1/8 inch in 96 inches.
  - 2. Anchor frames to anchors or blocking built in or directly attached to substrates.
    - a. Secure countersink, concealed fasteners and blind nailing.
    - b. Use fine finishing nails or finishing screws for exposed fastening, countersunk and filled flush with woodwork.
      - 1) For factory-finished items, use filler matching finish of items being installed.
  - 3. Install fire-rated doors in accordance with NFPA 80 requirements.
  - 4. Install smoke and draft control doors in accordance with NFPA 105 requirements.

### D. Job-Fitted Doors:

- 1. Align and fit doors in frames with uniform clearances and bevels as indicated below.
  - a. Do not trim stiles and rails inexcess of limits set by manufacturer or permitted for fire-rated doors.
- 2. Machine doors for hardware.
- 3. Seal edges of doors, edges of cutouts, and mortises after fitting and
- 4. Clearances:
  - a. Provide 1/8 inch at heads, jambs, and between pairs of doors.
  - b. Provide 1/8 inch from bottom of door to top of decorative floor finish or covering unless otherwise indicated on Drawings.
  - c. Where threshold is shown or scheduled, provide 1/4 inch from bottom of door to top of threshold unless otherwise indicated.
  - d. Comply with NFPA 80 for fire-rated doors.
- 5. Bevel non-fire-rated doors 1/8 inch in 2 inches at lock and hinge edges.
- 6. Bevel fire-rated doors 1/8 inch in 2 inches at lock edge; trim stiles and rails only to extent permitted by labeling agency.
- E. Factory-Fitted Doors: Align in frame for uniform clearance at each edge.
- F. Factory-Finished Doors: Restore finish before installation if fitting or machining is required at project site.
- G. Use machine tools to cut or drill for hardware.
- H. Coordinate installation of doors with installation of frames and hardware.
- I. Coordinate installation of glazing.

# 3.03 FIELD QUALITY CONTROL

- A. Inspection Agency: Owner will engage a qualified inspector to perform inspections and to furnish reports to Architect.
- B. Inspections:
  - 1. Provide inspections of installed Work through AWI's Quality Certification Program, certifying that wood doors and frames, including installation, comply with requirements of AWI/AWMCA/WI's "Architectural Woodwork Standards" for the specified grade.
  - 2. Fire-Rated Door Inspections: Inspect each fire-rated door inaccordance with NFPA 80, Section 5.2.
  - 3. Egress Door Inspections: Inspect each door equipped with panic hardware, each door equipped with fire exit hardware, each door located in an exit enclosure, each electrically controlled egress door, and each door equipped with special locking arrangments in accordance with NFPA 101, Section 7.2.1.15.
- C. Repair or remove and replace installations where inspections indicate that they do not comply with specified requirements.
- D. Reinspect repaired or replaced installations to determine if replaced or repaired door assembly installations comply with specified requirements.
- E. Prepare and submit seperate inspection report for each fire-rated door assembly indicating compliance with each item listed in NFPA 80, and NFPA 101.

### 3.04 ADJUSTING

- A. Operation: Rehang or replace doors that do not swing or operate freely.
- B. Finished Doors: Replace doors that are damaged or that do not comply with requirements. Doors may be repaired or refinished if Work complies with requirements and shows no evidence of repair or refinishing.
- C. Adjust doors for smooth and balanced door movement.
- D. Adjust closers for full closure.

**END OF SECTION** 

# SECTION 084313 ALUMINUM-FRAMED STOREFRONTS

# PART 1 GENERAL

# 1.01 SECTION INCLUDES

- A. Aluminum doors.
- B. Weatherstripping.
- C. Door hardware.

## 1.02 RELATED REQUIREMENTS

A. Section 088000 - Glazing: Glass and glazing accessories.

# 1.03 REFERENCE STANDARDS

- A. AAMA CW-10 Care and Handling of Architectural Aluminum from Shop to Site; 2015.
- B. AAMA 501.2 Quality Assurance and Diagnostic Water Leakage Field Check of Installed Storefronts, Curtain Walls, and Sloped Glazing Systems; 2015.
- C. AAMA 503 Voluntary Specification for Field Testing of Newly Installed Storefronts, Curtain Walls and Sloped Glazing Systems; 2014.
- D. AAMA 609 & 610 Cleaning and Maintenance Guide for Architecturally Finished Aluminum (Combined Document); 2015.
- E. AAMA 611 Voluntary Specification for Anodized Architectural Aluminum; 2020.
- F. AAMA 1503 Voluntary Test Method for Thermal Transmittance and Condensation Resistance of Windows, Doors and Glazed Wall Sections; 2009.
- G. ASTM B221 Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes; 2021.
- H. ASTM B221M Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes (Metric); 2021.
- I. ASTM E283/E283M Standard Test Method for Determining Rate of Air Leakage Through Exterior Windows, Skylights, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen; 2019.
- J. ASTM E330/E330M Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference; 2014 (Reapproved 2021).
- K. ASTM E331 Standard Test Method for Water Penetration of Exterior Windows, Skylights, Doors, and Curtain Walls by Uniform Static Air Pressure Difference; 2000 (Reapproved 2023).
- L. ASTM E783 Standard Test Method for Field Measurement of Air Leakage Through Installed Exterior Windows and Doors; 2002 (Reapproved 2018).
- M. ASTM E1105 Standard Test Method for Field Determination of Water Penetration of Installed Exterior Windows, Skylights, Doors, and Curtain Walls, by Uniform or Cyclic Static Air Pressure Difference; 2015 (Reapproved 2023).

## 1.04 SUBMITTALS

- A. See Section 013300 Submittals, for submittal procedures.
- B. Product Data: Provide component dimensions, describe components within assembly, anchorage and fasteners, glass and infill, door hardware, and internal drainage details.
- C. Shop Drawings: Indicate system dimensions, framed opening requirements and tolerances, affected related work, expansion and contraction joint location and details, and field welding required.
- D. Manufacturer's Certificate: Certify that the products supplied meet or exceed the specified requirements.

- E. Hardware Schedule: Complete itemization of each item of hardware to be provided for each door, cross-referenced to door identification numbers in Contract Documents.
- F. Field Quality Control Submittals: Report of field testing for water penetration and air leakage.
- G. Manufacturer's qualification statement.
- H. Installer's qualification statement.
- I. Specimen warranty.

### 1.05 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in performing work of type specified and with at least three years of documented experience.
  - 1. Provide certified glass products through ANSI accredited certifications that include plant audits and independent laboratory performance testing.
- B. Installer Qualifications: Company specializing in performing work of type specified and with at least three years of documented experience.

# 1.06 DELIVERY, STORAGE, AND HANDLING

- A. Handle products of this section in accordance with AAMA CW-10.
- B. Protect finished aluminum surfaces with wrapping. Do not use adhesive papers or sprayed coatings that bond to aluminum when exposed to sunlight or weather.

#### 1.07 FIELD CONDITIONS

A. Do not install sealants when ambient temperature is less than 40 degrees F. Maintain this minimum temperature during and 48 hours after installation.

### 1.08 WARRANTY

- A. Provide five year manufacturer warranty against failure of glass seal on insulating glass units, including interpane dusting or misting. Include provision for replacement of failed units.
- B. Provide five year manufacturer warranty against excessive degradation of exterior finish. Include provision for replacement of units with excessive fading, chalking, or flaking.

# **PART 2 PRODUCTS**

# 2.01 MANUFACTURERS

- A. Aluminum-Framed Storefronts:
  - 1. Arcadia, Inc
  - 2. Kawneer North America
  - 3. Pittco Architectural Metals Inc;
  - 4. Trulite Glass & Aluminum Solutions, LLC

### 2.02 SWINGING DOORS

- A. Medium Stile, Insulating Glazing, Not Thermally-Broken.
- B. Wide Stile, Insulating Glazing, Thermally-Broken.

# 2.03 ALUMINUM-FRAMED STOREFRONT DOOR COMPONENTS

- A. Glazing: See Section 088000.
- B. Swing Doors: Glazed aluminum.
  - 1. Top Rail: 4 inches wide.
  - 2. Vertical Stiles: 4-1/2 inches wide.
  - 3. Bottom Rail: 4 inches wide.
  - 4. Glazing Stops: Square.

### 2.04 MATERIALS

- A. Extruded Aluminum: ASTM B221 (ASTM B221M).
- B. Fasteners: Stainless steel.
- C. Sealant for Setting Thresholds: Non-curing butyl type.
- D. Glazing Gaskets: Type to suit application to achieve weather, moisture, and air infiltration requirements.

#### 2.05 FINISHES

- A. Class II Natural Anodized Finish: AAMA 611 AA-M12C22A31 Clear anodic coating not less than 0.4 mils thick.
- B. Color: Dark Bronze to match existing frame.

# 2.06 HARDWARE

- A. For each door, include weatherstripping, sill sweep strip, and threshold.
- B. Weatherstripping: Wool pile, continuous and replaceable; provide on all doors.
- C. Sill Sweep Strips: Resilient seal type, retracting, of neoprene; provide on all doors.
- D. Threshold: Extruded aluminum, one piece per door opening, ribbed surface; provide on all doors.
- E. Hinges: Butt type, swing clear; top and bottom. New to match existing frame.
- F. Push/Pull Set: Standard configuration push/pull handles.
  - 1. Provide vertical pulls on interior and exterior door as indicated.
  - 2. Provide horizontal push bar on interior door as indicated.
- G. Exit Devices: Panic type.
  - 1. Provide horizontal panic push bar on exterior door on egress side.
- H. Door Closers: Remove and Reinstall Existing
- I. Power Door Operators: Remove and Reinstall Existing
- J. Security Hardware: Remove and Reinstall Existing

## PART 3 EXECUTION

# 3.01 EXAMINATION

- A. Verify dimensions, tolerances, and method of attachment with other work.
- B. Verify that storefront wall openings and adjoining water-resistive and/or air barrier seal materials are ready to receive work of this section.

# 3.02 INSTALLATION

- A. Install wall system in accordance with manufacturer's instructions.
- B. Attach to structure to permit sufficient adjustment to accommodate construction tolerances and other irregularities.
- C. Provide alignment attachments and shims to permanently fasten system to building structure.
- D. Align assembly plumb and level, free of warp or twist. Maintain assembly dimensional tolerances, aligning with adjacent work.
- E. Provide thermal isolation where components penetrate or disrupt building insulation.
- F. Where fasteners penetrate sill flashings, make watertight by seating and sealing fastener heads to sill flashing.
- G. Install hardware using existing frame conditions. Field Verify.
- H. Install glass using glazing method required to achieve performance criteria; see Section 088000.
- I. Touch-up minor damage to factory applied finish; replace components that cannot be satisfactorily repaired.

# 3.03 TOLERANCES

- A. Maximum Variation from Plumb: 0.06 inch per 3 feet non-cumulative or 0.06 inch per 10 feet, whichever is less.
- 3. Maximum Misalignment of Two Adjoining Members Abutting in Plane: 1/32 inch.

# 3.04 FIELD QUALITY CONTROL

- A. Provide services of storefront manufacturer's field representative to observe for proper installation of system and submit report.
- B. Provide field testing of installed storefront system by independent laboratory in accordance with AAMA 503 during construction process and before installation of interior finishes.
  - 1. Perform a minimum of two tests in each designated area as indicated on drawings.
  - 2. Conduct tests in each area prior to 10 percent and 50 percent completion of this work.
  - 3. Field test for water penetration in accordance with ASTM E1105 with uniform static air pressure difference (Procedure A) not less than 4.18 psf.
    - a. Maximum allowable rate of water penetration in 15-minute test is 0.5 ounce that is not contained in an area with provisions to drain to exterior, or collected on surface of interior horizontal framing member.
  - 4. Field test for air leakage in accordance with ASTM E783 with uniform static air pressure difference of 1.57 psf.
    - a. Maximum allowable rate of air leakage is 0.09 cfm/sq ft.
- C. Repair or replace storefront components that have failed designated field testing, and retest to verify performance complies with specified requirements.

### 3.05 ADJUSTING

A. Adjust operating hardware for smooth operation.

# 3.06 CLEANING

- A. Remove protective material from pre-finished aluminum surfaces.
- Upon completion of installation, thoroughly clean aluminum surfaces in accordance with AAMA 609 & 610.

## 3.07 PROTECTION

A. Protect installed products from damage until Date of Substantial Completion.

# **END OF SECTION**

# SECTION 087100 DOOR HARDWARE

# PART 1 GENERAL

# 1.01 SECTION INCLUDES

- A. Hinges.
- B. Mortise Locks.
- C. Hardware for wood, aluminum, and hollow metal doors.
- D. Hardware for fire-rated doors.
- E. Electrically operated and controlled hardware.
- F. Thresholds.
- G. Weatherstripping and gasketing.

### 1.02 COORDINATION

- A. Installation Templates: Distribute for doors, frames, and other work specified to be factory prepared. Check Shop Drawings of other work to confirm that adequate provisions are made for locating and installing door hardware to comply with indicated requirements.
- Security: Coordinate installation of door hardware, keying, and access control with Owner's security consultant.
- C. Existing Openings: Where hardware components are scheduled for application to existing construction or where modifications to existing door hardware are required, field-verify existing conditions and coordinate installation of door hardware to suit opening conditions and to provide proper door operation.

### 1.03 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.
  - 1. Conference participants must include Installer's Architectural Hardware Consultant and Owner's security consultant.
- B. Keying Conference: Conduct conference at Project site.
  - 1. Conference participants must include Installer's Architectural Hardware Consultant and Owner's security consultant.
  - 2. Incorporate conference decisions into keying schedule after reviewing door hardware keying system, including, but not limited to, the following:
    - a. Flow of traffic and degree of security required.
    - b. Preliminary key system schematic diagram.
    - c. Requirements for key control system.
    - d. Requirements for access control.
    - e. Address for delivery of keys.

### 1.04 RELATED REQUIREMENTS

- A. Section 081113 Hollow Metal Doors and Frames.
- B. Section 081416 Flush Wood Doors.
- C. Section 084313 Aluminum-Framed Storefronts: Door hardware, except as noted in section.
- D. Section 087113 Power Door Operators.

### 1.05 REFERENCE STANDARDS

- A. ADA Standards 2010 ADA Standards for Accessible Design; 2010.
- B. BHMA A156.1 Standard for Butts and Hinges; 2021.
- C. BHMA A156.3 Exit Devices; 2020.
- D. BHMA A156.4 Door Closers and Pivots; 2024.

Door Hardware

- E. BHMA A156.5 Cylinders and Input Devices for Locks; 2020.
- F. BHMA A156.6 Standard for Architectural Door Trim; 2021.
- G. BHMA A156.7 Template Hinge Dimensions; 2016.
- H. BHMA A156.8 Door Controls Overhead Stops and Holders; 2021.
- I. BHMA A156.13 Mortise Locks & Latches Series 1000; 2022.
- J. BHMA A156.21 Thresholds; 2019.
- K. BHMA A156.22 Standard for Gasketing; 2021.
- L. BHMA A156.31 Electric Strikes and Frame Mounted Actuators; 2024.
- M. BHMA A156.36 Auxiliary Locks; 2020.
- N. DHI (LOCS) Recommended Locations for Architectural Hardware for Standard Steel Doors and Frames; 2004.
- O. DHI WDHS.3 Recommended Locations for Architectural Hardware for Flush Wood Doors; 1993; also in WDHS-1/WDHS-5 Series, 1996.
- P. ICC A117.1 Accessible and Usable Buildings and Facilities; 2017.
- Q. NFPA 70 National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- R. NFPA 80 Standard for Fire Doors and Other Opening Protectives; 2022.
- S. NFPA 101 Life Safety Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- T. NFPA 252 Standard Methods of Fire Tests of Door Assemblies; 2022.
- U. UL (DIR) Online Certifications Directory; Current Edition.
- V. UL 10C Standard for Positive Pressure Fire Tests of Door Assemblies; Current Edition, Including All Revisions.

# 1.06 ADMINISTRATIVE REQUIREMENTS

- A. Coordinate the manufacture, fabrication, and installation of products that door hardware is installed on.
- B. Sequence installation to ensure utility connections are achieved in an orderly and expeditious manner.
- C. Furnish templates for door and frame preparation to manufacturers and fabricators of products requiring internal reinforcement for door hardware.
- D. Keying Requirements Meeting:
  - 1. Schedule meeting at project site prior to Contractor occupancy.
  - 2. Attendance Required:
    - a. Contractor.
    - b. Owner.
    - c. Architect.
    - d. Hardware Installer.
    - e. Owner's Security Consultant.
  - 3. Agenda:
    - a. Establish keying requirements.
    - b. Verify locksets and locking hardware are functionally correct for project requirements.
    - c. Verify that keying and programming complies with project requirements.
    - d. Establish keying submittal schedule and update requirements.
  - 4. Incorporate "Keying Requirements Meeting" decisions into keying submittal upon review of door hardware keying system including, but not limited to, the following:
    - a. Access control requirements.
    - b. Key control system requirements.

- c. Flow of traffic and extent of security required.
- 5. Record minutes and distribute copies within two days after meeting to participants, with two copies to Architect, Owner, participants, and those affected by decisions made.
- 6. Deliver established keying requirements to manufacturers.

### 1.07 ACTION SUBMITTALS

- A. See Section 013300 Submittals, for submittal procedures.
- B. Product Data: Manufacturer's catalog literature for each type of hardware, marked to clearly show products to be furnished for this project, and includes construction details, material descriptions, finishes, and dimensions and profiles of individual components.
- C. Shop Drawings Door Hardware Schedule: Submit detailed listing that includes each item of hardware to be installed on each door. Use door numbering scheme as included in Contract Documents.
  - 1. Prepared by or under supervision of Architectural Hardware Consultant (AHC).
  - 2. Provide complete description for each door listed.
  - 3. Provide manufacturer name, product names, and catalog numbers; include functions, types, styles, sizes and finishes of each item.
- D. Shop Drawings Electrified Door Hardware: Submit diagrams for power, signal, and control wiring for electrified door hardware that include details of interface with building safety and security systems. Provide elevations and diagrams for each electrified door opening as follows:
  - 1. Prepared by or under supervision of Architectural Hardware Consultant (AHC) and Electrified Hardware Consultant (EHC).
  - 2. Elevations: Submit front and back elevations of each door opening showing electrified devices with connections installed and an operations narrative describing how opening operates from either side at any given time.
  - 3. Diagrams: Submit point-to-point wiring diagram that shows each device in door opening system with related colored wire connections to each device.

# E. Samples for Initial Selection:

- 1. Sample Size: Full-size units or minimum size of 2 by 4 inch for sheet samples, and minimum length of 4 inch for other products.
- 2. Submit one (1) sample of hinge, latchset, lockset, closer, and \_\_\_\_\_ illustrating style, color, and finish.
- 3. Return full-size samples to Contractor.
  - a. Units that are acceptable and remain undamaged through submittal, review, and field comparison process may, after final check of operation, be incorporated into the Work, within limitations of keying requirements.
- 4. Submit product description with samples.
  - a. Tag samples with full product descriptions to coordinate samples with Door Hardware Schedule.
- 5. Manufacturer's Installation Instructions: Indicate special procedures and perimeter conditions requiring special attention.
- 6. Maintenance Data: Include data on operating hardware, lubrication requirements, and inspection procedures related to preventative maintenance.
  - a. Submit manufacturer's parts lists and templates.
- 7. Keying Schedule:
  - a. Submit three (3) copies of Keying Schedule in compliance with requirements established during Keying Requirements Meeting unless otherwise indicated.
- 8. Manufacturer's qualification statement.
- 9. Installer's qualification statement.
- 10. Specimen warranty.
- 11. Project Record Documents: Record actual locations of concealed equipment, services, and conduit.
- 12. Maintenance Materials and Tools: Furnish the following for Owner's use in maintenance of project.

- a. Lock Cylinders: Ten for each master keyed group.
- b. Tools: One set of each special wrench or tool applicable for each different or special hardware component, whether supplied by hardware component manufacturer or not.

### 1.08 QUALITY ASSURANCE

- A. Standards for Fire-Rated Doors: Maintain one copy of each referenced standard on site, for use by Architect and Contractor.
- B. Manufacturer Qualifications: Company specializing in manufacturing products specified in this section with minimum three years of documented experience.
- C. Installer Qualifications: Supplier of products and an employer of workers trained and approved by product manufacturers and of an Architectural Hardware Consultant who is available during the course of the Work to consult Contractor, Architect, and Owner about door hardware and keying.
  - 1. Warehousing Facilities: In Project's vicinity.
  - 2. Scheduling Responsibility: Preparation of door hardware and keying schedule.
- D. Architectural Hardware Consultant Qualifications: A person who is experienced in providing consulting services for door hardware installations that are comparable in material, design, and extent to that indicated for this Project and who is currently certified by DHI as an Architectural Hardware Consultant (AHC)
- E. Supplier Qualifications: Company with certified Architectural Hardware Consultant (AHC) and Electrified Hardware Consultant (EHC) to assist in work of this section.

# 1.09 DELIVERY, STORAGE, AND HANDLING

- A. Inventory door hardware on receipt and provide secure lockup for door hardware delivered to Project site.
- B. Tag each item or package seperately with identification coordinated with the final door hardware schedule, and include installation instructions, templates, and necessary fasteners with each item or package.
- C. Deliver keys to manufacturer of key control system for subsequent delivery to Owner.
- D. Deliver keys to permanent cores to Owner by registered mail or overnight package service.
- E. Package hardware items individually; label and identify each package with door opening code to match door hardware schedule.

# 1.10 WARRANTY

- A. Special Warranty: Manufacturer agrees to repair or replace components of door hardware that fail in materials or workmanship within specified warranty period.
  - 1. Failures include, but are not limited to, the following:
    - a. Structural failures, including excessive deflection, cracking, or breakage.
    - b. Faulty operation of doors and door hardware.
    - c. Deterioation of metals, metal finishes, and other materials beyond normal weathering and use.
  - 2. Warranty Period: Three years from date of Substatial Completion unless otherwise indicated below:
    - a. Manual Closers: 10 years from date of Substatial Completion.
- B. Manufacturer's Warranty: Provide warranty against defects in material and workmanship for period indicated. Complete forms in Owner's name and register with manufacturer.
  - 1. Closers: Five years, minimum.
  - 2. Exit Devices: Three years, minimum.
  - 3. Locksets and Cylinders: Three years, minimum.
  - 4. Other Hardware: Two years, minimum.

### PART 2 PRODUCTS

### 2.01 SOURCE LIMITATIONS

A. Obtain each type of door hardware from single manufacturer.

#### 2.02 PERFORMANCE CRITERIA

- A. Provide specified door hardware as required to make doors fully functional, compliant with applicable codes, and secure to extent indicated.
- B. Provide individual items of single type, of same model, and by same manufacturer.
- C. Provide door hardware products that comply with the following requirements:
  - 1. Applicable provisions of federal, state, and local codes.
  - 2. Accessibility: ADA Standards and ICC A117.1.
  - 3. Applicable provisions of NFPA 101.
  - 4. Hardware Preparation for Steel Doors and Steel Frames: BHMA A156.115.
  - 5. Hardware Preparation for Wood Doors with Wood or Steel Frames: BHMA A156.115W.
  - 6. Products Requiring Electrical Connection: Listed and classified by UL (DIR) as suitable for the purpose specified.
- D. Fire-Rated Doors Assemblies: Where fire-rated doors are indicated, provide door hardware complying with NFPA 80, that is listed and labeled by qualified testing agency, for fire-protection ratings indicated, based on testing at positive pressure in accordance with NFPA 252 or UL 10C.
- E. Smoke- and Draft-Control Door Assemblies: Where smoke- and draft-control door assemblies are required, proivde door hardware that complies with requirements of assemblies tested in accordance with UL 1784 and installed in compliance with NFPA 105.
  - 1. Air-leakage Rate: Maximum air leakage of 0.3 cfm per sq. ft. at the tested pressure differential of 0.3 inch wg of water.
- F. Means of Egree Doors: Latches do not require more than 15 lbf to release the latch. Locks do not require use of a key, tool, or special knowledge for operation.
- G. Accessiblity Requirements: For door hardware on doors in an accesible route, comply with the USDOJ's "2010 ADA Standards for Accessible Design."
  - 1. Provide operating devices that do not require tight grasping, pinching, or twisting of the wrist and that operate with a force of not more than 5 lbf.
  - 2. Comply with the following maximum opening-force requirements:
    - a. Interior, Non-Fire-Rated Hinged Doors: 5lbf. applied perpendicular to door.
    - b. Sliding or Folding Doors: 5 lbf. applied parallel to door at latch.
    - c. Fire Doors: Minimum opening force allowable by authorities having jurisdication.
  - 3. Bevel raised thresholds with a slope of not more than 1:2. Provide thresholds not more than 1/2 inch high.
  - 4. Adjust door closer sweep periods so that, from an open position of 90 degrees, the door will take at least 5 seconds to move to a position of 12 degrees from the latch.
  - 5. Adjust spring hinges so that, from an open position of 70 degrees, the door will take at least 1.5 seconds to move to the closed position.
    - a. Products Requiring Electrical Connection: Listed and classified by UL (DIR) as suitable for the purpose specified.
- H. Electrically Operated and/or Controlled Hardware: Provide necessary power supplies, power transfer hinges, relays, and interfaces as required for proper operation; provide wiring between hardware and control components and to building power connection in compliance with NFPA 70.
- Lock Function: Provide lock and latch function numbers and descriptions of manufacturer's series. See Door Hardware Schedule.
- J. Fasteners:

- 1. Provide fasteners of proper type, size, quantity, and finish that comply with commercially recognized standards for proposed applications.
  - a. Aluminum fasteners are not permitted.
  - b. Provide phillips flat-head screws with heads finished to match door surface hardware unless otherwise indicated.
- 2. Provide machine screws for attachment to reinforced hollow metal and aluminum frames.
  - a. Self-drilling (Tek) type screws are not permitted.
- Provide stainless steel machine screws and lead expansion shields for concrete and masonry substrates.
- 4. Provide spacers or sex bolts with sleeves for through bolting of hollow metal doors and frames.
- 5. Fire-Rated Applications: Comply with NFPA 80.
  - a. Provide wood or machine screws for hinges mortised to doors or frames, strike plates to frames, and closers to doors and frames.
  - b. Provide steel through bolts for attachment of surface mounted closers, hinges, or exit devices to door panels unless proper door blocking is provided.

#### 2.03 HINGES

- A. Manufacturers:
  - 1. McKinney; an Assa Abloy Group company
  - 2. D&D Technologies USA, Inc
  - 3. Hager Companies;
  - 4. Stanley, dormakaba Group
- B. Hinges: Comply with BHMA A156.1, Grade 1. Provide template-produced hinges for hinges installed on hollow-metal doors and hollow-metal frames.
  - 1. Butt Hinges: Comply with BHMA A156.1 and BHMA A156.7 for templated hinges.
    - a. Provide hinge width required to clear surrounding trim.
  - 2. Provide hinges on every swinging door.
  - 3. Provide non-removable pins on exterior outswinging doors.
  - 4. Provide following quantity of butt hinges for each door:
    - a. Doors From 60 inches High up to 90 inches High: Three hinges.

### 2.04 EXIT DEVICES

- A. Manufacturers:
  - 1. Sargent or Yale; an Assa Abloy Group company
  - 2. dormakaba
  - 3. Hager Companies
  - 4. Precision, dormakaba Group
  - 5. Von Duprin, an Allegion brand
- B. Exit Devices: Comply with BHMA A156.3, Grade 1.
  - 1. Lever design to match lockset trim.
  - 2. Provide cylinder with cylinder dogging or locking trim.
  - 3. Provide exit devices properly sized for door width and height.
  - 4. Provide strike as recommended by manufacturer for application indicated.
  - 5. Provide UL (DIR) listed exit device assemblies for fire-rated doors and panic device assemblies for non-fire-rated doors.

# 2.05 ELECTRIC STRIKES

- A. Manufacturers:
  - 1. Adams Rite, HES, or Securitron; an Assa Abloy Group company
  - 2. Pamex, Inc
  - 3. Von Duprin, an Allegion brand.
- B. Electric Strikes: Comply with BHMA A156.31, Grade 1.

Door Hardware

- 1. Provide UL (DIR) listed burglary-resistant electric strike; style to suit locks.
- 2. Provide non-handed 24 VDC electric strike suitable for door frame material and scheduled lock configuration.
- 3. Connect electric strikes into fire alarm where non-rated doors are scheduled to release with fire or sprinkler alarm condition.

### 2.06 LOCK CYLINDERS

- A. Manufacturers:
  - 1. Best, dormakaba Group
  - Schlage, an Allegion brand
  - 3. Sargent; an Assa Abloy Group company
- B. Lock Cylinders: Provide key access on outside of each lock, unless otherwise indicated.
  - Provide standard, electronic, conventional, full size interchangeable core (FSIC), and small format interchangeable core (SFIC) type cylinders, Grade 1, with six-pin core in compliance with BHMA A156.5 at locations indicated.
  - 2. Provide cylinders from same manufacturer as locking device.
  - 3. Provide cams and/or tailpieces as required for locking devices.

# 2.07 MORTISE LOCKS

- A. Manufacturers:
  - 1. Sargent; an Assa Abloy Group company
  - 2. Best, dormakaba Group
  - 3. DORMA USA, Inc;
  - 4. Hager Companies
  - 5. Schlage, an Allegion brand
- B. Mortise Locks: Comply with BHMA A156.13, Grade 1, Security, 1000 Series.
  - 1. Latchbolt Throw: 3/4 inch, minimum.
  - 2. Deadbolt Throw: 1 inch, minimum.
  - 3. Backset: 2-3/4 inch unless otherwise indicated.
  - 4. Strikes: Provide manufacturer's standard strike for each latchset or lockset with strike box and curved lip extending to protect frame in compliance with indicated requirements.
    - a. Finish: To match lock or latch.

# 2.08 AUXILIARY LOCKS (DEADLOCKS)

- A. Manufacturers:
  - 1. Yale or Sargent; an Assa Abloy Group company
  - 2. Best, dormakaba Group
  - 3. dormakaba
  - 4. Hager Companies
- B. Auxiliary Locks (Deadlocks): Comply with BHMA A156.36, Grade 1.
  - 1. Type: Bored (cylindrical).
  - 2. Application: Bored.
  - 3. Backset: 2-3/4 inch, unless otherwise indicated.
  - 4. Bolt Throw: 1/2 inch, with latch made of hardened steel.
  - 5. Provide strike that matches frame.

# 2.09 DOOR PULLS AND PUSH PLATES

- A. Manufacturers:
  - 1. Rockwood; an Assa Abloy Group company; \_\_\_\_\_
  - 2. Hager Companies
  - 3. Hiawatha, Inc, division of Activar Construction Products Group, Inc
  - 4. Pamex, Inc

- 5. Trimco
- B. Door Pulls and Push Plates: Comply with BHMA A156.6.
  - 1. Pull Type: Straight, unless otherwise indicated.
  - 2. Push Plate Type: Flat, with square corners, unless otherwise indicated.
    - a. Edges: Beveled, unless otherwise indicated.
  - 3. Material: Aluminum, unless otherwise indicated.

# 2.10 CLOSERS

- A. Manufacturers: Surface Mounted:
  - 1. Corbin Russwin, Norton, Rixson, Sargent, or Yale; an Assa Abloy Group company
  - 2. DORMA USA, Inc
  - 3. Hager Companie
  - 4. LCN, an Allegion brand
  - 5. Pamex, Inc
  - 6. Stanley, dormakaba Group
- B. Closers: Comply with BHMA A156.4, Grade 1.
  - 1. Type: Surface mounted to door.
  - 2. Provide door closer on each exterior door.
  - 3. At corridor entry doors, mount closer on room side of door.
  - 4. At outswinging exterior doors, mount closer on interior side of door.

# 2.11 OVERHEAD STOPS AND HOLDERS

- A. Manufacturers:
  - 1. Rixson or Sargent; an Assa Abloy Group company
  - 2. DORMA USA, Inc
  - 3. Glynn-Johnson, an Allegion brand
  - 4. Pamex, Inc
- 3. Overhead Stops and Holders (Door Checks): Comply with BHMA A156.8, Grade 1.
  - 1. Provide stop for every swinging door, unless otherwise indicated.

### 2.12 POWER DOOR OPERATORS

A. See Section 087113.

## 2.13 KICK PLATES

- A. Manufacturers:
  - 1. Hiawatha, Inc, an Activar Construction Products Group company
  - 2. Ives, an Allegion brand
  - 3. Standard Metal Hardware Manufacturing Ltd
  - 4. Trimco
- B. Kick Plates: Provide along bottom edge of push side of every door with closer, except aluminum storefront and glass entry doors, unless otherwise indicated.
  - 1. Size: 12 inch high by 2 inch less door width (LDW) on push side of door.

### 2.14 ASTRAGALS

- A. Manufacturers:
  - 1. Pemko; an Assa Abloy Group company
  - 2. Hager Companies
  - 3. Standard Metal Hardware Manufacturing Ltd
- B. Astragals: Comply with BHMA A156.22.
  - 1. Type: Split, two parts, and with sealing gasket.
  - 2. Material: Aluminum, with neoprene weatherstripping.
  - 3. Provide non-corroding fasteners at exterior locations.

### Door Hardware

### 2.15 THRESHOLDS

- A. Manufacturers:
  - 1. Dunbarton Corporation
  - 2. Pemko; an Assa Abloy Group company
  - 3. Hager Companies
  - 4. Futura Transitions; by Bonnell Aluminum
- B. Thresholds: Comply with BHMA A156.21.
  - 1. Provide threshold at each exterior door, unless otherwise indicated.
  - 2. Type: Flat surface.
  - 3. Material: Aluminum.
  - 4. Threshold Surface: Fluted horizontal grooves across full width.
  - 5. Field cut threshold to profile of frame and width of door sill for tight fit.
  - 6. Provide non-corroding fasteners at exterior locations.

## 2.16 WEATHERSTRIPPING AND GASKETING

- A. Manufacturers:
  - 1. Dunbarton Corporation
  - 2. Pemko; an Assa Abloy Group company
  - 3. Hager Companies
- B. Weatherstripping and Gasketing: Comply with BHMA A156.22.
  - 1. Head and Jamb Type: Adjustable.
  - 2. Door Sweep Type: Encased in retainer.
  - 3. Material: Aluminum, with neoprene weatherstripping.
  - 4. Provide weatherstripping on each exterior door at head, jambs, and meeting stiles of door pairs, unless otherwise indicated.
  - 5. Provide door bottom sweep on each exterior door, unless otherwise indicated.

### 2.17 LATCH PROTECTOR

- A. Latch Protector: Provide on door to protect latch from being tampered with while in locked position.
  - 1. Type: Standard latch protector.
  - 2. Material: Stainless steel.

#### 2.18 FINISHES

A. Finishes: Identified in Door Hardware Schedule.

## PART 3 EXECUTION

# 3.01 EXAMINATION

- A. Examine doors and frames, with Installer present, for compliance with requirements for installation tolerances, labeled fire-rated door assembly construction, wall and floor construction, and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.
- C. Verify that electric power is available to power operated devices and of correct characteristics.

## 3.02 PREPARATION

- A. Steel Doors and Frames: For surface-applied door hardware, drill and tap doors and frames in accordance with ANSI/SDI A250.6.
- B. Wood Doors: Comply with door and hardware manufacturers' written instructions.

### 3.03 INSTALLATION

- A. Install hardware in accordance with manufacturer's instructions and applicable codes.
- B. Install hardware on fire-rated doors and frames in accordance with applicable codes and NFPA 80.

Door Hardware

- C. Use templates provided by hardware item manufacturer.
- D. Do not install surface mounted items until application of finishes to substrate are fully completed.
- E. Door Hardware Mounting Heights: Distance from finished floor to center line of hardware item. As indicated in following list; unless noted otherwise in Door Hardware Schedule or on drawings.
  - 1. For Steel Doors and Frames: Install in compliance with DHI (LOCS) recommendations.
  - 2. For Wood Doors: Install in compliance with DHI WDHS.3 recommendations.
  - 3. Mounting heights in compliance with ADA Standards:
    - a. Locksets: 40-5/16 inch.
    - b. Push Plates/Pull Bars: 42 inch.
    - c. Deadlocks (Deadbolts): 48 inch.
    - d. Exit Devices: 40-5/16 inch.
- F. Set exterior door thresholds with full-width bead of elastomeric sealant at each point of contact with floor providing a continuous weather seal; anchor thresholds with stainless steel countersunk screws.

# 3.04 FIELD QUALITY CONTROL

A. Provide an Architectural Hardware Consultant (AHC) to inspect installation and certify that hardware and installation has been furnished and installed in accordance with manufacturer's instructions and as specified.

# 3.05 ADJUSTING

- A. Adjust hardware for smooth operation.
- B. Adjust gasketing for complete, continuous seal; replace if unable to make complete seal.

## 3.06 CLEANING

- A. Clean finished hardware in accordance with manufacturer's written instructions after final adjustments have been made.
- B. Clean adjacent surfaces soiled by hardware installation.

### 3.07 PROTECTION

A. Do not permit adjacent work to damage hardware or finish.

### END OF SECTION

# SECTION 087113 POWER DOOR OPERATORS

# PART 1 GENERAL

# 1.01 SECTION INCLUDES

- A. Operators for swinging doors.
- B. Controllers, actuators, and safety devices.

### 1.02 REFERENCE STANDARDS

- A. AAMA 611 Voluntary Specification for Anodized Architectural Aluminum; 2020.
- B. ADA Standards 2010 ADA Standards for Accessible Design; 2010.
- C. BHMA A156.19 Power Assist and Low Energy Power Operated Swinging Doors; 2019.
- D. NFPA 70 National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- E. NFPA 101 Life Safety Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

# 1.03 ADMINISTRATIVE REQUIREMENTS

A. Coordination: Coordinate power door operators with balance of door hardware and electrical work required for each affected door opening.

### 1.04 SUBMITTALS

- A. See Section 013300 Submittals for submittal procedures.
- B. Product Data: Provide data on system components, sizes, features, and finishes.
- C. Manufacturer's Installation Instructions: Indicate special procedures, perimeter conditions requiring special attention, and manufacturer's hardware and component templates.
- D. Maintenance Data: Include manufacturer's parts list and maintenance instructions for each type of hardware and operating component.

# 1.05 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing products specified in this section, with not less than three years of documented experience, and a member of AAADM.
- B. Installer Qualifications: Company specializing in performing work of the type specified and with at least three years documented experience and approved by manufacturer.

# 1.06 WARRANTY

A. Manufacturer Warranty: Provide 2-year manufacturer warranty for components of power door operators. Complete forms in Owner's name and register with manufacturer.

# **PART 2 PRODUCTS**

# 2.01 MANUFACTURERS

- A. Operators for Swinging Doors:
  - 1. Horton Automatics: www.hortondoors.com.
  - 2. NABCO Entrances Inc: www.nabcoentrances.com.
  - 3. Stanley Access Technologies: www.stanleyaccess.com.

# 2.02 POWER DOOR OPERATORS - GENERAL

- A. Comply with ADA Standards for egress requirements.
- B. Comply with NFPA 101 and requirements of authorities having jurisdiction; provide units selected for actual door weight and for light pedestrian traffic unless otherwise indicated.

- C. System Integration: Integrate operator functionality with other systems as required for a complete working installation.
  - 1. Provide time delay relay to signal automatic door operator to activate only after electric lock system is released.
  - 2. Provide controller output signals at the door closed or door open positions to facilitate interaction with security and access control systems.

# 2.03 OPERATORS FOR SWINGING DOORS

- A. Door Operator: Electromechanical.
  - 1. Applications: Include operators for single and double doors.
  - Electromechanical Operators: Capable of operating and controlling up to 330 pound door, selfcontained.
  - 3. Speed Control: Constant opening and closing cycles.
  - 4. Functionality: Low-energy power open, spring close operation.
    - a. Low-Energy Power Operators: Comply with BHMA A156.19; operator activated by pushing or pulling the door or by manual actuator, not a sensor; safeties not required.
      - 1) Kinetic Energy of Door in Motion: 1.25 lbf ft, maximum.
      - 2) Force Required to Prevent Stopped Door From Opening or Closing: 15 lbf, maximum, measured at 1 inch from the latch edge of the door at any point in the swing cycle.
  - 5. Mounting: Surface mounted overhead.
  - 6. Power Supply Units: Self-contained, electrically operated, and independent of door operator.
  - 7. Actuators:
    - a. Push-Side Actuator: Push plate.
    - b. Pull-Side Actuator: Push plate.
  - 8. Pull-Side Safety: Door mounted.

# 2.04 CONTROLLERS, ACTUATORS, AND SAFETY DEVICES

- A. Actuators: Manufacturer's standard for products specified.
  - 1. Push Plate Actuator: Standard, wall mounted, recessed, momentary contact type; satin stainless steel plate; 4.5 inch square; labeled with handicapped logo and "Push To Open" Text.
- B. Safety Devices: Manufacturer's standard units recommended for project applications and conditions.
  - 1. Swinging Door Safety Device: Door-mounted presence detector arranged to prevent operation of door when persons or obstructions are in the swing zone.

# 2.05 ELECTRICAL CHARACTERISTICS AND COMPONENTS

- A. Electrical Characteristics:
  - 1. 5 rated load amperes.
  - 2. 115 volts, single phase, 60 Hz.
- B. Wiring Terminations: Provide terminal lugs to match branch circuit conductor quantities, sizes, and materials indicated. Enclose terminal lugs in terminal box sized to NFPA 70.
- C. Disconnect Switch: Factory mount disconnect switch in control panel.

### 2.06 FINISHES

- A. Aluminum Finishes: Manufacturer's standard.
  - 1. Class II Natural Anodized Finish: Clear anodic coating; AAMA 611 AA-M12C22A31, minimum dry film thickness (DFT) of 0.4 mil, 0.0004 inch.

### PART 3 EXECUTION

### 3.01 EXAMINATION

- A. Verify installation conditions including, but not limited to the following: opening sizes, floor conditions, plumb and level mounting surfaces.
- B. Verify that surfaces are ready to receive work and dimensions are as instructed by the manufacturer.

Power Door Operators

C. Verify that electric power is available, in the correct location, and of the correct characteristics.

# 3.02 INSTALLATION

- A. Coordinate installation of components with related and adjacent work.
- B. Install equipment in accordance with manufacturer's instructions.

# 3.03 ADJUSTING

A. Adjust door equipment for correct function and smooth operation.

# 3.04 CLEANING

A. Remove temporary protection, clean exposed surfaces.

# 3.05 CLOSEOUT ACTIVITIES

A. Demonstrate to Owner's representative equipment operation, operating components, adjustment features, and lubrication requirements.

# **END OF SECTION**

# SECTION 088000 GLAZING

# PART 1 GENERAL

# 4.01 SECTION INCLUDES

Insulating glass units.

### 4.02 RELATED REQUIREMENTS

A. Section 084313 - Aluminum-Framed Storefronts: Glazing provided as part of storefront assembly.

## 4.03 REFERENCE STANDARDS

- A. 16 CFR 1201 Safety Standard for Architectural Glazing Materials; Current Edition.
- B. ANSI Z97.1 American National Standard for Safety Glazing Materials Used in Buildings Safety Performance Specifications and Methods of Test; 2015 (Reaffirmed 2020).
- C. ASCE 7 Minimum Design Loads and Associated Criteria for Buildings and Other Structures; Most Recent Edition Cited by Referring Code or Reference Standard.
- D. ASTM C864 Standard Specification for Dense Elastomeric Compression Seal Gaskets, Setting Blocks, and Spacers; 2005 (Reapproved 2019).
- E. ASTM C1036 Standard Specification for Flat Glass; 2021.
- F. ASTM C1048 Standard Specification for Heat-Strengthened and Fully Tempered Flat Glass; 2018.
- G. ASTM C1172 Standard Specification for Laminated Architectural Flat Glass; 2019.
- H. ASTM C1193 Standard Guide for Use of Joint Sealants; 2016 (Reapproved 2023).
- ASTM C1376 Standard Specification for Pyrolytic and Vacuum Deposition Coatings on Flat Glass; 2021a.
- J. ASTM E1300 Standard Practice for Determining Load Resistance of Glass in Buildings; 2016.
- K. ASTM E2190 Standard Specification for Insulating Glass Unit Performance and Evaluation; 2019.
- L. GANA (SM) GANA Sealant Manual; 2008.
- M. NFRC 100 Procedure for Determining Fenestration Product U-factors; 2023.
- N. NFRC 200 Procedure for Determining Fenestration Product Solar Heat Gain Coefficient and Visible Transmittance at Normal Incidence: 2023.
- O. NFRC 300 Test Method for Determining the Solar Optical Properties of Glazing Materials and Systems; 2023.

# 4.04 SUBMITTALS

- A. See Section 013300 Submittals, for submittal procedures.
- B. Product Data on Insulating Glass Unit Glazing Types: Provide structural, physical and environmental characteristics, size limitations, special handling and installation requirements.
- C. Product Data on Glazing Compounds and Accessories: Provide chemical, functional, and environmental characteristics, limitations, special application requirements, and identify available colors.
- D. Certificate: Certify that products of this section meet or exceed specified requirements.
- E. Manufacturer's qualification statement.
- F. Installer's qualification statement.
- G. Warranty Documentation: Submit manufacturer warranty and ensure that forms have been completed in Owner's name and registered with manufacturer.

### 4.05 OUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum three years of documented experience.
  - 1. Provide certified glass products through ANSI accredited certifications that include plant audits and independent laboratory performance testing.
    - a. Insulating Glass Certification Council (IGCC).
    - b. Safety Glazing Certification Council (SGCC).
- B. Installer Qualifications: Company specializing in performing work of the type specified and with at least three years documented experience.

### 4.06 FIELD CONDITIONS

- A. Do not install glazing when ambient temperature is less than 40 degrees F.
- B. Maintain minimum ambient temperature before, during and 24 hours after installation of glazing compounds.

# 4.07 WARRANTY

A. Insulating Glass Units: Provide a five (5) year manufacturer warranty to include coverage for seal failure, interpane dusting or misting, including providing products to replace failed units.

# PART 2 PRODUCTS

# 5.01 MANUFACTURERS

- A. Glass Fabricators:
  - 1. GGI General Glass International
  - 2. Tecnoglass
  - 3. Thompson I.G., LLC
  - 4. Trulite Glass & Aluminum Solutions, LLC
  - 5. Viracon, Inc

# 5.02 PERFORMANCE REQUIREMENTS - EXTERIOR GLAZING ASSEMBLIES

- A. Provide type and thickness of exterior glazing assemblies to support assembly dead loads, and to withstand live loads caused by positive and negative wind pressure acting normal to plane of glass.
  - 1. Design Pressure: Calculated in accordance with ASCE 7.
  - 2. Comply with ASTM E1300 for design load resistance of glass type, thickness, dimensions, and maximum lateral deflection of supported glass.
  - 3. Provide glass edge support system sufficiently stiff to limit the lateral deflection of supported glass edges to less than 1/175 of their lengths under specified design load.
  - 4. Glass thicknesses listed are minimum.
- B. Weather-Resistive Barrier Seals: Provide completed assemblies that maintain continuity of building enclosure water-resistive barrier, vapor retarder, and/or air barrier.
- C. Thermal and Optical Performance: Provide exterior glazing products with performance properties as indicated. Performance properties are in accordance with manufacturer's published data as determined with the following procedures and/or test methods:
  - 1. Center of Glass U-Value: Comply with NFRC 100 using Lawrence Berkeley National Laboratory (LBNL) WINDOW 6.3 computer program.
  - 2. Center of Glass Solar Heat Gain Coefficient (SHGC): Comply with NFRC 200 using Lawrence Berkeley National Laboratory (LBNL) WINDOW 6.3 computer program.
  - 3. Solar Optical Properties: Comply with NFRC 300 test method.

# 5.03 GLASS MATERIALS

- A. Float Glass: Provide float glass based glazing unless otherwise indicated.
  - 1. Kind FT Fully Tempered Type: Complies with ASTM C1048.

- 2. Safety Wired Glass Type: ASTM C1036, Type II Wired Flat Glass, Quality Q5, complying with ANSI Z97.1 Class B, or 16 CFR 1201 Category I impact test requirements, and with color and performance characteristics as indicated.
- B. Laminated Glass: Float glass laminated in accordance with ASTM C1172.
  - 1. Laminated Safety Glass: Complies with ANSI Z97.1 Class B or 16 CFR 1201 Category I impact test requirements.

### 5.04 INSULATING GLASS UNITS

- A. Fabricator: Certified by glass manufacturer for type of glass, coating, and treatment involved and capable of providing specified warranty.
- B. Insulating Glass Units: Types as indicated.
  - 1. Durability: Certified by an independent testing agency to comply with ASTM E2190.
  - 2. Coated Glass: Comply with requirements of ASTM C1376 for pyrolytic (hard-coat) or magnetic sputter vapor deposition (soft-coat) type coatings on flat glass; coated vision glass, Kind CV; coated overhead glass, Kind CO; or coated spandrel glass, Kind CS.
  - 3. Spacer Color: Black.
  - Edge Seal:
    - a. Single-Sealed System: Provide silicone, polysulfide, or polyurethane sealant as seal applied around perimeter.
    - b. Color: Black.
  - 5. Purge interpane space with dry air, hermetically sealed.
- C. Insulating Glass Units: Safety glazing.
  - 1. Applications:
    - a. Other locations required by applicable federal, state, and local codes and regulations.
    - b. Other locations indicated on drawings.
  - 2. Space between lites filled with air.
  - 3. Total Thickness: 1 inch.
  - 4. Glazing Method: Dry glazing method, gasket glazing.

## 5.05 ACCESSORIES

- A. Setting Blocks: Silicone, with 80 to 90 Shore A durometer hardness; ASTM C864 Option II. Length of 0.1 inch for each square foot of glazing or minimum 4 inch by width of glazing rabbet space minus 1/16 inch by height to suit glazing method and pane weight and area.
- B. Glazing Splines: Resilient silicone extruded shape to suit glazing channel retaining slot; ASTM C864 Option II; color black.

# PART 3 EXECUTION

## 6.01 VERIFICATION OF CONDITIONS

- A. Verify that openings for glazing are correctly sized and within tolerances, including those for size, squareness, and offsets at corners.
- B. Verify that the minimum required face and edge clearances are being provided.
- C. Verify that surfaces of glazing channels or recesses are clean, free of obstructions that may impede moisture movement, weeps are clear, and support framing is ready to receive glazing system.
- D. Verify that sealing between joints of glass framing members has been completed effectively.
- E. Proceed with glazing system installation only after unsatisfactory conditions have been corrected.

### 6.02 PREPARATION

- A. Clean contact surfaces with appropriate solvent and wipe dry within maximum of 24 hours before glazing. Remove coatings that are not tightly bonded to substrates.
- 3. Seal porous glazing channels or recesses with substrate compatible primer or sealer.

C. Prime surfaces scheduled to receive sealant where required for proper sealant adhesion.

# 6.03 INSTALLATION, GENERAL

- A. Install glazing in compliance with written instructions of glass, gaskets, and other glazing material manufacturers, unless more stringent requirements are indicated, including those in glazing referenced standards.
- B. Install glazing sealants in accordance with ASTM C1193, GANA (SM), and manufacturer's instructions.
- C. Do not exceed edge pressures around perimeter of glass lites as stipulated by glass manufacturer.
- D. Prevent glass from contact with any contaminating substances that may be the result of construction operations such as, and not limited to the following; weld splatter, fire-safing, plastering, mortar droppings, and paint.

# 6.04 INSTALLATION - DRY GLAZING METHOD (GASKET GLAZING)

- A. Application Exterior and/or Interior Glazed: Set glazing infills from either the exterior or the interior of the building.
- B. Place setting blocks at 1/4 points with edge block no more than 6 inch from corners.
- Rest glazing on setting blocks and push against fixed stop with sufficient pressure on gasket to attain full contact.
- D. Install removable stops without displacing glazing gasket; exert pressure for full continuous contact.

# 6.05 FIELD QUALITY CONTROL

- Glass and Glazing product manufacturers to provide field surveillance of the installation of their products.
- B. Monitor and report installation procedures and unacceptable conditions.

# 6.06 CLEANING

- A. Remove excess glazing materials from finish surfaces immediately after application using solvents or cleaners recommended by manufacturers.
- B. Remove nonpermanent labels immediately after glazing installation is complete.
- C. Clean glass and adjacent surfaces after sealants are fully cured.
- D. Clean glass on both exposed surfaces not more than 4 days prior to Date of Substantial Completion in accordance with glass manufacturer's written recommendations.

## 6.07 PROTECTION

- A. After installation, mark pane with an 'X' by using removable plastic tape or paste; do not mark heat absorbing or reflective glass units.
- B. Remove and replace glass that is damaged during construction period prior to Date of Substantial Completion.

### END OF SECTION

# SECTION 092116 GYPSUM BOARD ASSEMBLIES

# PART 1 GENERAL

# 1.01 SECTION INCLUDES

- A. Performance criteria for gypsum board assemblies.
- B. Metal stud wall framing.
- C. Acoustic insulation.
- D. Gypsum wallboard.
- E. Joint treatment and accessories.

# 1.02 RELATED REQUIREMENTS

A. Section 092216 - Non-Structural Metal Framing.

### 1.03 REFERENCE STANDARDS

- A. AISI S220 North American Standard for Cold-Formed Steel Nonstructural Framing; 2020.
- B. AISI S240 North American Standard for Cold-Formed Steel Structural Framing; 2015, with Errata (2020).
- C. ASTM A36/A36M Standard Specification for Carbon Structural Steel; 2019.
- D. ASTM A653/A653M Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process; 2023.
- E. ASTM A1003/A1003M Standard Specification for Steel Sheet, Carbon, Metallic- and Nonmetallic-Coated for Cold-Formed Framing Members; 2015.
- F. ASTM C1007 Standard Specification for Installation of Load Bearing (Transverse and Axial) Steel Studs and Related Accessories; 2020.
- G. ASTM C475/C475M Standard Specification for Joint Compound and Joint Tape for Finishing Gypsum Board; 2017 (Reapproved 2022).
- H. ASTM C754 Standard Specification for Installation of Steel Framing Members to Receive Screw-Attached Gypsum Panel Products; 2020.
- I. ASTM C840 Standard Specification for Application and Finishing of Gypsum Board; 2023.
- J. ASTM C1396/C1396M Standard Specification for Gypsum Board; 2017.
- K. ASTM C1658/C1658M Standard Specification for Glass Mat Gypsum Panels; 2019, with Editorial Revision (2020).
- L. ASTM D3273 Standard Test Method for Resistance to Growth of Mold on the Surface of Interior Coatings in an Environmental Chamber; 2021.
- M. ASTM E84 Standard Test Method for Surface Burning Characteristics of Building Materials; 2023d.
- N. ASTM E90 Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements; 2023.
- O. ASTM E413 Classification for Rating Sound Insulation; 2022.
- P. GA-216 Application and Finishing of Gypsum Panel Products; 2021.

# 1.04 ADMINISTRATIVE REQUIREMENTS

- A. Coordination: Coordinate the installation of gypsum board assemblies with size, location, and installation of service utilities.
- B. Preinstallation Meeting: Conduct a preinstallation meeting one week prior to the start of the work of this section; require attendance by all affected installers.
- C. Sequencing: Install service utilities in an orderly and expeditious manner.

Gypsum Board Assemblies

### 1.05 SUBMITTALS

- A. See Section 013300 Submittals, for submittal procedures.
- B. Product Data:
  - 1. Provide data on metal framing, gypsum board, accessories, and joint finishing system.
  - 2. Provide manufacturer's data on partition head to structure connectors, showing compliance with requirements.
- C. Installer's Qualification Statement.

# 1.06 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Member of Steel Stud Manufacturers Association (SSMA): www.ssma.com/#sle.
- B. Installer Qualifications: Company specializing in performing work of the type specified and with at least three years of documented experience.

# 1.07 DELIVERY, STORAGE, AND HANDLING

- A. Store gypsum products and accessories indoors and keep above freezing. Elevate boards above floor, on nonwicking supports, in accordance with manufacturer's recommendations.
- B. Store metal products to prevent corrosion.

### PART 2 PRODUCTS

### 2.01 GYPSUM BOARD ASSEMBLIES

- A. Provide completed assemblies complying with ASTM C840 and GA-216.
- B. Interior Partitions: Provide completed assemblies with the following characteristics:
  - 1. Acoustic Attenuation: STC of 45-49 calculated in accordance with ASTM E413, based on tests conducted in accordance with ASTM E90.
- C. Fire-Resistance-Rated Assemblies: Provide completed assemblies complying with applicable code.

# 2.02 METAL FRAMING MATERIALS

- A. Steel Sheet: ASTM A1003/A1003M, subject to the ductility limitations indicated in AISI S220 or equivalent.
- B. Manufacturers Metal Framing, Connectors, and Accessories:
  - 1. ClarkDietrich
  - 2. Jaimes Industries
  - 3. R-stud
  - 4. SCAFCO Corporation
  - 5. Steel Construction Systems
  - 6. Telling Industries
- C. Nonstructural Steel Framing for Application of Gypsum Board: See Section 092216.
- D. Metal Suspension Systems for Application of Gypsum Board: See Section 092226.23.
- E. Nonstructural Framing System Components: AISI S220; galvanized sheet steel, of size and properties necessary to comply with ASTM C754 for the spacing indicated, with maximum deflection of wall framing of L/120 at 5 psf.
  - 1. Studs: C-shaped with flat faces.
  - 2. Runners: U shaped, sized to match studs.
  - 3. Ceiling Channels: C-shaped.
  - 4. Flexible Track: Flexible framing consisting of adjustable leg straps and pivoting, hinged track brackets designed to provide curved framing assemblies of varying radii.
  - 5. Furring Members: Hat-shaped sections, minimum depth of 7/8 inch.

- F. Partition Head To Structure Connections: Provide track fastened to structure with legs of sufficient length to accommodate deflection, for friction fit of studs cut short.
- G. Deflection and Firestop Track: Intumescent strip factory-applied to track flanges expands when exposed to heat or flames to provide a perimeter joint seal.
- H. Non-structural Framing Accessories:
  - 1. Ceiling Hangers: Type and size as specified in ASTM C754 for spacing required.
  - 2. Partial Height Wall Framing Support: Provides stud reinforcement and anchored connection to floor.
    - a. Materials: ASTM A36/A36M formed sheet steel support member with factory-welded ASTM A1003/A1003M steel plate base.
  - 3. Framing Connectors: ASTM A653/A653M G90 galvanized steel clips; secures cold rolled channel to wall studs for lateral bracing.
- I. Grid Suspension Systems: Steel grid system of main tees and support bars connected to structure using hanging wire.

# 2.03 BOARD MATERIALS

- A. Manufacturers Gypsum-Based Board:
  - 1. American Gypsum Company
  - 2. CertainTeed Corporation
  - 3. Georgia-Pacific Gypsum
  - 4. USG Corporation
- B. Gypsum Wallboard: Paper-faced gypsum panels as defined in ASTM C1396/C1396M; sizes to minimize joints in place; ends square cut.
  - 1. Application: Use for vertical surfaces, unless otherwise indicated.
  - 2. Glass mat faced gypsum panels, as defined in ASTM C1658/C1658M, suitable for paint finish, of the same core type and thickness may be substituted for paper-faced board.
  - 3. Mold Resistance: Score of 10, when tested in accordance with ASTM D3273.
    - a. Mold resistant board is required at all locations.
  - 4. At Assemblies Indicated with Fire-Resistance Rating: Use type required by indicated tested assembly; if no tested assembly is indicated, use Type X board, UL or WH listed.
  - 5. Thickness:
    - a. Vertical Surfaces: 5/8 inch.
- C. Ceiling Board: Special sag resistant gypsum ceiling board as defined in ASTM C1396/C1396M; sizes to minimize joints in place; ends square cut.
  - 1. Application: Ceilings, unless otherwise indicated.
  - 2. Thickness: 5/8 inch.
  - 3. Edges: Tapered.

# 2.04 GYPSUM BOARD ACCESSORIES

- A. Fire and Sound Attenuating Insulation: Sprayed cellulose fire-rated material for cavities in wall assemblies.
  - Surface Burning Characteristics: Provide assemblies with Class I rating, when tested in accordance with ASTM E84.
  - Sound Transmission Class (STC): 56, calculated in accordance with ASTM E413, based on tests conducted in accordance with ASTM E90.
- B. Joint Materials: ASTM C475/C475M and as recommended by gypsum board manufacturer for project conditions.

# PART 3 EXECUTION

# 3.01 EXAMINATION

A. Verify that project conditions are appropriate for work of this section to commence.

Gypsum Board Assemblies

O2339-01-Howerton State Office Building-Renovate

### 3.02 FRAMING INSTALLATION

- A. Metal Framing: Install in accordance with ASTM C1007AISI S220 and manufacturer's instructions.
- B. Suspended Ceilings and Soffits: Space framing and furring members as indicated.
- C. Studs: Space studs at 16 inches on center.
  - 1. Extend partition framing to structure where indicated and to ceiling in other locations.
  - 2. Partitions Terminating at Ceiling: Attach ceiling runner securely to ceiling track in accordance with manufacturer's instructions.
  - 3. Partitions Terminating at Structure: Attach extended leg top runner to structure, maintain clearance between top of studs and structure, and brace both flanges of studs with continuous bridging.

### 3.03 ACOUSTIC ACCESSORIES INSTALLATION

- A. Acoustic Insulation: Place tightly within spaces, around cut openings, behind and around electrical and mechanical items within partitions, and tight to items passing through partitions.
- 3. Acoustic Sealant: Install in accordance with manufacturer's instructions.

# 3.04 BOARD INSTALLATION

- A. Comply with ASTM C840, GA-216, and manufacturer's instructions. Install to minimize butt end joints, especially in highly visible locations.
- B. Single-Layer Nonrated: Install gypsum board in most economical direction, with ends and edges occurring over firm bearing.
- C. Fire-Resistance-Rated Construction: Install gypsum board in strict compliance with requirements of assembly listing.
- D. Installation on Metal Framing: Use screws for attachment of gypsum board except face layer of nonrated double-layer assemblies, which may be installed by means of adhesive lamination.

# 3.05 INSTALLATION OF TRIM AND ACCESSORIES

- A. Control Joints: Place control joints consistent with lines of building spaces and as indicated.
- B. Corner Beads: Install at external corners, using longest practical lengths.
- C. Edge Trim: Install at locations where gypsum board abuts dissimilar materials.
  - 1. See Section 092226.23 and Section 095100 for transition trim.

# 3.06 JOINT TREATMENT

- A. Finish gypsum board in accordance with levels defined in ASTM C840, as follows:
  - 1. Level 4: Walls and ceilings to receive paint finish or wall coverings, unless otherwise indicated.
  - 2. Level 1: Fire-resistance-rated wall areas above finished ceilings, whether or not accessible in the completed construction.
- B. Tape, fill, and sand exposed joints, edges, and corners to produce smooth surface ready to receive finishes.
  - 1. Feather coats of joint compound so that camber is maximum 1/32 inch.

### 3.07 TOLERANCES

A. Maximum Variation of Finished Gypsum Board Surface from True Flatness: 1/8 inch in 10 feet in any direction.

# 3.08 PROTECTION

A. Protect installed gypsum board assemblies from subsequent construction operations.

# SECTION 092216 NON-STRUCTURAL METAL FRAMING

# PART 1 GENERAL

# 1.01 SECTION INCLUDES

A. Framing systems.

### 1.02 RELATED REQUIREMENTS

- A. Section 055000 Metal Fabrications: Toilet partition suspension members.
- B. Section 092116 Gypsum Board Assemblies: Metal studs for gypsum board partition framing.
- C. Section 092226.23 Metal Suspension Systems
- D. Section 095100 Acoustical Ceilings.

# 1.03 REFERENCE STANDARDS

- A. AISI S220 North American Standard for Cold-Formed Steel Nonstructural Framing; 2020.
- B. ASTM E413 Classification for Rating Sound Insulation; 2022.

### 1.04 SUBMITTALS

- A. See Section 013300 Submittals, for submittal procedures.
- B. Product Data: Provide data describing framing member materials and finish, product criteria, load charts, and limitations.
- C. Product Data: Provide manufacturer's data on partition head to structure connectors, showing compliance with requirements.
- D. Product Certificates: For each type of code-compliance certification for studs and tracks.

### 1.05 OUALITY ASSURANCE

- A. Notify manufacturer of damaged materials received prior to installation.
- B. Deliver materials in manufacturer's original, upopened, undamaged containers with identification labels intact.
- C. Protect cold-formed metal framing from corrosion, deformation, and other damage during delivery, storage, and handling as required by AISI S202, "Code of Standard Practice for Cold-Formed Steel Structural Framing."
- D. Installer Qualifications: Company specializing in performing the work of this section with minimum five years documented experience and approved by manufacturer.

# **PART 2 PRODUCTS**

# 2.01 PERFORMANCE REQUIREMENTS

- A. Fire-Test-Response Characteristics: For fire-resistance-rated assemblies that incorporate non-load-bearing steel framing, provide materials and construction identical to those tested in assembly indicated, in accordance with ASTM E119 by an independent testing agency.
- B. STC-Rated Assemblies: For STC-rated assemblies, provide materials and construction identical to those tested in assembly indicated on Drawings, in accordance with ASTM E90 and classfied in accordance with ASTM E413 by an independent testing agency.
- C. Horizontal Deflection: For composite and non-composite wall assemblies, limited to 1/360 of the wall height based on horizontal loading of 10 lbf/sq. ft.
- D. Design framing systems in accordance with AISI S220, "North America Specification for the Design of Cold-Formed Steel Framing Nonstructural Members," unless otherwise indicated.
- E. Design Loads: As indicated on architectural Drawings of 5 lbf/sq. ft. minimum as required by IBC.

### 2.02 FRAMING SYSTEMS

- A. Framing Members, General: Comply with ASTM C645, AISI S220 and ASTM C645, Section 10, AISI S220 for conditions indicated.
  - 1. Steel Sheet Components: Comply with ASTM C645, AISI S220 and ASTM C645, Section 10, AISI S220 requirements for metal unless otherwise noted.
  - 2. Protective Coating: Comply with ASTM C645; ASTM A653/A653M, G40; or coating with equivalent corrosion resistance. Galvannealed products are unacceptable.
    - a. Coating demonstrates equivalent corrosion resistance with an evaluation report acceptable to authorities having jurisdiction.
- B. Studs and Track: ASTM C645.
  - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but not limited to, the following:
    - a. CEMCO
    - b. ClarkDietrich
    - c. Jaimes Industries
    - d. MarinoWARE
    - e. MBA Building Supplies
    - f. MRI Steel Framing, LLC
    - g. Phillips Manufacturering Co
    - h. SCAFCO Corporation
    - i. Steel Construction Systems

### 2.03 SUSPENSION SYSTEMS

- A. See Section 092226.23 for drywall suspension system and drywall soffit framing system.
- B. See Section 095100 for acoustical grid suspension system.

### 2.04 AUXILIARY MATERIALS

- A. General: Provide auxiliary materials that comply with referenced installation standards.
  - 1. Fastners for Steel Framing: Of type, material, size, corrosion, resistance, holding power, and other properties required to fasten steel members to substrates.
  - 2. Non-Loadbearing Framing System Components: AISI S220; sheet steel, of size and properties necessary for the spacing indicated, with maximum deflection of wall framing of L/240 at 5 psf.
    - a. Studs: C-shaped with flat faces.
    - b. Runners: U-shaped, sized to match studs.
  - 3. FABRICATION
    - a. Fabricate assemblies of framed sections to sizes and profiles required.
    - b. Fit, reinforce, and brace framing members to suit design requirements.

### PART 3 EXECUTION

### 3.01 EXAMINATION

- A. Verify existing conditions before starting work.
- B. Examine areas and substrates, with Installer present, and including welded hollow-metal frames, cast-in anchors, and structural framing, for compliance with requirements and other conditions affecting performance of the Work.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

# 3.02 INSTALLATION, GENERAL

- A. Installation Standard: ASTM C754.
  - Gypsum Board Assemblies: Also comply with requirements in ASTM C840 that apply to framing installation.
- B. Install framing and accessories plumb, square, and true to line, with connections securely fastened.

- C. Install supplementary framing, and blocking to support fixtures, equipment services, heavy trim, grab bars, toilet accessories, furnishings, or similar construction.
- D. Install bracing at terminations in assemblies.
- E. Do not bridge building control and expansion joints with non-load-bearing steel framing members. Frame both sides of joints independently.

### 3.03 INSTALLATION OF STUD FRAMING

- A. Extend partition framing to structure where indicated and to ceiling in other locations.
- B. Partitions Terminating at Ceiling: Attach ceiling runner securely to ceiling track in accordance with manufacturer's instructions.
- C. Install Framing system components according to spacings indicated, but not greater than spacings required by referenced installation standards for assembly types.
  - 1. Single-Layer Application: 16 inches o.c. unless otherwise indicated.
- D. Install studs so flanges within framing system point in same direction.
- E. Install tracks at floors and overhead supports. Extend framing full height to structural supports or substrates above suspended ceilings except where partitions are indicated to terminate at suspended ceilings. Continue framing around ducts that penetrate partitions above ceiling.
  - 1. Slip-Type Head Joints: Where framing extends to overhead structural supports, install to produce joints at tops of framing systems that prevent axial loading of finished assemblies.
  - 2. Other Framed Openings: Frame openings other than door openings the same as required for door openings unless otherwise indicated. Install framing below sills of openings to match framing required above door heads.
  - 3. Sound-Rated Partitions: Install framing to comply with sound-rated assembly indicated.
- F. Align and secure top and bottom runners at 24 inches on center.
- G. Fit runners under and above openings; secure intermediate studs to same spacing as wall studs.
- H. Align stud web openings horizontally.
- I. Secure studs to tracks using crimping method. Do not weld.
- J. Fabricate corners using a minimum of three studs.
- K. Install double studs at wall openings, door and window jambs, not more than 2 inches from each side of openings.
- L. Coordinate installation of bucks, anchors, and blocking with electrical, mechanical, and other work to be placed within or behind stud framing.
- M. Blocking: Use wood blocking secured to studs. Provide blocking for support of plumbing fixtures, toilet partitions, wall cabinets, toilet accessories, hardware, and opening frames.

# 3.04 INSTALLATION OF SUSPENSION SYSTEMS

- A. Install suspension sysem components according to spacings indicated, but not greater than spacings required by referenced installation standards for assembly types.
  - 1. Hangers: 48 inches o.c.
  - 2. Carrying Channels (Main Runners): 48 inches o.c.
- B. Isolate suspension systems from building structure where they abut or are penetrated by building structure to prevent transfer of loading imposed by structural movement.
- C. Suspend hangers from building structure as follows:
  - 1. Install ahngers plumb and free from contact with insulation or other objects within ceiling plenum that are not part of supporting structural or suspension system.
    - a. Splay hangers only where required to miss obstructions and offset resulting horizontal forces by bracing, countersplaying, or other equally effective means.

- 2. Where widths of ducts and other construction within ceiling plenum produces hanger spacings that interefere with locations of hangers required to support standard suspension system members, install supplemental suspension members and hangers in the form of trapezes or equivalent devices.
  - a. Size supplemental suspension members and hangers to support ceiling loads within performance limits established by referenced installation standards
- 3. Wire Hangers: Secure by looping and wiring tying, either directly to structures or to inserts, eye screws, or other devices and fasteners that are secure and appropriate for substrate, and in a manner that wil not cause hangers to deteriorate or otherwise fail.
- 4. Flat Hangers: Secure to structure, including intermediate framing members, by attaching to inserts, eye screws, or other devices and fasteners that are secure and appropriate for structure and hanger, and in a manner that will not cause hangers to deteriorate or otherwise fail.
- 5. Do not attach hangers to steel roof deck.
- 6. Do not attach hangers to permanent metal forms. Furnish cast-in-place hanger inserts that extend through forms.
- 7. Do not attach hangers to rolled-in hangers tabs of composite steel floor deck.
- 8. Do not connect or suspend steel framing from ducts, pipes, or conduit.

# 3.05 TOLERANCES

A. Maximum Variation From True Position: Install suspension systems that are level to within 1/8 inch in 12 feet measured lengthwise on each member that will receive finishes and transversely between parallel members that will receive finishes.

# SECTION 092226.23 METAL SUSPENSION SYSTEMS

# PART 1 - GENERAL

### 1.01 RELATED DOCUMENTS

A. Drawings and general conditions of Contract, including General and Supplementary Conditions and Divisions-1 Specification sections apply to work of this section.

#### 1.02 SUMMARY

- A. Section Includes:
  - 1. Suspension System Framing and Furring for Plaster and Gypsum Board Assemblies
  - 2. Main runners, cross tees, framing angles, aluminum trims, steel trims, accessories, hanger wire, finishing trims and fasteners.

# B. Related Sections:

- 1. Section 092116 Gypsum Board Assemblies
- 2. Section 095100 Acoustical Ceilings

### 1.03 REFERENCES

- A. American Society for Testing and Materials (ASTM):
  - 1. ASTM A 641 Standard Specification for Zinc-Coated (Galvanized) Carbon Steel Wire.
  - ASTM A 653 Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) by the Hot-Dip Process.
  - 3. ASTM A 1008 Standard Specification for Steel, Sheet, Cold Rolled, Carbon, Structural, High-Strength Low-Alloy and High-Strength Low-Alloy with Improved Formability"
  - 4. ASTM D 610 Standard Test Method for Evaluating Degree of Rusting on Painted Steel Surfaces
  - 5. ASTM B 117 Standard Practice for Operating Salt Spray (Fog) Apparatus
  - 6. ASTM C 635 Standard Specification for Manufacture, Performance, and Testing of Metal Suspension Systems for Acoustical Tile and Lay-in Panel Ceilings.
  - 7. ASTM C 636 Standard Practice for Installation of Metal Ceiling Suspension Systems for Acoustical Tile and Lay-in Panels.
  - ASTM C 1858 Standard Practice for Design, Construction, and Material Requirements for Direct Hung Suspended T-bar Type Ceiling Systems Intended to Receive Gypsum Panel Products in Areas Subject to Earthquake Ground Motions
  - 9. ASTM C 645 Standard Specification for Nonstructural Steel Framing Members
  - ASTM C 754 Installation of Steel Framing Members to Receive Screw-Attached Gypsum Panel Products
  - 11. ASTM C1002 Standard Specification for Steel Self-Piercing Tapping Screws for the Application of Gypsum Panel Products or Metal Plaster Bases to Wood Studs or Steel Studs.
  - 12. ASTM A1003 Standard Specification for steel sheet used in cold-formed framing members
  - 13. ASTM E 119 Standard Test Method for Fire Tests of Building Construction and Materials (if applicable).
  - 14. ASTM E3118 Standard for Seismic Ceiling Testing
  - 15. ESR-1289 ICC-ES Evaluation Report. (Pending. 2021 ESR Revision)
  - 16. ASTM C1925 Standard Specification for Testing Drywall Grid Suspension systems.

# 1.04 SUBMITTALS

- A. Product Data: Submit manufacturer's technical literature.
- B. Certifications: Manufacturer's certifications that products comply with specified requirements, including laboratory reports showing compliance with specified tests and standards.

# 1.05 QUALITY ASSURANCE

A. Single-Source Responsibility: To ensure proper interface, all drywall furring components shall be produced or supplied by a single manufacturer.

# METAL SUSPENSION SYSTEMS

- B. All accessory components from other manufacturers shall conform to ASTM standards.
- C. Fire Resistance Ratings: As indicated by reference to design designations in UL Fire Resistance Directory, for types of assemblies in which drywall ceilings function as a fire protective membrane and tested per ASTM E 119. Installation in accordance with the UL Design being referenced.

### D. Coordination of Work:

- 1. Coordinate drywall furring work with installers of related work including, but not limited to acoustical ceilings, building insulation, gypsum board, light fixtures, mechanical systems, electrical systems, and sprinklers.
- All work above the ceiling line should be completed prior to installing the drywall sheet goods.
  There should be no materials resting against or wrapped around the suspension system, hanger
  wires or ties.

# 1.06 DELIVERY, STORAGE, AND HANDLING

A. Deliver materials to project site in original, unopened packages and store them in a fully enclosed space where they will be protected against damage from moisture, direct sunlight, surface contamination, and other causes.

#### 1.07 WARRANTY

- A. Suspensions System: Submit a written limited warranty executed by the manufacturer, agreeing to repair or replace grid components that are supplied with a hot-dipped galvanized coating or aluminum base material. Failures include, but are not limited to: The occurrence of 50% red rust as defined by ASTM D 610 test procedures as a result of defects in materials or factory workmanship.
- B. Warranty Period of Grid: Ten years from date of installation.
- C. The Warranty shall not deprive the Owner of other rights the Owner may have under other provisions of the Contract Documents and will be in addition to and run concurrent with other warranties made by the Contractor under the requirements of the Contract Documents.

# **PART 2 - PRODUCTS**

### 2.01 MANUFACTURERS

- A. Suspension Systems Basis-of-Design:
  - 1. Armstrong World Industries, Inc.; FrameAll Flat Drywall Grid, flat suspension system.
- B. Soffit Framing Systems Basis-of-Design:
  - 1. Armstrong World Industries, Inc.; SimpleSoffit, drywall soffit framing system.
- C. Other acceptable manufacturers include, but are not limited to, the following:
  - 1. Armstrong World Industries, Inc.
  - 2. USG Corporation
  - 3. Certainteed Architectural

### 2.02 SUSPENSION SYSTEMS

- A. Structural Classification:
  - 1. Main Beam shall be heavy duty per ASTM C 635.
  - 2. Classification can require wires to be closer together for additional loading when used to support double layer gypsum, verticals, slopes, circles, soffits, canopies, and step conditions which call for loading or unusual designs and shapes in drywall construction.
  - 3. Deflection of fastening suspension system supporting light fixtures, ceiling grilles, access doors, verticals and horizontal loads shall have a maximum deflection of 1/360 of the span.

# B. Components:

- 1. SimpleSoffit Main Beam: Shall be double-web construction (minimum 0.0179 inch prior to protective coating, ASTM C645), hot dipped galvanized (per ASTM A653).
  - a. L Soffit up, 1-1/4 inch web height, 1-1/2 inch flange, custom length, custom routes (up to 7 routes).

- FrameAll Main Beam: Shall meet ASTM A653 for zinc-coated hop dipped galvanized steel.
   Surfaces are chemically cleansed, sinc-coated, and prefinished. Materials shall conform to ASTM C645 and ASTM C635 performance standards.
  - a. Web height 1-11/16 inch.
  - b. Field verify length needed.
- 3. Drywall Grid Cross Tees: Shall be double-web steel construction (minimum 0.0179 inch prior to protective coating, ASTM C645), hot dipped galvanized (minimum G40 or G90 per ASTM A653).
  - a. Web height 1-1/2 inch with PeakForm bulb and pre-finished 1-1/2 inch knurled flange.
  - b. Field verify length needed.
- 4. Support Hanger
  - a. SB12P: Strong Back Support Hanger
  - b. Channel beam splice used to suspend main beams to 1-1/2 inch black iron carrying channels.
    - 1) Field verify length needed.
- 5. Clips and Accessories
  - a. DW90C: 90 Degree Drywall Angle Clip
- 6. Metal Edge Transition Trim for Suspension Systems: Steel or extruded aluminum; provide attachment clips, splice plates, and preformed corner pieces for complete trim system.
  - a. Trim Height: 8 inches
  - b. Finish: Baked enamel
  - c. Color: As selected by Architect from manufacturer's standard range.
  - d. Basis-of-Design Products:
    - 1) Armstrong World Industries, Inc.; Axiom Transitions, AXTR8STR.
    - 2) Armstrong World Industries, Inc.; Axiom Transitions, AXTR8QSIS.
  - e. For transitions with no change in elevation, see Section 095100 for flush transition trim.

### **PART 3 - EXECUTION**

# 3.01 INSTALLATION - GENERAL

- A. Install suspension system and panels in accordance with the manufacturer's instructions, in compliance with ASTM installation standard, and with applicable codes as required by the authorities having jurisdiction.
- B. To secure to metal clips, concrete inserts, steel bar joist or steel deck, use power actuated fastener, or insert. Coordinate placement for hanger wire spaced as required for expected ceiling loads and layout.
- C. Install hanger wire as required with necessary on center spacing to support expected ceiling load requirements, following local practices, codes and regulations. Provide additional wires at light fixtures, grilles, and access doors where necessary. A pigtail knot shall be used with three tight wraps at top and bottom fastening locations.
- D. Add additional wire as needed when using compatible clips and accessories.
- E. Control Joints: Roll formed zinc alloy, aluminum, or plastic as required for expansion and contraction as shown on drawings.
- F. Expansion Joints: Roll formed zinc alloy, aluminum, or plastic as required for expansion and contraction as shown on drawings.
- G. Main beams shall be suspended from the overhead construction with hanger wire, spaced as required for expected ceiling loads, along the length of the main beams.
- H. Install cross tees at on center spacing as specified by the drywall manufacturer. Typical drywall cross tee spacing:
  - 1. 16 inches on center with 5/8 or 1/2 inch gypsum board
- I. Other items such as wood, sheet metal, or plastic panels should be screwed to comply with deflection limit equivalent to that of the ceiling installation.
- J. Use channel molding or angle molding to interface with Drywall Grid System to provide perimeter attachment or to obtain drop soffits, verticals, slopes, etc.

- K. To suspend a second ceiling beneath a new or existing drywall ceiling, without breaching the integrity of the upper ceiling, use the Drywall Clip. To form a transition from a drywall ceiling to an acoustical ceiling, use the Drywall Transition Clips spaced as required for expected loads.
- L. For light fixtures (Type G, Type F) use secondary framing cross tees as required to frame opening.
- M. Single cross tees in a route hole to be secured by 7/16 inch framing screw or alternative methods.

# SECTION 093000 TILING

# PART 1 GENERAL

# 1.01 SECTION INCLUDES

- A. Tile for floor applications.
- B. Non-ceramic trim.

#### 1.02 REFERENCE STANDARDS

- A. ANSI A108/A118/A136 American National Standard Specifications for the Installation of Ceramic Tile (Compendium); 2019.
- B. ANSI A108.1a American National Standard Specifications for Installation of Ceramic Tile in the Wet-Set Method, with Portland Cement Mortar; 2023.
- C. ANSI A108.1b Installation of Ceramic Tile on a Cured Portland Cement Mortar Setting Bed with Dry-Set, Modified Dry-Set, or Improved Modified Dry-Set Cement Mortar; 2023.
- D. ANSI A108.1c Contractor's Option: Installation of Ceramic Tile in the Wet-Set Method with Portland Cement Mortar or Installation of Ceramic Tile on a Cured Portland Cement Mortar Setting Bed with Dry-Set, Modified Dry-Set, or Improved Modified Dry-Set Cement Mortar; 2023.
- E. ANSI A108.2 American National Standard General Requirements: Materials, Environmental and Workmanship; 2019.
- F. ANSI A108.4 American National Standard Specifications for Installation of Ceramic Tile with Organic Adhesive or Water Cleanable Tile-Setting Epoxy Adhesive; 2023.
- G. ANSI A108.5 Setting of Ceramic Tile with Dry-Set Cement Mortar, Modified Dry-Set Cement Mortar, EGP (Exterior Glue Plywood) Modified Dry-Set Cement Mortar, or Improved Modified Dry-Set Cement Mortar; 2023.
- H. ANSI A108.6 American National Standard Specifications for Installation of Ceramic Tile with Chemical Resistant, Water Cleanable Tile-Setting and -Grout Epoxy; 2023.
- I. ANSI A108.8 American National Standard Specifications for Installation of Ceramic Tile with Chemical Resistant Furan Resin Mortar and Grout; 1999 (Reaffirmed 2019).
- J. ANSI A108.9 American National Standard Specifications for Installation of Ceramic Tile with Modified Epoxy Emulsion Mortar/Grout; 2023.
- K. ANSI A108.10 American National Standard Specifications for Installation of Grout in Tilework; 2017 (Reaffirmed 2022).
- L. ANSI A108.12 Installation of Ceramic Tile with EGP (Exterior Glue Plywood) Modified Dry-Set Mortar; 2023.
- M. ANSI A108.13 American National Standard for Installation of Load Bearing, Bonded, Waterproof Membranes for Thin-Set Ceramic Tile and Dimension Stone; 2005 (Reaffirmed 2021).
- N. ANSI A108.19 American National Standard Specifications for Interior Installation of Gauged Porcelain Tiles and Gauged Porcelain Tile Panels/Slabs by the Thin-Bed Method Bonded with Modified Dry-Set Cement Mortar or Improved Modified Dry-Set Cement Mortar; 2020.
- O. ANSI A108.20 American National Standard Specifications for Exterior Installation of Gauged Porcelain Tiles and Gauged Porcelain Tile Panels/Slabs; 2020.
- P. ANSI A118.3 American National Standard Specifications for Chemical Resistant, Water Cleanable Tile-Setting and -Grouting Epoxy and Water Cleanable Tile-Setting Epoxy Adhesive; 2021.
- Q. ANSI A118.10 American National Standard Specifications for Load Bearing, Bonded, Waterproof Membranes for Thin-Set Ceramic Tile and Dimension Stone Installation; 2023.

- R. ANSI A118.12 American National Standard Specifications for Crack Isolation Membranes for Thin-Set Ceramic Tile and Dimension Stone Installation; 2014 (Reaffirmed 2019).
- S. ANSI A118.13 American National Standard Specification for Bonded Sound Reduction Membranes for Thin-Set Ceramic Tile Installation; 2014 (Reaffirmed 2019).
- T. ANSI A137.1 American National Standard Specifications for Ceramic Tile; 2022.
- U. ASTM C373 Standard Test Methods for Determination of Water Absorption and Associated Properties by Vacuum Method for Pressed Ceramic Tiles and Glass Tiles and Boil Method for Extruded Ceramic Tiles and Non-tile Fired Ceramic Whiteware Products; 2018 (Reapproved 2023).
- V. ASTM E492 Standard Test Method for Laboratory Measurement of Impact Sound Transmission through Floor-Ceiling Assemblies Using the Tapping Machine; 2022.
- W. ASTM E2179 Standard Test Method for Laboratory Measurement of the Effectiveness of Floor Coverings in Reducing Impact Sound Transmission Through Concrete Floors; 2021.
- X. ASTM F710 Standard Practice for Preparing Concrete Floors to Receive Resilient Flooring; 2022.
- Y. ASTM F1869 Standard Test Method for Measuring Moisture Vapor Emission Rate of Concrete Subfloor Using Anhydrous Calcium Chloride; 2023.
- Z. ASTM F2170 Standard Test Method for Determining Relative Humidity in Concrete Floor Slabs Using in situ Probes; 2019a.
- AA. ICC-ES AC380 Acceptance Criteria for Termite Physical Barrier Systems; 2021, with Editorial Revision (2022).
- BB. TCNA (HB) Handbook for Ceramic, Glass, and Stone Tile Installation; 2024.
- CC. TCNA (HB-GP) Handbook for Gauged Porcelain Tiles and Gauged Porcelain Tile Panels/Slabs Installation; 2023.

# 1.03 SUBMITTALS

- A. See Section 013300 Submittals, for submittal procedures.
- B. Product Data: Provide manufacturers' data sheets on tile, mortar, grout, and accessories. Include instructions for using grouts and adhesives.
- C. Samples: Mount tile and apply grout on two plywood panels, minimum 18 by 18 inches in size illustrating pattern, color variations, and grout joint size variations.
- D. Manufacturer's Certificate: Certify that products meet or exceed specified requirements.
- E. Installer's Qualification Statement:
  - Submit documentation of National Tile Contractors Association (NTCA) or Tile Contractors' Association of America (TCAA) accreditation.
  - 2. Submit documentation of completion of apprenticeship and certification programs.
- F. Maintenance Data: Include recommended cleaning methods, cleaning materials, and stain removal methods.
- G. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
  - 1. Extra Tile: 1 percent of each size, color, and surface finish combination.

# 1.04 QUALITY ASSURANCE

- A. Installer Qualifications:
  - 1. Company specializing in performing tile installation, with minimum of five years of documented experience.
    - a. Accredited Five-Star member of the National Tile Contractors Association (NTCA) or Trowel of Excellence member of the Tile Contractors' Association of America (TCAA).
  - 2. Installer Certification:
    - a. Ceramic Tile Education Foundation (CTEF): Certified Tile Installer (CTI).

- b. Apprenticeship Program: Installer has achieved Journeyworker status through an apprenticeship from the International Union of Bricklayers and Allied Craftworkers (IUBAC) or a U.S. Department of Labor (DOL)-recognized program.
- c. Advanced Certifications for Tile Installers (ACT): Certification in the installation of membranes, mortar bed (mud) floors, mortar (mud) walls, shower receptors, large format tile, gauged porcelain tile/panels/slabs, and grouts.
- d. International Masonry Training and Education Foundation (IMTEF): Supervisor Certification Program (SCP).

# 1.05 DELIVERY, STORAGE, AND HANDLING

A. Protect adhesives from freezing or overheating in accordance with manufacturer's instructions.

### 1.06 FIELD CONDITIONS

- A. Do not install solvent-based products in an unventilated environment.
- B. Maintain ambient and substrate temperature above 50 degrees F and below 100 degrees F during installation and curing of setting materials.

### **PART 2 PRODUCTS**

#### 2.01 TILE

- A. Manufacturers:
  - 1. American Olean Corporation
  - 2. Dal-Tile Corporation
  - 3. Mohawk Industries
- B. Glazed Porcelain Tile (CT1): ANSI A137.1 standard grade.
  - 1. Moisture Absorption: 0 to 0.5 percent as tested in accordance with ASTM C373.
  - 2. Size: 12 by 24 inch, nominal.
  - 3. Thickness: 5/16 inch.
  - 4. Surface Finish: Matte glazed.
  - 5. Color(s): Feature Beige AR07.
  - 6. Basis-of-Design Product:
    - a. Dal-Tile Corporation; Articulo.

### 2.02 TRIM AND ACCESSORIES

- A. Non-Ceramic Trim: Satin natural anodized extruded aluminum, style and dimensions to suit application and as approved by Architect, set with tile mortar or adhesive.
  - 1. Applications:
    - a. Transition between floor finishes of different heights.
    - b. Borders and other trim as indicated on drawings.

# 2.03 SETTING MATERIALS

- A. Provide setting and grout materials from same manufacturer.
- B. Manufacturers:
  - 1. Custom Building Products
  - 2. H.B. Fuller Construction Products, Inc
  - 3. Mapei Corporation
- C. Epoxy Adhesive and Mortar Bond Coat: ANSI A118.3.

# 2.04 GROUTS

- A. Provide setting and grout materials from same manufacturer.
- B. Manufacturers:
  - 1. Custom Building Products
  - 2. H.B. Fuller Construction Products, Inc

- 3. Mapei Corporation
- 4.
- C. Epoxy Grout: ANSI A118.3 chemical resistant and water-cleanable epoxy grout.
  - 1. Applications: Ceramic floor tiling.
  - 2. Color(s): As selected by Architect from manufacturer's full line.

### 2.05 ACCESSORY MATERIALS

- A. Concrete Floor Slab Crack Isolation Membrane: Material complying with ANSI A118.12; not intended as waterproofing.
  - 1. Crack Resistance: No failure at 1/8 inch gap, minimum.
  - 2. Fluid or Trowel Applied Type:
    - a. Material: Synthetic rubber or Acrylic.
    - b. Thickness: 20 mils, maximum.
- B. Waterproofing Membrane at Floors: Specifically designed for bonding to cementitious substrate under thick mortar bed or thin-set tile; complying with ANSI A118.10.
  - 1. Crack Resistance: No failure at 1/16 inch gap, minimum; comply with ANSI A118.12.
  - 2. Fluid or Trowel Applied Type:
    - a. Material: Synthetic rubber or Acrylic.
    - b. Thickness: 25 mils, minimum, dry film thickness.
- C. Tile Underlayment: Specifically designed for bonding to thin-set setting mortar; not primarily waterproofing material and having the following characteristics:
  - 1. Sound Reduction: Comply with ANSI A118.13, ASTM E492, and ASTM E2179.
  - 2. Crack Resistance: No failure at 1/16-inch gap, minimum; comply with ANSI A118.12.
  - 3. Water Resistance: Comply with ANSI A118.10, bonded waterproofing.
  - 4. Termite Resistance: 100 percent when tested in accordance with ICC-ES AC380.
  - 5. Type: Fluid or trowel applied.

### PART 3 EXECUTION

### 3.01 EXAMINATION

- A. Verify that subfloor surfaces are smooth and flat within the tolerances specified for that type of work and are ready to receive tile.
- B. Verify that subfloor surfaces are dust free and free of substances that could impair bonding of setting materials to subfloor surfaces.
- C. Cementitious Subfloor Surfaces: Verify that substrates are ready for tiling installation by testing for moisture and alkalinity (pH).
  - 1. Test as Follows:
    - a. Alkalinity (pH): ASTM F710.
    - b. Internal Relative Humidity: ASTM F2170.
    - c. Moisture Vapor Emission: ASTM F1869.
  - 2. Obtain instructions if test results are not within limits recommended by tiling material manufacturer and setting material manufacturer.

# 3.02 PREPARATION

- A. Protect surrounding work from damage.
- B. Vacuum clean surfaces and damp clean.
- C. Seal substrate surface cracks with filler. Level existing substrate surfaces to acceptable flatness tolerances.

# 3.03 INSTALLATION - GENERAL

- A. Install tile, thresholds, and stair treads and grout in accordance with applicable requirements of ANSI A108.1a through ANSI A108.20, manufacturer's instructions, and TCNA (HB) or TCNA (HB-GP) recommendations, as applicable.
- B. Lay tile to pattern indicated. Do not interrupt tile pattern through openings.
- C. Cut and fit tile to penetrations through tile, leaving sealant joint space. Form corners and bases neatly. Align floor joints.
- D. Place tile joints uniform in width, subject to variance in tolerance allowed in tile size. Make grout joints without voids, cracks, excess mortar or excess grout, or too little grout.
- E. Form internal angles square and external angles bullnosed.
- F. Install non-ceramic trim in accordance with manufacturer's instructions.
- G. Install thresholds where indicated.
- H. Sound tile after setting. Replace hollow sounding units.
- I. Keep control and expansion joints free of mortar, grout, and adhesive.
- J. Prior to grouting, allow installation to completely cure; minimum of 48 hours.
- K. Grout tile joints unless otherwise indicated.
- L. At changes in plane and tile-to-tile control joints, use tile sealant instead of grout, with either bond breaker tape or backer rod as appropriate to prevent three-sided bonding.

# 3.04 CLEANING

A. Clean tile and grout surfaces.

### 3.05 PROTECTION

A. Do not permit traffic over finished floor surface for 4 days after installation.

# SECTION 095100 ACOUSTICAL CEILINGS

# PART 1 GENERAL

# 1.01 SECTION INCLUDES

- Suspended metal grid ceiling system.
- B. Acoustical units.

### 1.02 REFERENCE STANDARDS

- A. ASTM C635/C635M Standard Specification for Manufacture, Performance, and Testing of Metal Suspension Systems for Acoustical Tile and Lay-in Panel Ceilings; 2022.
- B. ASTM C636/C636M Standard Practice for Installation of Metal Ceiling Suspension Systems for Acoustical Tile and Lay-In Panels; 2019.
- C. ASTM E580/E580M Standard Practice for Installation of Ceiling Suspension Systems for Acoustical Tile and Lay-in Panels in Areas Subject to Earthquake Ground Motions; 2022.
- D. ASTM E1264 Standard Classification for Acoustical Ceiling Products; 2023.

# 1.03 SUBMITTALS

- A. See Section 013300 Submittals, for submittal procedures.
- B. Product Data: Provide data on suspension system components and acoustical units.
- C. Samples: Submit two samples 4 by 4 inch in size illustrating material and finish of acoustical units.
- D. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
  - 1. Extra Acoustical Units: Quantity equal to 5 percent of total installed.

### 1.04 QUALITY ASSURANCE

- A. Suspension System Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum three years documented experience.
- B. Acoustical Unit Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum three years documented experience.

# 1.05 FIELD CONDITIONS

A. Maintain uniform temperature of minimum 60 degrees F, and maximum humidity of 40 percent prior to, during, and after acoustical unit installation.

# PART 2 PRODUCTS

# 2.01 MANUFACTURERS

- A. Acoustic Tiles/Panels:
  - 1. Armstrong World Industries, Inc
  - 2. Certainteed Architectural
  - 3. USG Corporation
- B. Suspension Systems:
  - 1. Armstrong World Industries, Inc
  - 2. Certainteed Architectural
  - 3. USG Corporation

# 2.02 ACOUSTICAL UNITS

- A. Acoustical Panels: Mineral fiber with membrane-faced overlay, with the following characteristics:
  - 1. Classification: ASTM E1264 Type IV.
    - a. Form: 2, water felted.
    - b. Pattern: "E" lightly textured.
  - 2. Size: 24 by 24 inches.

### **Acoustical Ceilings**

- 3. Thickness: 1 inch.
- 4. Light Reflectance: 0.85, determined in accordance with ASTM E1264.
- 5. Noise Reduction Coefficient (NRC): 0.85, determined in accordance with ASTM E1264.
- 6. Articulation Class (AC): 170, determined in accordance with ASTM E1264.
- 7. Ceiling Attenuation Class (CAC): 35, determined in accordance with ASTM E1264.
- 8. Flame Spread: ASTM E1264; Class A.
- 9. Panel Edge: Square.
- 10. Color: White.
- 11. Suspension System: Exposed grid.
- 12. Basis-of-Design Product:
  - a. Armstrong World Industries, Inc; Calla.

# 2.03 SUSPENSION SYSTEM(S)

- A. Metal Suspension Systems General: Complying with ASTM C635/C635M; die cut and interlocking components, with perimeter moldings, hold down clips, stabilizer bars, clips, and splices as required.
- B. Exposed Suspension System: Hot-dipped galvanized steel grid with steel cap.
  - 1. Structural Classification: Intermediate-duty, when tested in accordance with ASTM C635/C635M.
  - 2. Profile: Tee; 15/16 inch face width.
  - 3. Finish: Baked enamel.
  - 4. Color: White.
  - 5. Basis-of-Design Product:
    - a. Armstrong World Industries, Inc; Prelude XL #7300.

# 2.04 ACCESSORIES

- A. Support Channels and Hangers: Galvanized steel; size and type to suit application, seismic requirements, and ceiling system flatness requirement specified.
- B. Hanger Wire: 12 gauge, 0.08 inch galvanized steel wire.
- C. Hold-Down Clips: Manufacturer's standard clips to suit application.
- D. Perimeter Moldings: Same metal and finish as grid.
- E. Metal Edge Transition Trim for Suspension Systems: Steel or extruded aluminum; provide attachment clips, splice plates, and preformed corner pieces for complete trim system.
  - 1. Trim Height: Flush.
  - 2. Finish: Baked enamel.
  - 3. Color: White.
  - 4. Basis-of-Design Product:
    - a. Armstrong World Industries, Inc.; Axiom Transitions, AXTR7904STR.
  - 5. For transitions with elevation change, see Section 092226.23 for transition trim.
  - Touch-up Paint: Type and color to match acoustical and grid units.

# PART 3 EXECUTION

# 3.01 EXAMINATION

- A. Verify existing conditions before starting work.
- B. Verify that layout of hangers will not interfere with other work.

# 3.02 PREPARATION

- A. Install after major above-ceiling work is complete.
- B. Coordinate the location of hangers with other work.

# 3.03 INSTALLATION - SUSPENSION SYSTEM

A. Install suspension system in accordance with ASTM C636/C636M, ASTM E580/E580M, and manufacturer's instructions and as supplemented in this section.

### **Acoustical Ceilings**

- B. Rigidly secure system, including integral mechanical and electrical components, for maximum deflection of 1:360.
- C. Locate system on room axis according to reflected plan.
- D. Perimeter Molding: Install at intersection of ceiling and vertical surfaces and at junctions with other interruptions.
  - Use longest practical lengths.
- E. Suspension System, Non-Seismic: Hang suspension system independent of walls, columns, ducts, pipes and conduit. Where carrying members are spliced, avoid visible displacement of face plane of adjacent members.
- F. Where ducts or other equipment prevent the regular spacing of hangers, reinforce the nearest affected hangers and related carrying channels to span the extra distance.
- G. Do not support components on main runners or cross runners if weight causes total dead load to exceed deflection capability.
- H. Support fixture loads using supplementary hangers located within 6 inches of each corner, or support components independently.
- I. Do not eccentrically load system or induce rotation of runners.

### 3.04 INSTALLATION - ACOUSTICAL UNITS

- A. Install acoustical units in accordance with manufacturer's instructions.
- B. Fit acoustical units in place, free from damaged edges or other defects detrimental to appearance and function.
- C. Fit border trim neatly against abutting surfaces.
- D. Install acoustical units level, in uniform plane, and free from twist, warp, and dents.
- E. Cutting Acoustical Units:
  - 1. Make field cut edges of same profile as factory edges.

# 3.05 TOLERANCES

- A. Maximum Variation from Flat and Level Surface: 1/8 inch in 10 feet.
- B. Maximum Variation from Plumb of Grid Members Caused by Eccentric Loads: 2 degrees.

### 3.06 CLEANING

- A. Clean surfaces.
- B. Replace damaged or abraded components.

# SECTION 096500 RESILIENT FLOORING

# PART 1 GENERAL

### 1.01 SECTION INCLUDES

- A. Resilient base.
- B. Resilient stair accessories.
- C. Installation accessories.

### 1.02 REFERENCE STANDARDS

- A. ASTM F1861 Standard Specification for Resilient Wall Base; 2021.
- B. ASTM F2169 Standard Specification for Resilient Stair Treads; 2015 (Reapproved 2020).

# 1.03 SUBMITTALS

- A. See Section 013300 Submittals, for submittal procedures.
- B. Product Data: Provide data on specified products, describing physical and performance characteristics; including sizes, patterns and colors available; and installation instructions.
- C. Selection Samples: Submit manufacturer's complete set of color samples for Architect's initial selection.
- D. Product Schedule: For resilient base and accessory products. Use same designations indicated on Drawings.
- E. Installer's Qualification Statement.
- F. Maintenance Data: Include maintenance procedures, recommended maintenance materials, and suggested schedule for cleaning, stripping, and re-waxing.
- G. Maintenance Materials: Furnish extra materials, from the same product run, that match products installed and that are packaged with protective covering for stroage and identified with labels describing contents.
  - 1. Extra Wall Base: Furnish not less than 10 linear feet for every 500 linear feet or fraction thereof, of each type, color, pattern, and size of resilient product installed.
  - 2. Extra Stair Materials: Quantity equivalent to 5 percent of each type and color.

# 1.04 QUALITY ASSURANCE

- A. Installer Qualifications: A qualified installer who employs workers for this project who are competent in techniques required by manufacturer for floor tile installation and seaming method indicated.
  - 1. Engage an installer who employs workers for this Project who are trained or certified by floor tile manufacturer for installtion techniques required.

# 1.05 DELIVERY, STORAGE, AND HANDLING

- A. Upon receipt, immediately remove any shrink-wrap and check materials for damage and the correct style, color, quantity and run numbers.
- B. Store all materials off of the floor in an acclimatized, weather-tight space.
- C. Maintain temperature in storage area between 70 degrees F and 85 degrees F.
- D. Protect roll materials from damage by storing on end.
- E. Do not double stack pallets.

### 1.06 FIELD CONDITIONS

- A. Maintain ambient temperatures within range recommended by manufacturer, but no less than 75 degrees F or more than 85 degrees F in spaces to receive floor tile during the following time periods:
  - 1. 48 hours before installation.
  - 2. During installation.
  - 3. 48 hours after installation.

### **Resilient Flooring**

- B. After installation and until Substantial Completion, maintain ambient temperatures within range recommended by manufacturer, but not less than 70 degrees F or more than 85 degrees F.
- C. Install floor tile after other finishing operations, including painting, have been completed.

#### PART 2 PRODUCTS

### 2.01 STAIR COVERING

- A. Stair Treads: Rubber; full width and depth of stair tread in one piece; tapered thickness.
  - 1. Manufacturers:
    - a. Johnsonite, a Tarkett Company
    - b. Roppe Corporation
    - c. Nora by Interface
  - 2. Basis-of-Design Product:
    - a. Nora by Interface; Norament 926 Arago.
  - 3. Minimum Requirements: Comply with ASTM F2169, Type TS, Class 2, Group 1 and/or 2, Grade 2, rubber, vulcanized thermoset.
  - 4. Thickness: 5 mm.
  - 5. Nosing: Square.
  - 6. Color: To be selected by Architect from manufacturer's full range.

### 2.02 RESILIENT BASE

- A. Resilient Base: ASTM F1861, Type TV, vinyl, thermoplastic; style as scheduled.
  - 1. Manufacturers:
    - a. Flexco Corporation; Base Sculptures
    - b. Johnsonite, a Tarkett Company; Johnsonite Traditional Vinyl 1/8"
    - c. Mohawk Group; Elemental Edges
  - 2. Group: I (Solid, homogeneous).
  - 3. Style and Location:
    - a. Style A, Straight: Provide in areas with carpet.
  - 4. Height: 4 inches.
  - 5. Thickness: 0.125 inch.
  - 6. Length: 4 foot sections or coils in manufacturer's standard length.
  - 7. Color: To be selected by Architect from manufacturer's full range.
  - 8. Accessories: Premolded or Job formed external corners and internal corners.

# 2.03 ACCESSORIES

- A. Adhesive for Vinyl and Rubber Flooring:
  - 1. Manufacturers:
    - a. H.B. Fuller Construction Products, Inc; TEC Flexera 2K PSA Hybrid Adhesive: www.tecspecialty.com/#sle.
    - b. H.B. Fuller Construction Products, Inc; TEC Flexera HT High Tack Premium Universal PSA Adhesive: www.tecspecialty.com/#sle.
    - c. Stauf USA, LLC; D737 High-Tack: www.staufusa.com/#sle.

# PART 3 EXECUTION

### 3.01 EXAMINATION

- A. Examine substrates, with Installer present, for compliance with requirements for maximum moisture content and other conditions indicated.
- B. Verify that surfaces are flat to tolerances acceptable to flooring manufacturer, free of cracks that might telegraph through flooring, clean, dry, and free of curing compounds, surface hardeners, and other chemicals that might interfere with bonding of flooring to substrate.

- C. Verify that wall surfaces are smooth and flat within the tolerances specified for that type of work, are dust-free, and are ready to receive resilient base.
- D. Cementitious Subfloor Surfaces: Verify that substrates are ready for resilient flooring installation by testing for moisture and alkalinity (pH).
- E. Proceed with installation only after unsatisfactory conditions have been corrected.
  - 1. Obtain instructions if test results are not within limits recommended by resilient flooring manufacturer and adhesive materials manufacturer.

# 3.02 PREPARATION

- A. Prepare substrates as recommended by resilient-product and adhesive manufacturers.
- B. Remove ridges and bumps. Fill minor low spots, cracks, joints, holes, and other defects with substrate filler to achieve smooth, flat, hard surface.
- C. Prohibit traffic until filler is fully cured.
- D. Do not install resilient products until materials are the same temperature as space where they are to be installed.
  - 1. At least 48 hours in advance of installation, move resilient products and installation materials into spaces where they will be installed.
- E. Immediately before installation, sweep and vacuum clean substrates to be covered by resilient products.

# 3.03 INSTALLATION - GENERAL

- A. Starting installation constitutes acceptance of substrate conditions.
- B. Install in accordance with manufacturer's written instructions.
- C. Trowelable Leveling and Patching Compounds: Latex-modified, Portland-cement-based or blended hydralic-cement-based formulation provided or approved by resilient-product manufacturer for applications indicated.
- D. Adhesives: Water-resistant type recommended by resilient -product manufacturer for resilient products and substrate conditions indicated.

### 3.04 INSTALLATION - STAIR TREADS

- A. Comply with manufacturer's written instructions for installing Stair Tread.
- B. At the time of installation and of adhesive bonding, the subfloor temperature must be 15 degrees C (59 degrees F) or above.

# 3.05 INSTALLATION - RESILIENT BASE

- A. Comply with manufacturer's written instructions for installing resilient base.
- B. Apply resilient base to walls, columns, pilasters, casework, and cabinetes in toe spaces, and other permanent fixtures in rooms and areas where base is required.
- C. Install resilient base in lengths as practical without gaps at seams and with tops of adjaceent pieces aligned.
- D. Tightly ahere resilient base to substrate throughout length of each piece, with base in continuous contact with horizontal and vertical substrates.
- E. Do not stretch resilient base during installation.
- F. On masonry surfaces or other similar irregular substrates, fill voids along top edge of resilient base with manufacturer's recommended adhesive filler material.
- G. Job-formed Corners:
  - 1. Outside corners: use straight pieces of maximum lengths possible and form with return not less than 6 inches in length.
    - a. Form without producing discoloration (whitening) at bends.

- 2. Inside Corners: Use straight pieces of maximum lengths possible and form with returns not less than 6 inches in length.
  - a. Miter or cope corners to minimize open joints.

### 3.06 RESILIENT ACCESSORY INSTALLATION

- A. Comply with manufacturer's written instructions for installing resilient accessories.
- B. Resilient Molding Acessories: Butt to adjacent materials and tightly adhere to substrates throughtout length of each piece. Install reducer strips at edges of floor covering that would otherwise be exposed.
- C. Fit joints tightly and make vertical. Maintain minimum dimension of 18 inches between joints.
- D. Install base on solid backing. Bond tightly to wall and floor surfaces.
- E. Installation Stair Coverings
  - 1. Adhere over entire surface. Fit accurately and securely.

# 3.07 CLEANING AND PROTECTION

- A. Comply with manufacturer's written instructions for cleaning and protecting resilient products.
- B. Perform the following operations immediately after completing resilient-products installation
  - 1. Remove adhesive and other blemishes from surfaces.
  - 2. Sweep and vacuum horizontal surfaces thoroughly.
  - 3. Damp-mop horizontal surfaces to remove marks and soil.
- C. Protect resilient products from mars, marks, indentatations, and other damage from construction operations and placement of equipment and fixtures during remainder of construction period.
- D. Cover resilient products subject to wear and foot traffic until substatial completion.
- E. Remove excess adhesive from floor, base, and wall surfaces without damage.
- F. Clean in accordance with manufacturer's written instructions.
- G. PROTECTION
  - 1. Prohibit traffic on resilient flooring for 48 hours after installation.

# SECTION 096813 TILE CARPETING

# PART 1 GENERAL

# 1.01 RELATED DOCUMENTS

A. Appendix B "Tile Carpet Product Data"

### 1.02 SECTION INCLUDES

- A. Carpet tile, fully adhered.
- B. Removal of existing carpet tile.
- C. Walk off carpet tile.

# 1.03 COORDINATE

A. Coordinate location of electrical work in wire management channels with construction manager, owner to coordinate installation.

### 1.04 PREINSTALLATION MEETINGS

- A. Pre-installation Conference: Conduct conference at Project Site.
  - 1. Review methods and procedures related to carpet tile installation including, but not limited to, the following:
    - a. Review delivery, storage, and handling procedures.
    - b. Review ambient conditions and ventilation procedures.
    - c. Review subfloor preparation procedures.

### 1.05 SUBMITTALS

- A. Product Data: Provide data on specified products, describing physical and performance characteristics; sizes, patterns, colors available, and method of installation.
- B. Samples: Submit two walk off carpet tiles illustrating color and pattern design for each carpet color selected.
- C. Accessory Samples: Submit two 4 inch long samples of edge strip.
- D. Installer's Qualification Statement.
- E. Operation and Maintenance Data: Include maintenance procedures, recommended maintenance materials, and suggested schedule for cleaning.
- F. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
  - 1. Extra Walk Off Carpet Tiles: Quantity equal to 5 percent of total installed of each color and pattern installed.

### 1.06 QUALITY ASSURANCE

- A. Installer Qualifications: An expereienced installer who is certified by the International Certified Floorcovering Installers Association at the Commercial II certification level.
- B. Mockups: Build mockups to verify selections made under Sample submittals, to demonstrate aesthetic effects, and to set quality standards for fabrication and installation.

# 1.07 FIELD CONDITIONS

- A. Store materials in area of installation for minimum period of 24 hours prior to installation.
- B. Comply with the Carpet and Rug Institute's CRI 104 for temperature, humidity, and ventilation limitations.
- C. Environmental Limitations: Do not deliver or install carpet tiles until spaces are enclosed and weathertight, wet-work in spaces is complete and dry, including paint and ambient temperature and humidity conditions are maintained at levels planned for building occupants during the remainder of the construction period.

D. Where demountable partitions or other items are indicated for installation on top of carpet tiles, install carpet tiles before installing these items. If walls are already in place carpet tiles may be cut and laid tight to fit demountable partitions.

# **PART 2 PRODUCTS**

# 2.01 MATERIALS

- A. Carpet Tile (C1):
  - 1. Product: Owner provided. See Appendix A.
  - 2. Tile Size: 18 by 36 inch, nominal.
  - 3. Style: Knotted Tile 5T301
  - 4. Color: Silver 01535.
  - 5. Installation Method: Brick.
- B. Walk Off Carpet Tile (C2) Basis of Design: Shaw Contract; All Access, Portal Tile 5T035.
  - 1. Other Acceptable Manufacturers include the following:
    - a. Shaw Contract
    - b. Tarkett Company
    - c. Interface, Inc.
    - d. Mohawk Group
  - 2. Pattern/Style: As selected by Architect from manufacturer's full range.
  - 3. Color: As selected by Architect from manufacturer's standard pallette.
  - 4. Tile Size: 24 by 24 inch.
  - 5. Total Thickness: 0.275 inch.
  - 6. Construction: Multi-Level Pattern Loop.
  - 7. Gauge: 1/12 inch
  - 8. Stitches: 8.5 per inch.
  - 9. Tufted Weight: 28 oz/sq yd.
  - 10. Installation Method: Monolithic.

# 2.02 ACCESSORIES

- A. Edge Strips: Embossed aluminum, Mill finish color.
- B. Carpet Tile Adhesive:
  - 1. Product: Owner provided.
- C. Trowelable Leveling and Patching Compound:
  - 1. Type recommended by flooring material manufactuer.

### PART 3 EXECUTION

#### 3.01 EXAMINATION

- A. Verify that subfloor surfaces are smooth and flat within tolerances specified for that type of work and are ready to receive carpet tile if necessary level with trowelable leveling and patching compound.
- B. Verify that wall surfaces are smooth and flat within the tolerances specified for that type of work, are dust-free, and are ready to receive carpet tile.
- C. Verify that subfloor surfaces are dust-free and free of substances that could impair bonding of adhesive materials to subfloor surfaces or show through surface.
- D. Cementitious Subfloor Surfaces: Verify that substrates are ready for flooring installation by testing for moisture and alkalinity (pH).
  - 1. Obtain instructions if test results are not within limits recommended by flooring material manufacturer and adhesive materials manufacturer.
- E. Verify that required floor-mounted utilities are in correct location.
- F. Examine carpet tile for type, color, pattern, and potential defects.

G. Proceed with installation only after unsatisfactory conditions have been corrected.

# 3.02 PREPARATION

- A. General: Comply with the Carpet and Rug Institue's CRI 104 and with carpet tile manufacturer's written installation instructions for preparing substrates indicated to receive carpet tile.
- B. Remove existing carpet tile.
- C. Prepare floor substrates as recommended by flooring and adhesive manufacturers.
- D. Remove subfloor ridges and bumps. Fill minor or local low spots, cracks, joints, holes, and other defects with subfloor filler.
- E. Apply, trowel, and float filler to achieve smooth, flat, hard surface. Prohibit traffic until filler is cured.
- F. Complete an necessary subfloor prepartion, and vacuum subfloor to remove dust, dirt, and construction debris before beginning installation.

### 3.03 INSTALLATION

- A. General: Comply with the Carpet and Rug Institute's CRI 104, Section 10 "Carpet Tile," and with carpet tile manufacturer's written installation instructions.
- B. Starting installation constitutes acceptance of subfloor conditions.
- C. Install carpet tile in accordance with manufacturer's instructions,. Glue down; install every tile with full-spread, releasble, pressure-sensitive adhesive.
- D. Maintain dye-lot integrity. Do not mix dye lots in same area.
- E. Maintain pile-direction patterns as directed by Owner.
- F. Blend carpet from different cartons to ensure minimal variation in color match.
- G. Cut carpet tile clean. Fit carpet tight to intersection with vertical surfaces, permanent fixtures, and built-in furniture including cabinets, pipes, outlets, edging, thresholds, and nosings without gaps. Bind or seal cut edges as recommended by carpet tile manufacturers.
- H. Extend carpet tile into toe spaces, door reveals, closets, open-bottomed obstructions, removeable flanges, alcoves, and similar openings.
- I. Maintain reference markers, holes, and openings that are in place or marked for furture cutting by repeating on carpet tile as marked on subfloor. Use nonpermanent, nonstaining marking device.
- J. Install pattern parallel to walls and borders.
- K. Trim carpet tile neatly at walls and around interruptions.
- L. Complete installation of edge strips, concealing exposed edges.

# 3.04 CLEANING AND PROTECTION

- A. Perform the following operations immediately after installing carpet tile:
  - 1. Remove excess adhesive and other surface blemishes using cleaner recommended by carpet tile manufacturer without damage, from floor, base, and wall surfaces.
  - 2. Remove yarns that protrude from carpet tile surface.
  - 3. Clean and vacuum carpet surfaces using commercial machine with face-beater element.
- B. Protect installed carpet tile to comply with Carpet and Rug Institute's CRI 104, Section 13.7.
- C. Protect carpet tile against damage from construction operations and placement of equipment and fixtures during the remainder of construction period. Use protection methods indicated or recommended in writing by carpet tile manufacturer.

# SECTION 099123 INTERIOR PAINTING

# PART 1 GENERAL

### 1.01 SECTION INCLUDES

- A. Surface preparation.
- B. Field application of paints.
- Scope: Finish interior surfaces exposed to view, unless fully factory-finished and unless otherwise indicated.
- D. Do Not Paint or Finish the Following Items:
  - 1. Items factory-finished unless otherwise indicated; materials and products having factory-applied primers are not considered factory finished.
  - 2. Items indicated to receive other finishes.
  - 3. Items indicated to remain unfinished.
  - 4. Fire rating labels, equipment serial number and capacity labels, bar code labels, and operating parts of equipment.
  - 5. Floors, unless specifically indicated.
  - 6. Glass.
  - 7. Concealed pipes, ducts, and conduits.

# 1.02 REFERENCE STANDARDS

- A. 40 CFR 59, Subpart D National Volatile Organic Compound Emission Standards for Architectural Coatings; U.S. Environmental Protection Agency; Current Edition.
- B. ASTM D4442 Standard Test Methods for Direct Moisture Content Measurement of Wood and Wood-Based Materials; 2020.
- C. MPI (APSM) Master Painters Institute Architectural Painting Specification Manual; Current Edition.
- D. SSPC-SP 1 Solvent Cleaning; 2015, with Editorial Revision (2016).
- E. SSPC-SP 2 Hand Tool Cleaning; 2018.
- F. SSPC-SP 6/NACE No.3 Commercial Blast Cleaning; 2006.

### 1.03 SUBMITTALS

- A. See Section 013300 Submittals, for submittal procedures.
- B. Product Data: Provide complete list of products to be used, with the following information for each:
  - Manufacturer's name, product name and/or catalog number, and general product category (e.g., "alkyd enamel").
  - 2. MPI product number (e.g., MPI #47).
  - Cross-reference to specified paint system products to be used in project; include description of each system.
  - 4. Manufacturer's installation instructions.
- C. Samples: For each type of topcoat product.
- D. Samples for Initial Selection: For each type of paint system and each color and gloss of topcoat.
  - 1. Submit samples on rigid backing, 8 inches square.
  - 2. Apply coats on samples in steps to show each coat required for system.
  - 3. Label each coat of each sample.
  - 4. Label each sample for location and application area.
- E. Product Schedule: Use same designations indicated on Drawings and in the Interior Painting Schedule to cross-reference paint systems specificed in this Section. Include color designations.
- F. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.

- 1. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
- 2. Extra Paint and Finish Materials: 5 percent, but not less than 1 gal of each color/material; from the same product run, store where directed.
- 3. Label each container with color in addition to the manufacturer's label.

### 1.04 QUALITY ASSURANCE

A. Manufacturer Qualifications: Company specializing in manufacturing the products specified, with minimum three years documented experience.

### 1.05 MOCK-UP

- A. Apply mockups of each paint system indicated and each color and finish selected to verify preliminary selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.
  - 1. Designer will select one surface to represent surfaces and conditions for application of each paint system.
    - a. Vertical and Horizontal Surfaces: provide samples of at least 9 sq. ft..
    - b. Other items: Designer will designate items or areas required.
  - 2. Final approval of color selections will be based on mockups.
    - a. If preliminary color selections are not approved, apply additional mockups of additional colors selected by Designer at no added cost to Owner.
  - 3. Approval of mockups does not consitiue approval of deviations from the Contract Documents contained mockups unless Designer specifically approves such deviations in writing.
  - 4. Subject to compliance with requirements, approved mockups may become part of the completed Work if undistribed at time of Substantial Completion.

# 1.06 DELIVERY, STORAGE, AND HANDLING

- A. Deliver products to site in sealed and labeled containers; inspect to verify acceptability.
- B. Container Label: Include manufacturer's name, type of paint, brand name, lot number, brand code, coverage, surface preparation, drying time, cleanup requirements, color designation, and instructions for mixing and reducing.
- C. Paint Materials: Store at minimum ambient temperature of 45 degrees F and a maximum of 90 degrees F, in ventilated area, and as required by manufacturer's instructions.
  - 1. Maintain containers in clean condition, free of foreign materials and residue.
  - 2. Remove rags and waste from storage area daily.

### 1.07 FIELD CONDITIONS

- A. Do not apply materials when surface and ambient temperatures are outside the temperature ranges required by the paint product manufacturer.
- B. Follow manufacturer's recommended procedures for producing best results, including testing of substrates, moisture in substrates, and humidity and temperature limitations.
- C. Minimum Application Temperatures for Paints: 50 degrees F for interiors unless required otherwise by manufacturer's instructions.
- D. Provide lighting level of 80 fc measured mid-height at substrate surface.

# **PART 2 PRODUCTS**

# 2.01 MANUFACTURERS

- A. Paint P Sole Source Manufacturer:
  - 1. PPG Paints
- B. Provide paints and finishes from the same manufacturer to the greatest extent possible.
- C. Paint PT:
  - 1. Sherwin-Williams Company.

- 2. Behr Paint Company
- 3. PPG Paints

# D. Material Compatibility:

- 1. Materials for use within each paint system shall be compatible with one another and substrates indicated, under conditions of service and application as demostrated by manufacturer, based on testing and field experience.
- 2. For each coat in a paint system, products shall be recommended in writing by topcoat manufacturers for use in paint system and on substrate indicated.
- E. Colors: As selected by Designer from manufacturer's full range.

### 2.02 PAINTS AND FINISHES - GENERAL

- A. Paints and Finishes: Ready-mixed, unless intended to be a field-catalyzed paint.
  - 1. Provide paints and finishes of a soft paste consistency, capable of being readily and uniformly dispersed to a homogeneous coating, with good flow and brushing properties, and capable of drying or curing free of streaks or sags.
  - 2. Supply each paint material in quantity required to complete entire project's work from a single production run.
  - 3. Do not reduce, thin, or dilute paint or finishes or add materials unless such procedure is specifically described in manufacturer's product instructions.
- B. Volatile Organic Compound (VOC) Content:
  - 1. Provide paints and finishes that comply with the most stringent requirements specified in the following:
    - 40 CFR 59, Subpart D--National Volatile Organic Compound Emission Standards for Architectural Coatings.
  - 2. Determination of VOC Content: Testing and calculation in accordance with 40 CFR 59, Subpart D (EPA Method 24), exclusive of colorants added to a tint base and water added at project site; or other method acceptable to authorities having jurisdiction.

### 2.03 PAINT SYSTEMS - INTERIOR

- A. Paint P1, P2, P3, & P4 Interior Surfaces to be Painted, Unless Otherwise Indicated: Including gypsum board, wood, shop primed steel, galvanized steel, aluminum, and textured wall covering.
  - 1. Two top coats and one coat primer.
  - 2. Top Coat(s): Interior, 100 percent Acrylic Latex, Zero VOC..
    - a. Products:
      - 1) PPG Paints: Manor Hall Interior Latex.
  - 3. Primer: As recommended by top coat manufacturer for specific substrate.
- B. Paint PT1 Medium Duty Door/Trim: For surfaces subject to frequent contact by occupants, including metals:
  - 1. Medium duty applications include door frames, railings, handrails, guardrails, and balustrades.
  - 2. Two top coats and one coat primer.
  - 3. Top Coat(s): High Performance Architectural Interior Latex; MPI #138, 139, 140, or 141.
  - 4. Primer: As recommended by top coat manufacturer for specific substrate.

### 2.04 PRIMERS

- A. Primers: Provide the following unless other primer is required or recommended by manufacturer of top coats.
  - 1. Alkali Resistant Water Based Primer; MPI #3.

# 2.05 ACCESSORY MATERIALS

- A. Accessory Materials: Provide primers, sealers, cleaning agents, cleaning cloths, sanding materials, and clean-up materials as required for final completion of painted surfaces.
- B. Patching Material: Latex filler.

C. Fastener Head Cover Material: Latex filler.

### PART 3 EXECUTION

### 3.01 EXAMINATION

- A. Examine substrates and conditions, with Applicator present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.
- B. Do not begin application of paints and finishes until substrates have been adequately prepared.
- C. Verify that surfaces are ready to receive work as instructed by the product manufacturer.
- D. Examine surfaces scheduled to be finished prior to commencement of work. Report any condition that may potentially affect proper application.
- E. Test shop-applied primer for compatibility with subsequent cover materials.
- F. Measure moisture content of surfaces using an electronic moisture meter. Do not apply finishes unless moisture content of surfaces is below the following maximums:
  - 1. Gypsum Wallboard: 12 percent.
  - 2. Interior Wood: 15 percent, measured in accordance with ASTM D4442.
- G. Verify suitablity of substrates, including surface conditions and compatibility, with exisiting finishes and primers.
- H. Proceed with coating application only after unsatisfactory conditions have been corrected.
  - 1. Application of coating indicates acceptance of surfaces and conditions

### 3.02 PREPARATION

- A. Clean surfaces thoroughly and correct defects prior to application.
- B. Prepare surfaces using the methods recommended by the manufacturer for achieving the best result for the substrate under the project conditions.
- C. Remove or mask surface appurtenances, including electrical plates, hardware, light fixture trim, escutcheons, and fittings, prior to preparing surfaces or finishing.
  - 1. After completing painting operations, use workers skilled in the trades involved to reinstall items that were removed. Remove surface-applied protection if any.
- D. Clean substrates of substances that could impair bond of paints, including dust, dirt, oil, grease, and incompatible paints and encapsulants.
  - 1. Remove incompatible primers and reprime substrate with compatible primers or apply tie coat as required to produce paint systems indicated.
- E. Seal surfaces that might cause bleed through or staining of topcoat.
- F. Gypsum Board: Fill minor defects with filler compound. Spot prime defects after repair.
- G. Aluminum: Remove surface contamination and oils and wash with solvent according to SSPC-SP 1.
- H. Galvanized Surfaces:
  - 1. Remove surface contamination and oils and wash with solvent according to SSPC-SP 1.
  - 2. Prepare surface according to SSPC-SP 2.
- I. Ferrous Metal:
  - 1. Solvent clean according to SSPC-SP 1.
  - 2. Shop-Primed Surfaces: Sand and scrape to remove loose primer and rust. Feather edges to make touch-up patches inconspicuous. Clean surfaces with solvent. Prime bare steel surfaces. Re-prime entire shop-primed item.
  - 3. Remove rust, loose mill scale, and other foreign substances using methods recommended in writing by paint manufacturer and blast cleaning in accordance with SSPC-SP 6/NACE No.3. Protect from corrosion until coated.

- J. Wood Surfaces to Receive Opaque Finish: Wipe off dust and grit prior to priming. Seal knots, pitch streaks, and sappy sections with sealer. Fill nail holes and cracks after primer has dried; sand between coats. Back prime concealed surfaces before installation.
- K. Wood Doors to be Field-Finished: Seal wood door top and bottom edge surfaces with clear sealer.
- L. Metal Door Frames to be Painted: Prime metal door frame edge surfaces.

#### 3.03 APPLICATION

- A. Apply products in accordance with manufacturer's written instructions and recommendations in "MPI Architectural Painting Specification Manual".
  - 1. Use applicators and techniques suited for paint and substrate indicated
  - 2. Paint surfaces behind movable equipment and furniture same as similar exposed surfaces. Before final installation, paint surfaces behind permanently fixed equipment or furniture with prime coat only.
  - 3. Paint front and backsides of access panels, removeable or hinged covers, and similar hinged items to match exposed surfaces.
  - 4. Do not paint over labels of independent testing agencies or equipment name, identification, performance rating, or nomenclature plates.
  - 5. Primers specifed in painting schedules may be omitted on items that are factory primed or factory finished if acceptable to topcoat manufacturers.
- B. Do not apply finishes to surfaces that are not dry. Allow applied coats to dry before next coat is applied.
- C. Apply each coat to uniform appearance in thicknesses specified by manufacturer.
- D. Sand wood and metal surfaces lightly between coats to achieve required finish.
- E. Vacuum clean surfaces of loose particles. Use tack cloth to remove dust and particles just prior to applying next coat.
- F. Reinstall electrical cover plates, hardware, light fixture trim, escutcheons, and fittings removed prior to finishing.

# 3.04 FIELD QUALITY CONTROL

- A. Owner will provide field inspection.
- B. Notify Owner for inspection after completion of first wall being painted.
- C. Dry-Film Thickness Testing: Owner may engage the services of a qualified testing and inspecting agency to inspect and test paint for dry-film thickness.
  - 1. Contractor shall touch up and restore painted surfaces damaged by testing.
  - 2. If test results show dry-film thickness of applied paint does not comply with paint manufacturer's written recommendations, Contractor shall pay for testing and apply additional coats as needed to provide dry-film thickness that complies with paint manufacturer's written recommendations.

### 3.05 CLEANING

- A. At end of each workday, remove rubbish, empty cans, rags, and other discarded materials from Project site.
- B. Collect waste material that could constitute a fire hazard, place in closed metal containers, and remove daily from site.
- C. Source Limitations: Obtain each paint product from single source manufacturer.
- D. Material Compatibility:
  - 1. Materials for use within each paint system shall be compatible with one another and substrates indicated, under conditions of services and application as demonstrated by manufacturer, based on testing and field experience.
  - 2. For each coat in a paint system, products shall be recommended in writing by topcoat manufacturers for use in paint system and on substrate indicated.

3. Collect waste material that could constitute a fire hazard, place in closed metal containers, and remove daily from site.

### 3.06 CLEANING AND PROTECTION

- A. At end of each workday, remove rubbish, empty cans, rags, and other discarded materials from Project site.
  - 1. Do not clean equipment with free-draining water and prevent solvents, thinners, cleaners, and other contaminants from entering into waterways, sanitary and storm drain systems, and ground.
  - 2. Dispose of containments in accordance with requirements of authorities having jurisdication.
  - 3. Allow empty paint cans to dry before disposal.
  - 4. Collect waste paint by type and deliver to recyling or collection facility.
- B. After completing paint application, clean spattered surfaces. Remove splattered paints by washing, scraping, or other methods. Do not scratch or damage adjacent finished surfaces.
- C. Protect work of other trades against damage from paint application. Correct damage to work of other trades by cleaning, repairing, replacing, and refinishing, as approved by Designer, and leave in an undamaged condition.
- D. At completion of construction activities of other trades, touch up and restore damaged or defaced painted surfaces
- E. Protect finishes until completion of project.
- F. Touch-up damaged finishes after Substantial Completion.

### 3.07 SCHEDULE - PAINT SYSTEMS

A. Refer to finish schedule on drawings.

### 3.08 COLOR SCHEDULE

A. Refer to Room Schedule/Floor Plans on drawings.

# SECTION 102113.19 PLASTIC TOILET COMPARTMENTS

# PART 1 GENERAL

### 1.01 SECTION INCLUDES

- A. Solid surface toilet compartments.
- B. Urinal and vestibule screens.

# 1.02 RELATED REQUIREMENTS

- A. Section 051200 Structural Steel Framing: Concealed steel support members.
- B. Section 055000 Metal Fabrications: Concealed steel support members.
- C. Section 102800 Toilet, Bath, and Laundry Accessories.

# 1.03 REFERENCE STANDARDS

A. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2023d.

### 1.04 ADMINISTRATIVE REQUIREMENTS

A. Coordination: Coordinate the work with placement of support framing and anchors in walls and ceilings.

#### 1.05 SUBMITTALS

- A. See Section 013300 Submittals, for submittal procedures.
- B. Product Data: Provide data on panel construction, hardware, and accessories.
- Shop Drawings: Indicate partition plan, elevation views, dimensions, details of wall supports, door swings.
- D. Samples: Submit two samples of partition panels, 4 by 4 inch in size illustrating panel finish, color, and sheen.
- E. Manufacturer's Installation Instructions: Indicate special procedures.

# PART 2 PRODUCTS

### 2.01 MANUFACTURERS

- A. Solid Surface Toilet Compartments; Basis-of-Design Product:
  - 1. DuPont Corian; Privacy Plus Partitions.
- B. Solid Surface Toilet Compartments; Other acceptable manufacturers include the following:
  - 1. DuPont Corian
  - 2. Avonite Surfaces; a brand of Aristech Surfaces LLC
  - 3. Wilsonart LLC

# 2.02 PLASTIC TOILET COMPARTMENTS

- A. Solid Surface Toilet Compartments: Factory fabricated doors, pilasters, and divider panels made of acrylic polymer resin, mineral filler, and pigment, tested in accordance with ASTM E84; ceiling-hung.
  - 1. Color: Single color as selected.
  - 2. Doors:
    - a. Thickness: 1 inch.
    - b. Width: 24 inch.
    - c. Width for Handicapped Use: 36 inch, out-swinging.
    - d. Height: 55 inch.
  - 3. Panels:
    - a. Thickness: 1/2 inch.
    - b. Height: 55 inch.
    - c. Depth: As indicated on drawings.
  - 4. Pilasters:

Plastic Toilet Compartments

- a. Thickness: 1 inch.
- b. Width: As required to fit space; minimum 3 inch.
- 5. Screens: Without doors; to match compartments; mounted to wall with two panel brackets.

#### 2.03 ACCESSORIES

- A. Head Rails: Extruded aluminum, anti-grip profile.
  - 1. Size: Manufacturer's standard size.
- B. Wall and Pilaster Brackets: Stainless steel; manufacturer's standard type for conditions indicated on drawings.
- C. Attachments, Screws, and Bolts: Stainless steel, tamper proof type.
- D. Hinges: Stainless steel, manufacturer's standard finish.
  - 1. Pivot hinges, gravity type, adjustable for door close positioning; two per door.
  - 2. Continuous-type hinge, self closing.
- E. Door Hardware: Stainless steel, manufacturer's standard finish.
  - 1. Door Latch: Slide type with exterior emergency access feature.
  - 2. Door Strike and Keeper with Rubber Bumper: Mount on pilaster in alignment with door latch.
  - 3. Provide door pull for outswinging doors.
- F. Coat Hook: One per compartment, mounted on door.
  - See Section 102800.
- G. Toilet Partition Suspension Members: As specified in Section 055000.

# **PART 3 EXECUTION**

### 3.01 EXAMINATION

- A. Verify that field measurements are as indicated.
- B. Verify correct spacing of and between plumbing fixtures.
- C. Verify correct location of built-in framing, anchorage, and bracing.

### 3.02 INSTALLATION

- A. Install partitions secure, rigid, plumb, and level in accordance with manufacturer's instructions.
- B. Maintain 3/8 inch to 1/2 inch space between wall and panels and between wall and end pilasters.
- C. Attach panel brackets securely to walls using anchor devices.
- D. Attach panels and pilasters to brackets. Locate head rail joints at pilaster center lines.

# 3.03 TOLERANCES

- A. Maximum Variation From True Position: 1/4 inch.
- B. Maximum Variation From Plumb: 1/8 inch.

### 3.04 ADJUSTING

- A. Adjust and align hardware to uniform clearance at vertical edge of doors, not exceeding 3/16 inch.
- B. Adjust hinges to position doors in partial opening position when unlatched. Return out-swinging doors to closed position.
- C. Adjust adjacent components for consistency of line or plane.

# SECTION 102800 TOILET, BATH, AND LAUNDRY ACCESSORIES

# PART 1 GENERAL

### 1.01 SECTION INCLUDES

- A. Commercial toilet accessories.
- B. Diaper changing stations.

# 1.02 RELATED REQUIREMENTS

A. Section 102113.19 - Plastic Toilet Compartments.

# 1.03 REFERENCE STANDARDS

- A. ASTM B456 Standard Specification for Electrodeposited Coatings of Copper Plus Nickel Plus Chromium and Nickel Plus Chromium; 2017 (Reapproved 2022).
- B. ASTM C1036 Standard Specification for Flat Glass; 2021.
- C. ASTM C1503 Standard Specification for Silvered Flat Glass Mirror; 2024.
- D. ASTM F2285 Standard Consumer Safety Performance Specification for Diaper Changing Tables for Commercial Use; 2022.

### 1.04 SUBMITTALS

- A. See Section 013300 Submittals, for submittal procedures.
- B. Product Data: Submit data on accessories describing size, finish, details of function, and attachment methods.
- Manufacturer's Installation Instructions: Indicate special procedures and conditions requiring special attention.

### **PART 2 PRODUCTS**

### 2.01 MANUFACTURERS

- A. Commercial Toilet, Shower, and Bath Accessories:
  - 1. Bradley Corporation.
  - 2. Georgia-Pacific Professional.
  - 3. Bobrick.
  - 4. Tork USA.
  - 5. Spartan.
- B. Diaper Changing Stations:
  - 1. American Specialties, Inc
  - 2. Bradley Corporation
  - 3. Koala Kare Products

# 2.02 MATERIALS

- A. Accessories General: Shop assembled, free of dents and scratches and packaged complete with anchors and fittings, steel anchor plates, adapters, and anchor components for installation.
- B. Keys: Provide keys for each accessory to Owner; master key lockable accessories.
- C. Mirror Glass: Annealed float glass, ASTM C1036 Type I, Class 1, Quality Q2, with silvering, protective and physical characteristics complying with ASTM C1503.
- D. Adhesive: Two component epoxy type, waterproof.
- E. Fasteners, Screws, and Bolts: Hot dip galvanized; tamper-proof; security type.

### 2.03 FINISHES

A. Stainless Steel: Satin finish, unless otherwise noted.

- B. Chrome/Nickel Plating: ASTM B456, SC 2, polished finish, unless otherwise noted.
- C. Baked Enamel: Pretreat to clean condition, apply one coat primer and minimum two coats epoxy baked enamel.
- D. Powder-Coated Steel: Clean, degrease, and neutralize. Follow immediately with a phosphatizing treatment, prime coat, and two finish coats of powder coat enamel.

### 2.04 COMMERCIAL TOILET ACCESSORIES

- A. Toilet Paper Dispenser: Double roll, surface mounted, for coreless type rolls.
  - 1. Rool Capacity: 9 inch.
  - 2. Color: Smoke.
  - 3. Basis-of-Design Product:
    - a. Tork USA; Twin Jumbo Bath Tissue Roll Dispenser.
- B. Paper Towel Dispenser: Manual, roll paper type.
  - 1. Cover: Stainless steel.
  - 2. Paper Discharge: Manual dispense by lever operation.
  - 3. Capacity: 6-inch diameter roll.
  - 4. Mounting: Surface mounted.
  - 5. Refill Indicator: Transparent viewing slot.
- C. Combination Towel Dispenser/Waste Receptacle: Recessed flush with wall, stainless steel; seamless wall flanges, continuous piano hinges, \_\_\_\_.
- D. Soap Dispenser: Liquid soap dispenser, wall-mounted, surface, with plastic cover and horizontal stainless steel tank and working parts; push type soap valve, check valve, and window gauge refill indicator, tamper-proof key lock.
  - 1. Minimum Capacity: 34 ounces.
  - 2. Color: Black.
  - 3. Basis-of-Design Product:
    - a. Spartan; Lite'n Foamy Manual Dispenser.
- E. Mirrors: Stainless steel framed, 1/4 inch thick annealed float glass; ASTM C1036.
  - 1. Frame: 0.05 inchangle shapes, with mitered and welded and ground corners, and tamperproof hanging system; matte black finish.
  - 2. Backing: Full-mirror sized, minimum 0.03 inch galvanized steel sheet and nonabsorptive filler material.
  - 3. Basis-of-Design Product:
    - a. Bobrick; Glass Mirror with Stainless Steel Angle Frame, B-290 series.
- F. Seat Cover Dispenser: Stainless steel, surface-mounted, reloading by concealed opening at base, tumbler lock.
  - 1. Minimum capacity: 250 seat covers.
  - 2. Finish: Matte black.
  - 3. Basis-of-Design Product:
    - a. Bobrick; B-221 Classic Series, Surface-Mounted Seat-Cover Dispenser.
- G. Grab Bars: Stainless steel, smooth surface.
  - Standard Duty Grab Bars:
    - a. Push/Pull Point Load: 250 pound-force, minimum.
    - b. Dimensions: 1-1/2 inch outside diameter, minimum 0.05 inch wall thickness, exposed flange mounting, 1-1/2 inch clearance between wall and inside of grab bar.
    - c. Finish: Satin.
    - d. Length and Configuration: As indicated on drawings.
    - e. Basis-of-Design Product:
      - 1) Bobrick; B-6806 series, 1-1/2" Diameter Stainless Steel Grab Bars with Snap Flange.

- H. Sanitary Napkin Disposal Unit: Stainless steel, surface-mounted, self-closing door, locking bottom panel with full-length stainless steel piano-type hinge, removable receptacle.
  - 1. Basis-of-Design Product:
    - a. Bobrick; B-254 series, Surface-Mounted Sanitary Napkin Disposal.
- I. Coat Hook: Stainless steel, surface-mounted, with cylindrical post and hook pin, and concealed mounting flange.
  - 1. Post: 3/4 inch diamter, 2-31/32 inch length.
  - 2. Hook Pin: 5/8 inch diamter, integrated into the post.
  - 3. Flange Cover: 1/16 inch thick, 1-5/16 inch diamter.
  - 4. Concealed Mounting Flange: 5/32 inch thick, 1-5/16 inch diameter. Two mounting holes for attachment to wall.
  - 5. Strength: Support loads of up to 150 pounds.
  - 6. Finish: Matte black.
  - 7. Basis-of-Design Product:
    - a. Bobrick; B-9542, fino collection, coat hook.

### 2.05 DIAPER CHANGING STATIONS

- A. Diaper Changing Station: Wall-mounted folding diaper changing station for use in commercial toilet facilities, meeting or exceeding ASTM F2285.
  - 1. Material: Bacterial-resistant polyethylene with brushed 20 gauge stainless steel exterior..
  - 2. Mounting: Surface.
  - 3. Minimum Rated Load: Rated to support static load of 250 pounds, tested to 390 pounds.
  - 4. Pneumatic gas shock mechanism to ensure smooth, safe open and close motions.
  - 5. Corner Guards: Black nylon 6/6 corner guards for added protection.
  - 6. Handle: Black ABS plastic handle.
  - 7. Molded Dual Liner Dispenser: Holds approximately 50 per dispenser.
  - 8. Safety Belt: With came-buckle, adjustable with one hand.
  - 9. ADA compliant.
  - 10. Basis-of-Design Product:
    - Bradley Corporation; Stainless Steel Baby Changing Station, Model 962-11 Surface-Mounted Bradex.

### PART 3 EXECUTION

# 3.01 EXAMINATION

- A. Verify existing conditions before starting work.
- B. Verify exact location of accessories for installation.
- C. Verify that field measurements are as indicated on drawings.

# 3.02 PREPARATION

- A. Deliver inserts and rough-in frames to site for timely installation.
- B. Provide templates and rough-in measurements as required.

### 3.03 INSTALLATION

- A. Install accessories in accordance with manufacturers' instructions in locations indicated on drawings.
- B. Install plumb and level, securely and rigidly anchored to substrate.
- C. Mounting Heights: As required by accessibility regulations, unless otherwise indicated.

# 3.04 PROTECTION

A. Protect installed accessories from damage due to subsequent construction operations.

## SECTION 123600 COUNTERTOPS

## PART 1 GENERAL

# 1.01 SECTION INCLUDES

- A. Wall-hung counters and vanity tops.
- B. Solid surface material countertops.
- C. Solid surface material backsplashes.
- D. Solid surface material and end splashes.

## 1.02 REFERENCE STANDARDS

A. ASTM B211/B211M - Standard Specification for Aluminum and Aluminum-Alloy Rolled or Cold Finished Bar, Rod, and Wire; 2019.

### 1.03 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Product Data: Manufacturer's data sheets on each product to be used, including:
  - 1. Preparation instructions and recommendations.
  - 2. Storage and handling requirements and recommendations.
  - 3. Specimen warranty.
- C. Shop Drawings: For countertops. Show materials, finishes, edge and backsplash profiles, methods of joining, and cutouts for plumbing fixtures.
  - 1. Show locations and details of joints.
  - 2. Show direction of directional pattern, if any.
- D. Samples for Verifcation: For the following products:
  - 1. Countertop material, 6 inches square.
  - 2. One full-size solid surface material countertop, with front edge and backsplash, 8 by 10 inches, of construction and in configuration specifed.
- E. Qualification Data: For fabricator.
- F. Maintenance Data: Manufacturer's instructions and recommendations for maintenance and repair of countertop surfaces.

## 1.04 QUALITY ASSURANCE

- A. Fabricator Qualifications: Shop that employs skilled workers who custom-fabricate countertops similar to that required for this Project, and whose products have a record successful in-service performance.
- B. Installer Qualifications: Fabricator of countertops.
- C. Mockups: Build mockups to demonstrate aesthetic effects and to set qulaity standards for fabrication and execution.
  - 1. Build mockup of typical countertop as indicated on Drawings.
  - 2. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

### 1.05 FIELD CONDITIONS

- A. Maintain environmental conditions (temperature, humidity, and ventilation) within limits recommended by manufacturer for optimum results. Do not install products under environmental conditions outside manufacturer's absolute limits.
- B. Field Measurements: Verfiy dimensions of countertops by field measurements before countertop fabrication is complete.

### 1.06 COORDINATION

- A. Coordinate locations of utilities that will penetrate countertops or backsplashes.
- B. Coordinate provision of cabinetry with design and fabrication of countertops to be supported to ensure compatibility of dimensions and load capacity.
- Coordinate requirements needed for countertop structural supports system to ensure adequate means for installtion of cabinetry.
- D. Coordinate installation of countertop with application of wall finished. To the extent possible install countertops after finishes have been applied.

### **PART 2 PRODUCTS**

### 2.01 SOLID SURFACE COUNTERTOP MATERIAL

- A. Solid Surface Countertop Material: Homogenous-filled plastic resin complying with ISFA
  - 1. Basis-of-Design Product: Subject to compliance with requirements, provide Corian Design; Solid Surface, Domino Terazzo or comparable product by one of the following:
    - a. Avonite Surfaces; a Brand of Aristect Surfaces LLC
    - b. Dupont; Dupont de Nemours, Inc.
    - c. Wilsonart LLC
  - Type: Provide Standard type or Veneer type made from material complying with requirements for Standard type, as indicated unless Special Purpose type is indicated.
  - 3. Colors and Patterns: As selected by Designer from manufacturer's full range.
- B. Plywood: Exterior softwood plywood complying with DOC PS 1, Grade C-C Plugged, touch sanded.

#### 2.02 FABRICATION

- A. Fabricate countertops according to solid surface material manufacturer's written instructions and to the AWI/AWMAC/WI's "Architectural Woodwork Standards."
  - 1. Grade: Premium
- B. Configuration:
  - 1. Countertop: Straight, with one 1/4-inch radius edge.
  - 2. Backsplash: Straight, slightly eased at corner.
  - 3. End splash: Matching backsplash.
- C. Countertops:
  - 1. 1/2-inch thick, solid surface material with front edge built up with same material.
- D. Backsplashes: 1/2-inch thick, solid surface material.
- E. Fabricate tops with shop-appllied edges and backsplashes unless otherwise indicated. Comply with solid surface material manufacturer's written instructions for adhesives, sealers, fabrication, and finishing.
  - 1. Fabricate with loose backsplashes for field assembly.
- F. Joints:
  - 1. Fabricate countertops without joints.
- G. Cutouts and Holes:
  - 1. Undercounter Plumbing Fixtures: Make cutouts for fixtures in shop using template or pattern furnished by fixture manufactuer. Form cutouts to smooth, even curves.
    - a. Provide vertical edges, slightly eased at juncture of cutout edges with top and bottom surfaces of countertop and projecting 0 inches into fixture opening.
  - Fittings: Drill countertops in shop for plumbing fittings, undercounter soap dispensers, and similar items.
- H. Fabricate tops and splashes in the largest sections practicable, with top surface of joints flush.
  - 1. Join lengths of tops using best method recommended by manufacturer.

- Fabricate to overhang fronts and ends of cabinets 1 inch except where top butts against cabinet or wall
- 3. Prepare all cutouts accurately to size; replace tops having improperly dimensioned or unnecessary cutouts or fixture holes.
- I. Provide back/end splash wherever counter edge abuts vertical surface unless otherwise indicated.
  - 1. Secure to countertop with concealed fasteners and with contact surfaces set in waterproof glue.
  - 2. Height: 4 inches, unless otherwise indicated.

### 2.03 INSTALLATION MATERIALS

- A. Adhesives: Product recommended by solid surface material manufactuerer.
- B. Sealant fo Counterops: Comply with applicable requirements in Section 079200 "Joint Sealants."

### PART 3 EXECUTION

### 3.01 EXAMINATION

- A. Examine substrates to receive solid surface material countertops and conditions under which countertops will be installed, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of countertops.
- B. Do not begin installation until substrates have been properly prepared.
- C. If substrate preparation is the responsibility of another installer, notify Architect of unsatisfactory preparation before proceeding.
- D. Verify that wall surfaces have been finished and mechanical and electrical services and outlets are installed in proper locations.

### 3.02 INSTALLATION

- A. Install countertops level to a tolerance of 1/8 inch in 8 feet, 1/4 inch maximum. Do not exceed 1/64 difference between planes of adjacent units.
- B. Secure countertops to cabinetry with adhesive according to solid surface material manufacturer's written instructions. Align adjacent surfaces and, using adhesive in color to match countertop, form seams to comply with manufacturer's written instructions. Carefully dress joints smooth, remove surface scratches, and clean entire surface.
- C. Securely attach countertops to cabinets using concealed fasteners. Make flat surfaces level; shim where required.
- D. Seal joint between back/end splashes and vertical surfaces.
- E. Install backsplashes and end splashes by adhereing to wall and countertops with adhesive. Mask areas of countertops and splashes adjacent to joints to prevent adhesive smears.
- F. Complete cutouts not finished in shop. Mask areas of counterttops adjacent to cutouts to prevent damage while cutting. Make cutouts to accuraely fit items to be installed, and at right angles to finished surfaces unless beveling is required for clearance. Ease edges slightly to prevent snipping.
- G. Apply sealant to gaps at walls; comply with Section 079200 "Joint Sealants."

# 3.03 CLEANING

A. Clean countertops surfaces thoroughly.

## 3.04 PROTECTION

- A. Protect installed products until completion of project.
- B. Touch-up, repair or replace damaged products before Date of Substantial Completion.

## SECTION 211300 FIRE-SUPPRESSION SPRINKLER SYSTEMS

## PART 1 GENERAL

### 1.01 SECTION INCLUDES

A. System design, installation, and certification.

### 1.02 REFERENCE STANDARDS

A. NFPA 13 - Standard for the Installation of Sprinkler Systems; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

## 1.03 SUBMITTALS

- A. See Section 013300 Submittals for submittal procedures.
- B. Shop Drawings:
  - 1. State of Missouri is Authority Having Jurisdiction. Sprinkler system shall be designed and installed per NFPA 13-2025.
  - 2. Submit preliminary layout of finished ceiling areas indicating only sprinkler locations coordinated with ceiling installation.
- C. Operation and Maintenance Data: Include components of system, servicing requirements, record drawings, inspection data, replacement part numbers and availability, and location and numbers of service depot.

## 1.04 QUALITY ASSURANCE

- A. Designer Qualifications: Design system under direct supervision of a Professional Engineer experienced in design of this type of work and licensed in the State in which the Project is located.
- B. Manufacturer Qualifications: Company specializing in manufacturing the Products specified in this section with minimum three years documented experience.
- C. Installer Qualifications: Company specializing in performing the work of this section documented experience and approved by manufacturer.

## 1.05 DELIVERY, STORAGE, AND HANDLING

A. Store products in shipping containers and maintain in place until installation. Provide temporary inlet and outlet caps. Maintain caps in place until installation.

# PART 2 PRODUCTS

## 2.01 SPRINKLER SYSTEM

A. Occupancy: Light hazard; comply with NFPA 13.

## 2.02 SPRINKLERS

- A. Suspended Ceiling Type: Semi-recessed pendant type with matching push on escutcheon plate.
  - 1. Response Type: Standard.
  - 2. Coverage Type: Standard.
  - 3. Finish: Chrome plated.
  - 4. Escutcheon Plate Finish: Chrome plated.
  - 5. Fusible Link: Fusible solder link type temperature rated for specific area hazard.
- B. Sidewall Type: Semi-recessed horizontal sidewall type with matching push on escutcheon plate.
  - 1. Response Type: Standard.
  - 2. Coverage Type: Standard.
  - 3. Finish: Chrome plated.
  - 4. Escutcheon Plate Finish: Chrome plated.
  - 5. Fusible Link: Fusible solder link type temperature rated for specific area hazard.

## **PART 3 EXECUTION**

## 3.01 INSTALLATION

- A. Install in accordance with referenced NFPA design and installation standard.
- B. Install equipment in accordance with manufacturer's instructions.
- C. Place pipe runs to minimize obstruction to other work.
- D. Place piping in concealed spaces above finished ceilings.
- E. Apply masking tape or paper cover to ensure concealed sprinklers, cover plates, and sprinkler escutcheons do not receive field paint finish. Remove after painting. Replace painted sprinklers.
- F. Flush entire piping system of foreign matter.

# 3.02 SCHEDULES

- A. System Hazard Areas:
  - 1. Offices: Light Hazard.

## SECTION 221006 PLUMBING PIPING SPECIALTIES

## PART 1 GENERAL

## 1.01 SECTION INCLUDES

A. Drains.

## 1.02 SUBMITTALS

- A. See Section 013300 Submittals for submittal procedures.
- B. Product Data: Provide component sizes, rough-in requirements, service sizes, and finishes.

## 1.03 QUALITY ASSURANCE

A. Manufacturer Qualifications: Company specializing in manufacturing the Products specified in this section with not less than three years documented experience.

# 1.04 DELIVERY, STORAGE, AND HANDLING

A. Accept specialties on site in original factory packaging. Inspect for damage.

## **PART 2 PRODUCTS**

## 2.01 DRAINS

- A. Floor Drains:
  - 1. Manufacturers:
    - a. Jay R. Smith Manufacturing Company: www.jrsmith.com.
    - b. MIFAB, Inc: www.mifab.com.
    - c. Zurn Industries, LLC: www.zurn.com.
- B. Floor Drain (FD-1):
  - 1. ASME A112.6.3; PVC solvent weld body with bottom outlet, stainless steel deck plate, and 1/2" trap primer connection knock-out plug and top assembly.

### PART 3 EXECUTION

### 3.01 INSTALLATION

A. Install in accordance with manufacturer's instructions.

## SECTION 224000 PLUMBING FIXTURES

# PART 1 GENERAL

### 1.01 SECTION INCLUDES

- A. Flush valve water closets.
- B. Wall hung urinals.
- C. Lavatories.
- D. Under-lavatory pipe supply covers.

## 1.02 REFERENCE STANDARDS

- A. ADA Standards 2010 ADA Standards for Accessible Design; 2010.
- B. ASME A112.18.1 Plumbing Supply Fittings; 2018, with Errata.
- C. ASME A112.18.9 Protectors/Insulators for Exposed Waste and Supplies on Accessible Fixtures; 2011 (Reaffirmed 2022).
- D. ASME A112.19.2 Ceramic Plumbing Fixtures; 2024.
- E. ASME A112.19.5 Flush Valves and Spuds for Water Closets, Urinals, and Tanks; 2022.
- F. ASTM G21 Standard Practice for Determining Resistance of Synthetic Polymeric Materials to Fungi; 2015, with Editorial Revision (2021).
- G. ICC A117.1 Accessible and Usable Buildings and Facilities; 2017.
- H. NSF 61 Drinking Water System Components Health Effects; 2023, with Errata.
- I. NSF 372 Drinking Water System Components Lead Content; 2022.
- J. UL (DIR) Online Certifications Directory; Current Edition.

## 1.03 SUBMITTALS

- A. See Section 013300 Submittals for submittal procedures.
- B. Product Data: Provide catalog illustrations of fixtures, sizes, utility sizes, trim, and finishes.

#### 1.04 QUALITY ASSURANCE

A. Manufacturer Qualifications: Company specializing in manufacturing the type of products specified in this section, with minimum three years of documented experience.

## 1.05 DELIVERY, STORAGE, AND HANDLING

- A. Accept fixtures on-site in factory packaging. Inspect for damage.
- B. Protect installed fixtures from damage by securing areas and by leaving factory packaging in place to protect fixtures and prevent use.

### **PART 2 PRODUCTS**

## 2.01 GENERAL REQUIREMENTS

A. Potable Water Systems: Provide plumbing fittings and faucets that comply with NSF 61 and NSF 372 for maximum lead content; label pipe and fittings.

## 2.02 REGULATORY REQUIREMENTS

- A. Comply with applicable codes for installation of plumbing systems.
- B. Comply with UL (DIR) requirements.
- C. Perform work in accordance with local health department regulations.

## 2.03 FLUSH VALVE WATER CLOSETS

A. Water Closets:

Plumbing Fixtures

- 1. Vitreous china, ASME A112.19.2, floor mounted, siphon jet flush action, china bolt caps.
- 2. Bowl: ASME A112.19.2; 16.5 inches high with elongated rim.
- 3. Flush Valve: Exposed (top spud).
- 4. Flush Operation: Sensor operated.
- 5. Inlet Size: 1-1/2 inches.
- 6. Trapway Outlet: 2-1/8 inch.
- 7. Color: White.
- 8. Manufacturers:
  - a. American Standard, Inc: www.americanstandard-us.com.
  - b. Kohler Company: www.kohler.com.
  - c. Zurn Industries, LLC: www.zurn.com.

### B. Flush Valves:

- 1. Valve Supply Size: 1 inch.
- 2. Valve Outlet Size: 1-1/2 inches.
- Manufacturers:
  - a. American Standard, Inc: www.americanstandard-us.com.
  - b. Sloan Valve Company: www.sloanvalve.com.
  - c. Zurn Industries, LLC: www.zurn.com.
- Sensor-Operated:
  - a. Type: ASME A112.19.5; chloramine-resistant clog-resistant dual-seat diaphragm valve complete with vacuum breaker, stops and accessories.
  - b. Mechanism: Solenoid-operated piston or electronic motor-actuated operator with battery powered infrared sensor, and mechanical override or override push button.
  - c. Supplied Volume Capacity: 1.6 gal per flush.
- 5. Exposed Type: Chrome-plated, escutcheon, integral screwdriver stop.
- 6. Vacuum Breaker Tube:
  - For each water closet provide appropriately sized vacuum breaker tube from list of available standard sizes. Cut to fit as needed.

## C. Toilet Seats:

- Manufacturers:
  - a. American Standard, Inc: www.americanstandard-us.com.
  - b. Bemis Manufacturing Company: www.bemismfg.com.
  - c. Kohler Company: www.kohler.com.
  - d. Zurn Industries, LLC: www.zurn.com.
- 2. Plastic: Solid, white finish with factory applied antimicrobial agent, enlongated shape, open front, extended back complete with self-sustaining hinges, and brass bolts with covers.

### 2.04 WALL HUNG URINALS

- A. Manufacturers:
  - 1. American Standard, Inc: www.americanstandard-us.com.
  - 2. Kohler Company: www.kohler.com.
  - 3. Zurn Industries, LLC: www.zurn.com.
- B. Vitreous china, ASME A112.19.2, wall hung with side shields and concealed carrier.
  - 1. Consumption Volume: 0.125 gal per flush, maximum.
  - 2. Flush Valve: Exposed (top spud).
  - 3. Flush Operation: Sensor operated.
  - 4. Trapway Outlet: Integral.
  - 5. Outlet Size and Location: 2 inches, rear side.
- C. Flush Valves:
  - 1. Manufacturers:
    - a. American Standard, Inc: www.americanstandard-us.com.

Plumbing Fixtures

- b. Sloan Valve Company: www.sloanvalve.com.
- c. Zurn Industries, LLC: www.zurn.com.

### 2. Sensor-Operated:

- a. Type: ASME A112.19.5; chloramine-resistant, clog-resistant dual-seat diaphragm valve with vacuum breaker, stops and accessories.
- b. Mechanism: Solenoid-operated piston or electronic motor-actuated operator with battery powered infrared sensor, and mechanical override or override push button.
- c. Supplied Volume Capacity: 0.125 gal per flush.
- 3. Exposed Type: Chrome-plated, escutcheon, integral screwdriver stop.
- 4. Vacuum Breaker Tube:
  - For each urinal provide appropriately sized vacuum breaker tube from list of available standard sizes. Cut to fit as needed.

## 2.05 LAVATORIES

### A. Manufacturers:

- 1. American Standard, Inc: www.americanstandard-us.com.
- 2. Kohler Company: www.kohler.com.
- 3. Zurn Industries, LLC: www.zurn.com.

#### B. Under-Mount Sink:

1. Vitreous China: ASME A112.19.2; white interior, oval shape, front overflow, seal of putty, caulking, or concealed vinyl gasket, and white exterior finish. Size 15-3/8 by 19 inches.

## C. Supply Faucet:

- 1. Deck Mounted Faucet Manufacturers:
  - a. American Standard, Inc: www.americanstandard-us.com.
  - b. Kohler Company: www.kohler.com.
  - c. Zurn Industries, LLC: www.zurn.com.
- 2. ASME A112.18.1; chrome plated combination supply fitting, water economy aerator with maximum flow of 1 gpm, indexed handles.
- 3. Double Lever Handle, Commercial Faucet: ASME A112.18.1; deck-mount, ceramic cartridge disc valve, and maximum flow of 1 gpm. Polished chrome finish.

#### D. Accessories:

- 1. 1-1/2 inch grid drain with overflow and a polished chrome finish.
- 2. Multi-turn angle stops.

### 2.06 UNDER-LAVATORY PIPE SUPPLY COVERS

## A. General:

- 1. Insulate exposed drainage piping including hot, cold and tempered water supplies under lavatories or sinks per ADA Standards.
- 2. Construction: 1/8 inch PVC with antimicrobial, antifungal and UV resistant properties.
  - a. Comply with ASME A112.18.9 for covers on accessible lavatory piping.
  - b. Comply with ICC A117.1.
  - c. Microbial and Fungal Resistance for Interior and Exterior: Comply with ASTM G21.
- 3. Color: High gloss white.

### PART 3 EXECUTION

#### 3.01 EXAMINATION

- A. Verify that walls and floor finishes are prepared and ready for installation of fixtures.
- B. Confirm that millwork is constructed with adequate provision for the installation of counter top lavatories and sinks.

### 3.02 PREPARATION

A. Rough-in fixture piping connections in accordance with minimum sizes indicated in fixture rough-in schedule for particular fixtures.

## 3.03 INSTALLATION

- A. Install each fixture with trap, easily removable for servicing and cleaning.
- B. Provide chrome-plated rigid or flexible supplies to fixtures with multi-turn angle stops, reducers, and escutcheons.
- C. Install components level and plumb.
- D. Solidly attach water closets to floor with lag screws. Lead flashing is not intended to hold fixture in place.

## 3.04 ADJUSTING

A. Adjust stops or valves for intended water flow rate to fixtures without splashing, noise, or overflow.

## 3.05 CLEANING

A. Clean plumbing fixtures and equipment.

## 3.06 PROTECTION

- A. Protect installed products from damage due to subsequent construction operations.
- B. Do not permit use of fixtures by construction personnel.
- C. Repair or replace damaged products before Date of Substantial Completion.

### 3.07 SCHEDULES

- A. Fixture Heights: Install fixtures to heights above finished floor as indicated.
  - 1. Urinal:
    - a. Accessible: 17 inches maximum to top of bowl rim.

## SECTION 230593 TESTING, ADJUSTING, AND BALANCING FOR HVAC

## PART 1 GENERAL

## 1.01 SECTION INCLUDES

A. Testing, adjustment, and balancing of air systems.

## 1.02 REFERENCE STANDARDS

- A. AABC (NSTSB) AABC National Standards for Total System Balance, 7th Edition; 2016.
- B. ASHRAE Std 111 Measurement, Testing, Adjusting, and Balancing of Building HVAC Systems; 2008, with Errata (2019).
- C. NEBB (TAB) Procedural Standard for Testing, Adjusting and Balancing of Environmental Systems; 2019, with Errata (2022).
- D. SMACNA (TAB) HVAC Systems Testing, Adjusting and Balancing; 2023.

## 1.03 SUBMITTALS

- A. See Section 013300 Submittals for submittal procedures.
- B. Installer Qualifications: Submit name of adjusting and balancing agency and TAB supervisor for approval within 30 days after award of Contract.
- C. Final Report: Indicate deficiencies in systems that would prevent proper testing, adjusting, and balancing of systems and equipment to achieve specified performance.
  - 1. Include actual instrument list, with manufacturer name, serial number, and date of calibration.
  - 2. Form of Test Reports: Where the TAB standard being followed recommends a report format use that; otherwise, follow ASHRAE Std 111.
  - 3. Units of Measure: Report data in I-P (inch-pound) units only.
  - 4. Include the following on the title page of each report:
    - a. Name of Testing, Adjusting, and Balancing Agency.
    - b. Address of Testing, Adjusting, and Balancing Agency.
    - c. Telephone number of Testing, Adjusting, and Balancing Agency.
    - d. Project name.
    - e. Project location.
    - f. Project Engineer.
    - g. Project Contractor.
    - h. Report date.

## PART 2 PRODUCTS - NOT USED

## PART 3 EXECUTION

## 3.01 GENERAL REQUIREMENTS

- A. Perform total system balance in accordance with one of the following:
  - 1. AABC (NSTSB), AABC National Standards for Total System Balance.
  - 2. ASHRAE Std 111, Practices for Measurement, Testing, Adjusting and Balancing of Building Heating, Ventilation, Air-Conditioning, and Refrigeration Systems.
  - 3. NEBB (TAB) Procedural Standard for Testing Adjusting and Balancing of Environmental Ssytems; 2019.
  - 4. SMACNA (TAB).
- B. Begin work after completion of systems to be tested, adjusted, or balanced and complete work prior to Substantial Completion of the project.
- C. TAB Agency Qualifications:
  - 1. Company specializing in the testing, adjusting, and balancing of systems specified in this section.
  - 2. Having minimum of three years documented experience.

- 3. Certified by one of the following:
  - a. AABC, Associated Air Balance Council: www.aabc.com/; upon completion submit AABC National Performance Guaranty.
  - b. NEBB, National Environmental Balancing Bureau: www.nebb.org/.
  - c. TABB, The Testing, Adjusting, and Balancing Bureau of National Energy Management Institute: www.tabbcertified.org/.
- D. TAB Supervisor and Technician Qualifications: Certified by same organization as TAB agency.

### 3.02 EXAMINATION

- A. Verify that systems are complete and operable before commencing work. Ensure the following conditions:
  - 1. Systems are started and operating in a safe and normal condition.
  - 2. Duct systems are clean of debris.
  - 3. Air outlets are installed and connected.
  - 4. Duct system leakage is minimized.
- B. Submit field reports. Report defects and deficiencies that will or could prevent proper system balance.
- C. Beginning of work means acceptance of existing conditions.

#### 3.03 PREPARATION

A. Provide additional balancing devices as required.

## 3.04 ADJUSTMENT TOLERANCES

A. Air Outlets and Inlets: Adjust total to within plus 10 percent and minus 5 percent of design to space. Adjust outlets and inlets in space to within plus or minus 10 percent of design.

## 3.05 RECORDING AND ADJUSTING

- A. Ensure recorded data represents actual measured or observed conditions.
- B. Permanently mark settings of valves, dampers, and other adjustment devices allowing settings to be restored. Set and lock memory stops.
- C. Mark on drawings the locations where traverse and other critical measurements were taken and cross reference the location in the final report.
- D. After adjustment, take measurements to verify balance has not been disrupted or that such disruption has been rectified.
- E. Leave systems in proper working order, replacing belt guards, closing access doors, closing doors to electrical switch boxes, and restoring thermostats to specified settings.

## 3.06 AIR SYSTEM PROCEDURE

- A. Adjust air handling and distribution systems to provide required or design supply, return, and exhaust air quantities.
- B. Make air quantity measurements in ducts by Pitot tube traverse of entire cross sectional area of duct.
- C. Measure air quantities at air inlets and outlets.
- D. Adjust distribution system to obtain uniform space temperatures free from objectionable drafts and noise.
- E. Use volume control devices to regulate air quantities only to extend that adjustments do not create objectionable air motion or sound levels. Effect volume control by duct internal devices such as dampers and splitters.
- F. Provide system schematic with required and actual air quantities recorded at each outlet or inlet.

# **3.07 SCOPE**

- A. Test, adjust, and balance the following:
  - 1. Air Inlets and Outlets.

# 3.08 MINIMUM DATA TO BE REPORTED

- A. Air Outlets:
  - 1. Location.
  - 2. Airflow, specified and actual.

## SECTION 230713 DUCT INSULATION

# PART 1 GENERAL

### 1.01 SECTION INCLUDES

A. Duct insulation.

### 1.02 RELATED REQUIREMENTS

A. Section 233100 - HVAC Ducts and Casings.

#### 1.03 REFERENCE STANDARDS

- A. ASTM C518 Standard Test Method for Steady-State Thermal Transmission Properties by Means of the Heat Flow Meter Apparatus; 2021.
- B. ASTM C553 Standard Specification for Mineral Fiber Blanket Thermal Insulation for Commercial and Industrial Applications; 2013 (Reapproved 2019).
- C. ASTM E84 Standard Test Method for Surface Burning Characteristics of Building Materials; 2023d.
- D. ASTM E96/E96M Standard Test Methods for Gravimetric Determination of Water Vapor Transmission Rate of Materials; 2023.
- E. UL 723 Standard for Test for Surface Burning Characteristics of Building Materials; Current Edition, Including All Revisions.

## 1.04 SUBMITTALS

- A. See Section 013300 Submittals for submittal procedures.
- B. Product Data: Provide product description, thermal characteristics, list of materials and thickness for each service, and locations.

### 1.05 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing products of the type specified in this section with not less than three years of documented experience.
- B. Applicator Qualifications: Company specializing in performing the type of work specified in this section, documented experience and approved by manufacturer.

### 1.06 DELIVERY, STORAGE, AND HANDLING

- A. Accept materials on site in original factory packaging, labelled with manufacturer's identification, including product density and thickness.
- B. Protect insulation from weather and construction traffic, dirt, water, chemical, and mechanical damage, by storing in original wrapping.

### 1.07 FIELD CONDITIONS

- A. Maintain ambient temperatures and conditions required by manufacturers of adhesives, mastics, and insulation cements.
- B. Maintain temperature during and after installation for minimum period of 24 hours.

### PART 2 PRODUCTS

## 2.01 REGULATORY REQUIREMENTS

A. Surface Burning Characteristics: Flame spread index/Smoke developed index of 25/50, maximum, when tested in accordance with ASTM E84 or UL 723.

### 2.02 GLASS FIBER, FLEXIBLE

- A. Manufacturer:
  - 1. Johns Manville: www.jm.com.
  - 2. Knauf Insulation: www.knaufinsulation.com.

### **Duct Insulation**

- 3. Owens Corning Corporation: www.ocbuildingspec.com.
- B. Insulation: ASTM C553; flexible, noncombustible blanket.
  - 1. K value: 0.25 at 75 degrees F, when tested in accordance with ASTM C518.
- C. Vapor Barrier Jacket:
  - 1. Kraft paper with glass fiber yarn and bonded to aluminized film.
  - 2. Moisture Vapor Permeability: 0.02 perm inch, when tested in accordance with ASTM E96/E96M.
  - 3. Secure with pressure-sensitive tape.
- D. Vapor Barrier Tape:
  - Kraft paper reinforced with glass fiber yarn and bonded to aluminized film, with pressure-sensitive rubber-based adhesive.
- E. Indoor Vapor Barrier Mastic:
  - . Vinyl emulsion type acrylic or mastic, compatible with insulation, black color.
- F. Tie Wire: Annealed steel, 16 gauge, 0.0508 inch diameter.

## PART 3 EXECUTION

## 3.01 EXAMINATION

- A. Test ductwork for design pressure prior to applying insulation materials.
- B. Verify that surfaces are clean, foreign material removed, and dry.

### 3.02 INSTALLATION

- A. Install in accordance with manufacturer's instructions.
- B. Install in accordance with NAIMA National Insulation Standards.
- C. Insulated Ducts Conveying Air Below Ambient Temperature:
  - 1. Provide insulation with vapor barrier jackets.
  - 2. Finish with tape and vapor barrier jacket.
  - 3. Continue insulation through walls, sleeves, hangers, and other duct penetrations.
  - 4. Insulate entire system, including fittings, joints, flanges, fire dampers, flexible connections, and expansion joints.
- D. External Duct Insulation Application:
  - Secure insulation with vapor barrier with wires and seal jacket joints with vapor barrier adhesive or tape to match jacket.
  - 2. Install without sag on underside of duct. Use adhesive or mechanical fasteners where necessary to prevent sagging. Lift duct off trapeze hangers and insert spacers.
  - 3. Seal vapor barrier penetrations by mechanical fasteners with vapor barrier adhesive.
  - 4. Stop and point insulation around access doors and damper operators to allow operation without disturbing wrapping.

## 3.03 SCHEDULES

- A. Supply Ducts:
  - 1. Flexible Glass Fiber Duct Insulation: Installed R Value: R6

## SECTION 233100 HVAC DUCTS AND CASINGS

## PART 1 GENERAL

### 1.01 SECTION INCLUDES

- A. Metal ducts.
- B. Flexible ducts.

## 1.02 RELATED REQUIREMENTS

- A. Section 230713 Duct Insulation: External insulation.
- B. Section 233300 Air Duct Accessories.
- C. Section 233700 Air Outlets and Inlets.

## 1.03 REFERENCE STANDARDS

- A. ASTM A36/A36M Standard Specification for Carbon Structural Steel; 2019.
- B. ASTM A653/A653M Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process; 2023.
- C. ASTM E84 Standard Test Method for Surface Burning Characteristics of Building Materials; 2023d.
- D. NFPA 90A Standard for the Installation of Air-Conditioning and Ventilating Systems; 2024.
- E. NFPA 90B Standard for the Installation of Warm Air Heating and Air-Conditioning Systems; 2024.
- F. SMACNA (DCS) HVAC Duct Construction Standards Metal and Flexible; 2020.
- G. UL 181 Standard for Factory-Made Air Ducts and Air Connectors; Current Edition, Including All Revisions.

### 1.04 SUBMITTALS

- A. See Section 013300 Submittals for submittal procedures.
- B. Product Data: Provide data for Factory Insulated Flexible Duct.

### 1.05 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing the type of products specified in this section, with minimum three years of documented experience, and approved by manufacturer.
- B. Installer Qualifications: Company specializing in performing the type of work specified in this section, with minimum three years of documented experience.

## 1.06 FIELD CONDITIONS

- A. Do not install duct sealants when temperatures are less than those recommended by sealant manufacturers.
- B. Maintain temperatures within acceptable range during and after installation of duct sealants.

## PART 2 PRODUCTS

## 2.01 GENERAL REQUIREMENTS

- A. Provide UL Class 1 ductwork, fittings, hangers, supports, and appurtenances in accordance with NFPA 90A and SMACNA (DCS) guidelines unless stated otherwise.
- B. Provide metal duct unless otherwise indicated.
- C. Duct Shape and Material in accordance with Allowed Static Pressure Range:
  - 1. Round: Plus or minus 2 in-wc of galvanized steel.
  - 2. Rectangular: Plus or minus 2 in-wc of galvanized steel.
  - 3. Flexible Duct (Fabric and wire): Plus or minus 1 in-wc; see Section 233700.
- D. Duct Sealing and Leakage in accordance with Static Pressure Class:

## **HVAC Ducts and Casings**

- 1. Duct Pressure Class and Material for Common Mechanical Ventilation Applications:
  - a. Supply Air: 2 in-wc pressure class, galvanized steel.
  - b. General Exhaust Air: 1 in-wc pressure class, galvanized steel.
- 2. Low Pressure Service: Up to 2 in-wc:
  - a. Seal: Class C, apply to seal off transverse joints.
  - b. Leakage
    - 1) Rectangular: Class 24 or 24 cfm/100 sq ft.
    - 2) Round: Class 12 or 12 cfm/100 sq ft.

## E. Duct Fabrication Requirements:

- 1. Duct and Fitting Fabrication and Support: SMACNA (DCS) including specifics for continuously welded round and oval duct fittings.
- 2. Use reinforced and sealed sheet-metal materials at recommended gauges for indicated operating pressures or pressure class.
- 3. Construct tees, bends, and elbows with radius of not less than 1-1/2 times width of duct on centerline. Where not possible and where rectangular elbows must be used, provide airfoil turning vanes of perforated metal with glass fiber insulation.

### 2.02 METAL DUCTS

- A. Material Requirements:
  - 1. Galvanized Steel: Hot-dipped galvanized steel sheet, ASTM A653/A653M FS Type B, with G60/Z180 coating.
- B. Round Metal Ducts:
  - 1. Round Single Wall Duct: Round lock seam duct with galvanized steel outer wall.
  - Round Connection System: Interlocking duct connection system in accordance with SMACNA (DCS).
- C. Connectors, Fittings, Sealants, and Miscellaneous:
  - 1. Fittings: Manufacture with solid inner wall of perforated galvanized steel.
  - 2. Joint Sealers and Sealants: Non-hardening, water resistant, mildew and mold resistant.
    - a. Type: Heavy mastic or liquid used alone or with tape, suitable for joint configuration and compatible with substrates, and recommended by manufacturer for pressure class of ducts.
    - Surface Burning Characteristics: Flame spread index of zero and smoke developed index of zero, when tested in accordance with ASTM E84.
    - c. For Use with Flexible Ducts: UL labeled.
  - 3. Hanger Rod: ASTM A36/A36M; steel, galvanized; threaded both ends, threaded one end, or continuously threaded.

## 2.03 FLEXIBLE DUCTS

- A. Flexible Ducts: UL 181, Class 1, polyethylene film, mechanically fastened and rolled using galvanized steel to form spiral helix.
  - 1. Insulation: R4.2 insulation with polyethylene vapor barrier film.
  - 2. Pressure Rating: 10 in-wc positive and 5 in-wc negative.
  - 3. Maximum Velocity: 5500 fpm.
  - 4. Temperature Range: Minus 20 degrees F to 250 degrees F.
  - 5. Manufacturers:
    - a. Flexmaster USA, a brand of Masterduct, Inc: www.flexmasterusa.com.
    - b. JP Lamborn Co.: https://jplflex.com.
    - c. Thermaflex; a Flex-Tek Group Company: https://thermaflex.net.

## PART 3 EXECUTION

### 3.01 INSTALLATION

A. Install, support, and seal ducts in accordance with SMACNA (DCS).

- B. Install products following the manufacturer's instructions.
- C. Comply with safety standards NFPA 90A and NFPA 90B.
- D. During construction, provide temporary closures of metal or taped polyethylene on open ductwork to prevent construction dust from entering the ductwork system.
- E. Flexible Ducts: Connect to metal ducts with adhesive.
- F. Duct sizes indicated are precise inside dimensions.
- G. Use double nuts and lock washers on threaded rod supports.
- H. Connect diffusers or light troffer boots to low-pressure ducts directly or with 5 feet maximum length of flexible duct held in place with strap or clamp.
- Duct Accessories, Inlets, and Outlets: Interconnect as indicated in Sections 233300, and 233700.
- J. Duct Insulation: Provide duct insulation. See Section 230713.

## SECTION 233300 AIR DUCT ACCESSORIES

## PART 1 GENERAL

## 1.01 SECTION INCLUDES

A. Volume control dampers.

### 1.02 RELATED REQUIREMENTS

A. Section 233100 - HVAC Ducts and Casings.

### 1.03 REFERENCE STANDARDS

- A. NFPA 90A Standard for the Installation of Air-Conditioning and Ventilating Systems; 2024.
- B. SMACNA (DCS) HVAC Duct Construction Standards Metal and Flexible; 2020.

## 1.04 SUBMITTALS

- A. See Section 013300 Submittals for submittal procedures.
- B. Product Data: Provide for volume control dampers. Include connection requirements.

### 1.05 QUALITY ASSURANCE

A. Manufacturer Qualifications: Company specializing in manufacturing the type of products specified in this section, with minimum three years of documented experience.

### 1.06 DELIVERY, STORAGE, AND HANDLING

A. Protect dampers from damage to operating linkages and blades.

### **PART 2 PRODUCTS**

## 2.01 VOLUME CONTROL DAMPERS

- A. Manufacturers:
  - 1. Nailor Industries, Inc: www.nailor.com.
  - 2. Pottorff: www.pottorff.com.
  - 3. Ruskin Company: www.ruskin.com.
- B. Fabricate in accordance with SMACNA (DCS) and as indicated.
- C. Single Blade Dampers:
  - 1. Fabricate for duct sizes up to 6 by 30 inch.
  - 2. Blade: 24 gauge, 0.0239 inch, minimum.
- D. Quadrants:
  - 1. Provide locking, indicating quadrant regulators on single and multi-blade dampers.
  - 2. On insulated ducts mount quadrant regulators on stand-off mounting brackets, bases, or adapters.

### PART 3 EXECUTION

### 3.01 INSTALLATION

- A. Install accessories in accordance with manufacturer's instructions, NFPA 90A, and follow SMACNA (DCS). See Section 233100 for duct construction and pressure class.
- B. Provide balancing dampers at points on supply, return, and exhaust systems where branches are taken from larger ducts as required for air balancing. Install minimum two duct widths from duct take-off.

## SECTION 233700 AIR OUTLETS AND INLETS

## PART 1 GENERAL

### 1.01 SECTION INCLUDES

- A. Diffusers:
  - Perforated ceiling diffusers.
- B. Rectangular ceiling diffusers.

### 1.02 REFERENCE STANDARDS

A. ASHRAE Std 70 - Method of Testing the Performance of Air Outlets and Air Inlets; 2023.

### 1.03 SUBMITTALS

- A. See Section 013300 Submittals for submittal procedures.
- B. Product Data: Provide data for equipment required for this project. Review outlets and inlets as to size, finish, and type of mounting prior to submission. Submit schedule of outlets and inlets showing type, size, location, application, and noise level.

## 1.04 QUALITY ASSURANCE

- A. Test and rate air outlet and inlet performance in accordance with ASHRAE Std 70.
- B. Manufacturer Qualifications: Company specializing in manufacturing the type of products specified in this section, with minimum three years of documented experience.

### PART 2 PRODUCTS

### 2.01 MANUFACTURERS

- A. Krueger-HVAC: www.krueger-hvac.com.
- B. Price Industries: www.priceindustries.com.
- C. Titus, a brand of Air Distribution Technologies: www.titus-hvac.com.

### 2.02 RECTANGULAR CEILING DIFFUSERS

- A. Type: Provide square formed smooth face plaque ceiling diffusers constructed to maintain 360 degree discharge air pattern.
- B. Frame: Provide inverted T-bar type.
- C. Fabrication: Steel with baked enamel finish.
- D. Color: As indicated on drawings.

## 2.03 PERFORATED FACE CEILING DIFFUSERS

- A. Type: Perforated face.
- B. Frame: Inverted T-bar type.
- C. Fabrication: Steel with steel frame and baked enamel finish.
- D. Color: As indicated on drawings.

## PART 3 EXECUTION

### 3.01 INSTALLATION

- A. Install in accordance with manufacturer's instructions.
- B. Check location of outlets and inlets and make necessary adjustments in position to comply with architectural features, symmetry, and lighting arrangement.
- C. Install diffusers to ductwork with air tight connection.

# 3.02 PROTECTION

- A. Protect installed products until completion of project.
- B. Replace, repair, or touch-up damaged products before Substantial Completion.

## SECTION 260519 LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES

## PART 1 GENERAL

## 1.01 SECTION INCLUDES

- A. Single conductor building wire.
- B. Metal-clad cable.
- C. Wiring connectors.
- D. Electrical tape.
- E. Heat shrink tubing.
- F. Wire pulling lubricant.
- G. Cable ties.

## 1.02 RELATED REQUIREMENTS

A. Section 260526 - Grounding and Bonding for Electrical Systems: Additional requirements for grounding conductors and grounding connectors.

#### 1.03 REFERENCE STANDARDS

- A. ASTM B3 Standard Specification for Soft or Annealed Copper Wire; 2013 (Reapproved 2018).
- B. ASTM B8 Standard Specification for Concentric-Lay-Stranded Copper Conductors, Hard, Medium-Hard, or Soft; 2023.
- C. ASTM B787/B787M Standard Specification for 19 Wire Combination Unilay-Stranded Copper Conductors for Subsequent Insulation; 2004 (Reapproved 2020).
- D. ASTM D3005 Standard Specification for Low-Temperature Resistant Vinyl Chloride Plastic Pressure-Sensitive Electrical Insulating Tape; 2017.
- E. ASTM D4388 Standard Specification for Nonmetallic Semi-Conducting and Electrically Insulating Rubber Tapes; 2020.
- F. NECA 1 Standard for Good Workmanship in Electrical Construction; 2023.
- G. NECA 120 Standard for Installing Armored Cable (AC) and Type Metal-Clad (MC) Cable; 2018.
- H. NEMA WC 70 Power Cables Rated 2000 Volts or Less for the Distribution of Electrical Energy; 2021.
- NETA ATS Standard For Acceptance Testing Specifications For Electrical Power Equipment And Systems; 2021.
- J. NFPA 70 National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- K. UL 44 Thermoset-Insulated Wires and Cables; Current Edition, Including All Revisions.
- L. UL 83 Thermoplastic-Insulated Wires and Cables; Current Edition, Including All Revisions.
- M. UL 267 Outline of Investigation for Wire-Pulling Compounds; Current Edition, Including All Revisions.
- N. UL 486A-486B Wire Connectors; Current Edition, Including All Revisions.
- O. UL 486C Splicing Wire Connectors; Current Edition, Including All Revisions.
- P. UL 486D Sealed Wire Connector Systems; Current Edition, Including All Revisions.
- Q. UL 510 Polyvinyl Chloride, Polyethylene, and Rubber Insulating Tape; Current Edition, Including All Revisions.
- R. UL 1569 Metal-Clad Cables; Current Edition, Including All Revisions.

## 1.04 ADMINISTRATIVE REQUIREMENTS

### A. Coordination:

- Coordinate sizes of raceways, boxes, and equipment enclosures installed under other sections with the actual conductors to be installed, including adjustments for conductor sizes increased for voltage drop.
- 2. Coordinate with electrical equipment installed under other sections to provide terminations suitable for use with the conductors to be installed.
- 3. Notify Engineer of any conflicts with or deviations from Contract Documents. Obtain direction before proceeding with work.

## 1.05 QUALITY ASSURANCE

A. Comply with requirements of NFPA 70.

### 1.06 DELIVERY, STORAGE, AND HANDLING

A. Receive, inspect, handle, and store conductors and cables in accordance with manufacturer's instructions.

## 1.07 FIELD CONDITIONS

A. Do not install or otherwise handle thermoplastic-insulated conductors at temperatures lower than 14 degrees F, unless otherwise permitted by manufacturer's instructions. When installation below this temperature is unavoidable, notify Engineer and obtain direction before proceeding with work.

### PART 2 PRODUCTS

## 2.01 CONDUCTOR AND CABLE APPLICATIONS

- A. Do not use conductors and cables for applications other than as permitted by NFPA 70 and product listing.
- B. Provide single conductor building wire installed in suitable raceway unless otherwise indicated, permitted, or required.
- C. Metal-clad cable is permitted only as follows:
  - 1. Where not otherwise restricted, may be used:
    - a. Where concealed above accessible ceilings for final connections from junction boxes to luminaires.
      - 1) Maximum Length: 6 feet.
    - b. Where concealed in hollow stud walls and above accessible ceilings for branch circuits up to 20 A.
      - Exception: Provide single conductor building wire in raceway for circuit homerun from first outlet to panelboard.
  - 2. In addition to other applicable restrictions, may not be used:
    - a. Where exposed to damage.
    - b. For damp, wet, or corrosive locations.

### 2.02 CONDUCTOR AND CABLE GENERAL REQUIREMENTS

- A. Provide products that comply with requirements of NFPA 70.
- B. Provide products listed, classified, and labeled as suitable for the purpose intended.
- C. Unless specifically indicated to be excluded, provide all required conduit, boxes, wiring, connectors, etc. as required for a complete operating system.
- D. Comply with NEMA WC 70.
- E. Thermoplastic-Insulated Conductors and Cables: Listed and labeled as complying with UL 83.
- F. Thermoset-Insulated Conductors and Cables: Listed and labeled as complying with UL 44.
- G. Conductors for Grounding and Bonding: Also comply with Section 260526.

- H. Conductors and Cables Installed Exposed in Spaces Used for Environmental Air (only where specifically permitted): Plenum rated, listed and labeled as suitable for use in return air plenums.
- I. Conductor Material:
  - 1. Provide copper conductors only. Aluminum conductors are not acceptable for this project. Conductor sizes indicated are based on copper.
  - 2. Copper Conductors: Soft drawn annealed, 98 percent conductivity, uncoated copper conductors complying with ASTM B3, ASTM B8, or ASTM B787/B787M unless otherwise indicated.
- J. Minimum Conductor Size:
  - 1. Branch Circuits: 12 AWG.
    - a. Exceptions:
      - 1) 20 A, 120 V circuits longer than 75 feet: 10 AWG, for voltage drop.
      - 2) 20 A, 120 V circuits longer than 150 feet: 8 AWG, for voltage drop.
- K. Where conductor size is not indicated, size to comply with NFPA 70 but not less than applicable minimum size requirements specified.
- L. Conductor Color Coding:
  - Color code conductors as indicated unless otherwise required by the authority having jurisdiction.
     Maintain consistent color coding throughout project.
  - 2. Color Coding Method: Integrally colored insulation.
  - 3. Color Code:
    - a. 480Y/277 V, 3 Phase, 4 Wire System:
      - 1) Phase A: Brown.
      - 2) Phase B: Orange.
      - 3) Phase C: Yellow.
      - 4) Neutral/Grounded: Gray.
    - o. 208Y/120 V, 3 Phase, 4 Wire System:
      - 1) Phase A: Black.
      - 2) Phase B: Red.
      - 3) Phase C: Blue.
      - 4) Neutral/Grounded: White.
    - c. Equipment Ground, All Systems: Green.
    - d. For modifications or additions to existing wiring systems, comply with existing color code when existing code complies with NFPA 70 and is approved by the authority having jurisdiction.

## 2.03 SINGLE CONDUCTOR BUILDING WIRE

- A. Manufacturers:
  - 1. Copper Building Wire:
    - a. Cerro Wire LLC: www.cerrowire.com.
    - b. Encore Wire Corporation: www.encorewire.com.
    - c. General Cable Technologies Corporation: www.generalcable.com.
    - d. Southwire Company: www.southwire.com.
- B. Description: Single conductor insulated wire.
- C. Conductor Stranding:
  - 1. Feeders and Branch Circuits:
    - a. Size 10 AWG and Smaller: Solid.
    - b. Size 8 AWG and Larger: Stranded.
- D. Insulation Voltage Rating: 600 V.
- E. Insulation:
  - 1. Copper Building Wire: Type THHN/THWN or THHN/THWN-2.

### 2.04 METAL-CLAD CABLE

- A. Manufacturers:
  - 1. AFC Cable Systems Inc: www.afcweb.com.
  - 2. Encore Wire Corporation: www.encorewire.com.
  - 3. Southwire Company: www.southwire.com.
- B. Description: NFPA 70, Type MC cable listed and labeled as complying with UL 1569, and listed for use in classified firestop systems to be used.
- C. Conductor Stranding:
  - 1. Size 10 AWG and Smaller: Solid.
  - 2. Size 8 AWG and Larger: Stranded.
- D. Insulation Voltage Rating: 600 V.
- E. Insulation: Type THHN, THHN/THWN, or THHN/THWN-2.
- F. Grounding: Full-size integral equipment grounding conductor.
- G. Armor: Steel, interlocked tape.

## 2.05 WIRING CONNECTORS

- A. Description: Wiring connectors appropriate for the application, suitable for use with the conductors to be connected, and listed as complying with UL 486A-486B or UL 486C as applicable.
- B. Connectors for Grounding and Bonding: Comply with Section 260526.

### 2.06 ACCESSORIES

- A. Electrical Tape:
  - Vinyl Insulating Electrical Tape: Complying with ASTM D3005 and listed as complying with UL 510; minimum thickness of 7 mil; resistant to abrasion, corrosion, and sunlight; conformable for application down to 0 degrees F and suitable for continuous temperature environment up to 221 degrees F.
  - Rubber Splicing Electrical Tape: Ethylene Propylene Rubber (EPR) tape, complying with ASTM D4388; minimum thickness of 30 mil; suitable for continuous temperature environment up to 194 degrees F and short-term 266 degrees F overload service.
  - 3. Electrical Filler Tape: Rubber-based insulating moldable putty, minimum thickness of 125 mil; suitable for continuous temperature environment up to 176 degrees F.
  - 4. Varnished Cambric Electrical Tape: Cotton cambric fabric tape, with or without adhesive, oil-primed and coated with high-grade insulating varnish; minimum thickness of 7 mil; suitable for continuous temperature environment up to 221 degrees F.
  - 5. Moisture Sealing Electrical Tape: Insulating mastic compound laminated to flexible, all-weather vinyl backing; minimum thickness of 90 mil.
- B. Heat Shrink Tubing: Heavy-wall, split-resistant, with factory-applied adhesive; rated 600 V; suitable for direct burial applications; listed as complying with UL 486D.
- C. Wire Pulling Lubricant:
  - 1. Listed and labeled as complying with UL 267.
  - 2. Suitable for use with conductors/cables and associated insulation/jackets to be installed.
  - 3. Suitable for use at installation temperature.
- D. Cable Ties: Material and tensile strength rating suitable for application.

## PART 3 EXECUTION

### 3.01 EXAMINATION

- A. Verify that interior of building has been protected from weather.
- B. Verify that work likely to damage wire and cable has been completed.

- C. Verify that raceways, boxes, and equipment enclosures are installed and are properly sized to accommodate conductors and cables in accordance with NFPA 70.
- D. Verify that field measurements are as indicated.
- E. Verify that conditions are satisfactory for installation prior to starting work.

### 3.02 PREPARATION

A. Clean raceways thoroughly to remove foreign materials before installing conductors and cables.

### 3.03 INSTALLATION

- A. Circuiting Requirements:
  - 1. Unless dimensioned, circuit routing indicated is diagrammatic.
  - 2. When circuit destination is indicated without specific routing, determine exact routing required.
- B. Install products in accordance with manufacturer's instructions.
- C. Perform work in accordance with NECA 1 (general workmanship).
- D. Install metal-clad cable (Type MC) in accordance with NECA 120.
- E. Installation in Raceway:
  - 1. Tape ends of conductors and cables to prevent infiltration of moisture and other contaminants.
  - 2. Pull all conductors and cables together into raceway at same time.
  - 3. Do not damage conductors and cables or exceed manufacturer's recommended maximum pulling tension and sidewall pressure.
  - 4. Use suitable wire pulling lubricant where necessary, except when lubricant is not recommended by the manufacturer.
- F. Paralleled Conductors: Install conductors of the same length and terminate in the same manner.
- G. Secure and support conductors and cables in accordance with NFPA 70 using suitable supports and methods approved by the authority having jurisdiction. Provide independent support from building structure. Do not provide support from raceways, piping, ductwork, or other systems.
  - 1. Installation Above Suspended Ceilings: Do not provide support from ceiling support system. Do not provide support from ceiling grid or allow conductors and cables to lay on ceiling tiles.
- H. Terminate cables using suitable fittings.
  - 1. Metal-Clad Cable (Type MC):
    - a. Use listed fittings.
    - b. Cut cable armor only using specialized tools to prevent damaging conductors or insulation. Do not use hacksaw or wire cutters to cut armor.
- I. Install conductors with a minimum of 12 inches of slack at each outlet.
- J. Neatly train and bundle conductors inside boxes, wireways, panelboards and other equipment enclosures.
- K. Group or otherwise identify neutral/grounded conductors with associated ungrounded conductors inside enclosures in accordance with NFPA 70.
- L. Make wiring connections using specified wiring connectors.
  - 1. Make splices and taps only in accessible boxes. Do not pull splices into raceways or make splices in conduit bodies or wiring gutters.
  - 2. Remove appropriate amount of conductor insulation for making connections without cutting, nicking or damaging conductors.
  - 3. Do not remove conductor strands to facilitate insertion into connector.
  - 4. Clean contact surfaces on conductors and connectors to suitable remove corrosion, oxides, and other contaminates. Do not use wire brush on plated connector surfaces.
- M. Insulate splices and taps that are made with uninsulated connectors using methods suitable for the application, with insulation and mechanical strength at least equivalent to unspliced conductors.

- Dry Locations: Use insulating covers specifically designed for the connectors, electrical tape, or heat shrink tubing.
  - a. For taped connections, first apply adequate amount of rubber splicing electrical tape or electrical filler tape, followed by outer covering of vinyl insulating electrical tape.
- 2. Damp Locations: Use insulating covers specifically designed for the connectors, electrical tape, or heat shrink tubing.
  - For connections with insulating covers, apply outer covering of moisture sealing electrical tape.
  - b. For taped connections, follow same procedure as for dry locations but apply outer covering of moisture sealing electrical tape.
- N. Insulate ends of spare conductors using vinyl insulating electrical tape.
- O. Unless specifically indicated to be excluded, provide final connections to all equipment and devices, including those furnished by others, as required for a complete operating system.

## 3.04 FIELD QUALITY CONTROL

- A. Inspect and test in accordance with NETA ATS, except Section 4.
- B. Perform inspections and tests listed in NETA ATS, Section 7.3.2. The insulation resistance test is required for all conductors. The resistance test for parallel conductors listed as optional is not required.
- C. Correct deficiencies and replace damaged or defective conductors and cables.

## SECTION 260526 GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS

## PART 1 GENERAL

## 1.01 SECTION INCLUDES

- A. Grounding and bonding requirements.
- B. Conductors for grounding and bonding.
- C. Connectors for grounding and bonding.

## 1.02 RELATED REQUIREMENTS

A. Section 260519 - Low-Voltage Electrical Power Conductors and Cables: Additional requirements for conductors for grounding and bonding, including conductor color coding.

### 1.03 REFERENCE STANDARDS

- A. IEEE 81 IEEE Guide for Measuring Earth Resistivity, Ground Impedance, and Earth Surface Potentials of a Grounding System; 2012.
- B. NECA 1 Standard for Good Workmanship in Electrical Construction; 2023.
- C. NETA ATS Standard For Acceptance Testing Specifications For Electrical Power Equipment And Systems; 2021.
- D. NFPA 70 National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- E. UL 467 Grounding and Bonding Equipment; Current Edition, Including All Revisions.

### 1.04 QUALITY ASSURANCE

A. Comply with requirements of NFPA 70.

### 1.05 DELIVERY, STORAGE, AND HANDLING

A. Receive, inspect, handle, and store products in accordance with manufacturer's instructions.

## **PART 2 PRODUCTS**

## 2.01 GROUNDING AND BONDING REQUIREMENTS

- A. Do not use products for applications other than as permitted by NFPA 70 and product listing.
- B. Unless specifically indicated to be excluded, provide all required components, conductors, connectors, conduit, boxes, fittings, supports, accessories, etc. as necessary for a complete grounding and bonding system.
- C. Where conductor size is not indicated, size to comply with NFPA 70 but not less than applicable minimum size requirements specified.
- D. Grounding System Resistance:
  - Achieve specified grounding system resistance under normally dry conditions unless otherwise approved by Engineer. Precipitation within the previous 48 hours does not constitute normally dry conditions.
  - 2. Grounding Electrode System: Not greater than 5 ohms to ground, when tested according to IEEE 81 using "fall-of-potential" method.
  - 3. Between Grounding Electrode System and Major Electrical Equipment Frames, System Neutral, and Derived Neutral Points: Not greater than 0.5 ohms, when tested using "point-to-point" methods.
- E. Grounding Electrode System:
  - Provide connection to required and supplemental grounding electrodes indicated to form grounding electrode system.
    - a. Provide continuous grounding electrode conductors without splice or joint.

- b. Install grounding electrode conductors in raceway where exposed to physical damage. Bond grounding electrode conductor to metallic raceways at each end with bonding jumper.
- Provide additional ground electrode(s) as required to achieve specified grounding electrode system
  resistance.

#### 2.02 GROUNDING AND BONDING COMPONENTS

- A. General Requirements:
  - Provide products listed, classified, and labeled as suitable for the purpose intended.
  - 2. Provide products listed and labeled as complying with UL 467 where applicable.
- B. Conductors for Grounding and Bonding, in Addition to Requirements of Section 260526:
  - 1. Use insulated copper conductors unless otherwise indicated.
- C. Connectors for Grounding and Bonding:
  - 1. Description: Connectors appropriate for the application and suitable for the conductors and items to be connected; listed and labeled as complying with UL 467.
  - 2. Unless otherwise indicated, use mechanical connectors, compression connectors, or exothermic welded connections for accessible connections.

#### PART 3 EXECUTION

### 3.01 EXAMINATION

- A. Verify that work likely to damage grounding and bonding system components has been completed.
- B. Verify that field measurements are as indicated.
- C. Verify that conditions are satisfactory for installation prior to starting work.

### 3.02 INSTALLATION

- A. Install products in accordance with manufacturer's instructions.
- B. Perform work in accordance with NECA 1 (general workmanship).
- C. Make grounding and bonding connections using specified connectors.
  - Remove appropriate amount of conductor insulation for making connections without cutting, nicking or damaging conductors. Do not remove conductor strands to facilitate insertion into connector.
  - 2. Remove nonconductive paint, enamel, or similar coating at threads, contact points, and contact surfaces.
  - 3. Exothermic Welds: Make connections using molds and weld material suitable for the items to be connected in accordance with manufacturer's recommendations.
  - 4. Mechanical Connectors: Secure connections according to manufacturer's recommended torque settings.
  - 5. Compression Connectors: Secure connections using manufacturer's recommended tools and dies.

## 3.03 FIELD QUALITY CONTROL

- A. Inspect and test in accordance with NETA ATS except Section 4.
- B. Perform inspections and tests listed in NETA ATS, Section 7.13.
- C. Perform ground electrode resistance tests under normally dry conditions. Precipitation within the previous 48 hours does not constitute normally dry conditions.
- D. Investigate and correct deficiencies where measured ground resistances do not comply with specified requirements.

## SECTION 260529 HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

## PART 1 GENERAL

## 1.01 SECTION INCLUDES

A. Support and attachment requirements and components for equipment, conduit, cable, boxes, and other electrical work.

### 1.02 RELATED REQUIREMENTS

- A. Section 260533.13 Conduit for Electrical Systems: Additional support and attachment requirements for conduits.
- B. Section 260533.16 Boxes for Electrical Systems: Additional support and attachment requirements for boxes.
- Section 265100 Interior Lighting: Additional support and attachment requirements for interior luminaires.

### 1.03 REFERENCE STANDARDS

- A. ASTM A123/A123M Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products; 2017.
- B. ASTM A153/A153M Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware; 2023.
- C. ASTM B633 Standard Specification for Electrodeposited Coatings of Zinc on Iron and Steel; 2023.
- D. MFMA-4 Metal Framing Standards Publication; 2004.
- E. NECA 1 Standard for Good Workmanship in Electrical Construction; 2023.
- F. NFPA 70 National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

## 1.04 QUALITY ASSURANCE

A. Comply with NFPA 70

# 1.05 DELIVERY, STORAGE, AND HANDLING

A. Receive, inspect, handle, and store products in accordance with manufacturer's instructions.

### **PART 2 PRODUCTS**

## 2.01 SUPPORT AND ATTACHMENT COMPONENTS

- A. General Requirements:
  - 1. Comply with the following. Where requirements differ, comply with most stringent.
    - a. NFPA 70.
    - b. Applicable building code.
    - c. Requirements of authorities having jurisdiction.
  - 2. Provide required hangers, supports, anchors, fasteners, fittings, accessories, and hardware as necessary for complete installation of electrical work.
  - 3. Provide products listed, classified, and labeled as suitable for purpose intended, where applicable.
  - 4. Where support and attachment component types and sizes are not indicated, select in accordance with manufacturer's application criteria as required for load to be supported. Include consideration for vibration, equipment operation, and shock loads where applicable.
  - 5. Do not use products for applications other than as permitted by NFPA 70 and product listing.
  - 6. Steel Components: Use corrosion-resistant materials suitable for environment where installed.
    - Indoor Dry Locations: Use zinc-plated steel or approved equivalent unless otherwise indicated.
    - b. Zinc-Plated Steel: Electroplated in accordance with ASTM B633.

- Galvanized Steel: Hot-dip galvanized after fabrication in accordance with ASTM A123/A123M or ASTM A153/A153M.
- B. Conduit and Cable Supports: Straps and clamps suitable for conduit or cable to be supported.
  - 1. Conduit Straps: One-hole or two-hole type; steel or malleable iron.
  - 2. Conduit Clamps: Bolted type unless otherwise indicated.
- C. Outlet Box Supports: Hangers and brackets suitable for boxes to be supported.
- D. Metal Channel/Strut Framing Systems:
  - 1. Description: Factory-fabricated, continuous-slot, metal channel/strut and associated fittings, accessories, and hardware required for field assembly of supports.
  - 2. Comply with MFMA-4.
  - 3. Channel Material:
    - a. Indoor Dry Locations: Use painted steel, zinc-plated steel, or galvanized steel.
- E. Hanger Rods: Threaded, zinc-plated steel unless otherwise indicated.
- F. Anchors and Fasteners:
  - 1. Unless otherwise indicated and where not otherwise restricted, use anchor and fastener types indicated for specified applications.
  - 2. Hollow Stud Walls: Use toggle bolts.
  - 3. Steel: Use beam clamps, machine bolts, or welded threaded studs.
  - 4. Wood: Use wood screws.

### PART 3 EXECUTION

### 3.01 EXAMINATION

- A. Verify that field measurements are as indicated.
- B. Verify that mounting surfaces are ready to receive support and attachment components.
- C. Verify that conditions are satisfactory for installation prior to starting work.

### 3.02 INSTALLATION

- A. Install products in accordance with manufacturer's instructions.
- B. Install hangers and supports in accordance with NECA 1.
- C. Install anchors and fasteners in accordance with ICC Evaluation Services, LLC (ICC-ES) evaluation report conditions of use where applicable.
- D. Provide independent support from building structure. Do not provide support from piping, ductwork, or other systems.
- E. Do not provide support from suspended ceiling support system or ceiling grid.
- F. Do not provide support from roof deck.
- G. Do not penetrate or otherwise notch or cut structural members.
- H. Conduit Support and Attachment: See Section 260533.13 for additional requirements.
- I. Box Support and Attachment: See Section 260533.16 for additional requirements.
- J. Interior Luminaire Support and Attachment: See Section 265100 for additional requirements.
- K. Secure fasteners in accordance with manufacturer's recommended torque settings.
- L. Remove temporary supports.

# 3.03 FIELD QUALITY CONTROL

- A. Inspect support and attachment components for damage and defects.
- B. Repair cuts and abrasions in galvanized finishes using zinc-rich paint recommended by manufacturer. Replace components that exhibit signs of corrosion.

C. Correct deficiencies and replace damaged or defective support and attachment components. END OF SECTION

## SECTION 260533.13 CONDUIT FOR ELECTRICAL SYSTEMS

## PART 1 GENERAL

### 4.01 SECTION INCLUDES

- A. Intermediate metal conduit (IMC).
- B. Flexible metal conduit (FMC).
- C. Electrical metallic tubing (EMT).

## 4.02 RELATED REQUIREMENTS

- A. Section 260519 Low-Voltage Electrical Power Conductors and Cables: Cable assemblies consisting of conductors protected by integral metal armor.
- B. Section 260526 Grounding and Bonding for Electrical Systems.
- C. Section 260529 Hangers and Supports for Electrical Systems.
- D. Section 260533.16 Boxes for Electrical Systems.

## 4.03 REFERENCE STANDARDS

- A. ANSI C80.3 American National Standard for Electrical Metallic Tubing -- Steel (EMT-S); 2020.
- B. ANSI C80.6 American National Standard for Electrical Intermediate Metal Conduit; 2018.
- C. NECA 1 Standard for Good Workmanship in Electrical Construction; 2023.
- D. NECA 101 Standard for Installing Steel Conduits (Rigid, IMC, EMT); 2020.
- E. NEMA FB 1 Fittings, Cast Metal Boxes, and Conduit Bodies for Conduit, Electrical Metallic Tubing, and Cable; 2014.
- F. NFPA 70 National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- G. UL 1 Flexible Metal Conduit; Current Edition, Including All Revisions.
- H. UL 514B Conduit, Tubing, and Cable Fittings; Current Edition, Including All Revisions.
- I. UL 797 Electrical Metallic Tubing-Steel; Current Edition, Including All Revisions.
- J. UL 1242 Electrical Intermediate Metal Conduit-Steel; Current Edition, Including All Revisions.
- K. UL 2419 Outline of Investigation for Electrically Conductive Corrosion Resistant Compounds; Current Edition, Including All Revisions.

## 4.04 QUALITY ASSURANCE

A. Comply with NFPA 70.

### 4.05 DELIVERY, STORAGE, AND HANDLING

A. Receive, inspect, handle, and store conduit and fittings in accordance with manufacturer's instructions.

### **PART 2 PRODUCTS**

## 5.01 CONDUIT APPLICATIONS

- A. Do not use conduit and associated fittings for applications other than as permitted by NFPA 70, manufacturer's instructions, and product listing.
- B. Unless otherwise indicated and where not otherwise restricted, use conduit types indicated for specified applications. Where more than one listed application applies, comply with most restrictive requirements.
- C. Concealed Within Hollow Stud Walls: Use rigid metal conduit (RMC), intermediate metal conduit (IMC), or electrical metallic tubing (EMT).
- D. Concealed Above Accessible Ceilings: Use rigid metal conduit (RMC), intermediate metal conduit (IMC), or electrical metallic tubing (EMT).

Conduit for Electrical Systems

- E. Flexible Connections to Vibrating Equipment:
  - 1. Maximum Length: 6 feet unless otherwise indicated.
- F. Fished in Existing Walls, Where Necessary: Use flexible metal conduit (FMC) or electrical metallic tubing (EMT).

## 5.02 CONDUIT - GENERAL REQUIREMENTS

- A. Comply with NFPA 70.
- B. Existing Work: Where existing conduits are indicated to be reused, they may be reused only where they comply with specified requirements, are free from corrosion, and integrity is verified by pulling mandrel through them.
- C. Provide conduit, fittings, supports, and accessories required for complete raceway system.
- D. Provide products listed, classified, and labeled as suitable for purpose intended.
- E. Minimum Conduit Size, Unless Otherwise Indicated:
  - 1. Branch Circuits: 1/2-inch trade size.
  - 2. Branch Circuit Homeruns: 3/4-inch trade size.
- F. Where conduit size is not indicated, size to comply with NFPA 70 but not less than applicable minimum size requirements specified.

## 5.03 INTERMEDIATE METAL CONDUIT (IMC)

- A. Description: NFPA 70, Type IMC intermediate metal conduit complying with ANSI C80.6 and listed and labeled as complying with UL 1242.
- B. Fittings:
  - 1. Nonhazardous Locations: Use fittings complying with NEMA FB 1 and listed and labeled as complying with UL 514B or UL 1242.
  - 2. Material: Use steel or malleable iron.
  - 3. Connectors and Couplings: Use threaded type fittings only. Threadless fittings, including set screw and compression/gland types, are not permitted.

## 5.04 FLEXIBLE METAL CONDUIT (FMC)

- A. Description: NFPA 70, Type FMC standard-wall steel flexible metal conduit listed and labeled as complying with UL 1, and listed for use in classified firestop systems.
- B. Fittings:
  - 1. Description: Fittings complying with NEMA FB 1 and listed and labeled as complying with UL 514B.
  - 2. Material: Use steel or malleable iron.
    - a. Do not use die cast zinc fittings.

## 5.05 ELECTRICAL METALLIC TUBING (EMT)

- A. Description: NFPA 70, Type EMT galvanized steel electrical metallic tubing complying with ANSI C80.3 and listed and labeled as complying with UL 797.
- B. Fittings:
  - Description: Fittings complying with NEMA FB 1 and listed and labeled as complying with UL 514B.
  - 2. Material: Use steel or malleable iron.
    - a. Do not use die cast zinc fittings.
  - 3. Connectors and Couplings: Use compression/gland or set-screw type.
    - a. Do not use indenter type connectors and couplings.

## 5.06 ACCESSORIES

A. Conduit Joint Compound: Corrosion-resistant, electrically conductive compound listed as complying with UL 2419; suitable for use with conduit to be installed.

Conduit for Electrical Systems

B. Pull Strings: Use nylon or polyester tape with average breaking strength of not less than 1,250 lbf.

## PART 3 EXECUTION

### 6.01 EXAMINATION

- A. Verify that field measurements are as indicated.
- B. Verify that mounting surfaces are ready to receive conduits.
- C. Verify that conditions are satisfactory for installation prior to starting work.

### 6.02 INSTALLATION

- A. Install products in accordance with manufacturer's instructions.
- B. Install conduit in accordance with NECA 1.
- C. Intermediate Metal Conduit (IMC): Install in accordance with NECA 101.

### D. Conduit Routing:

- 1. Unless dimensioned, conduit routing indicated is diagrammatic.
- 2. When conduit destination is indicated without specific routing, determine exact routing required.
- 3. Conceal conduits unless specifically indicated to be exposed.
- 4. Arrange conduit to maintain adequate headroom, clearances, and access.

# E. Conduit Support:

- 1. Secure and support conduits in accordance with NFPA 70 using suitable supports and methods approved by authorities having jurisdiction; see Section 260529.
- 2. Provide independent support from building structure. Do not provide support from piping, ductwork, or other systems.
- 3. Installation Above Suspended Ceilings: Do not provide support from ceiling support system. Do not provide support from ceiling grid or allow conduits to lay on ceiling tiles.

### F. Connections and Terminations:

- 1. Use approved zinc-rich paint or conduit joint compound on field-cut threads of galvanized steel conduits prior to making connections.
- 2. Where two threaded conduits must be joined and neither can be rotated, use three-piece couplings or split couplings. Do not use running threads.
- 3. Use suitable adapters where required to transition from one type of conduit to another.
- 4. Terminate threaded conduits in boxes and enclosures using threaded hubs or double lock nuts for dry locations and raintight hubs for wet locations.
- 5. Provide insulating bushings, insulated throats, or listed metal fittings with smooth, rounded edges at conduit terminations to protect conductors.
- 6. Secure joints and connections to provide mechanical strength and electrical continuity.

### G. Penetrations:

- 1. Do not penetrate or otherwise notch or cut structural members, including footings and grade beams.
- 2. Make penetrations perpendicular to surfaces unless otherwise indicated.
- 3. Provide sleeves for penetrations as indicated or as required to facilitate installation. Set sleeves flush with exposed surfaces unless otherwise indicated or required.
- H. Conduit Movement Provisions: Where conduits are subject to movement, provide expansion and expansion/deflection fittings to prevent damage to enclosed conductors or connected equipment. This includes, but is not limited to:
  - 1. Where conduits cross structural joints intended for expansion, contraction, or deflection.

## I. Conduit Sealing:

- 1. Where conduits cross barriers between areas of potential substantial temperature differential, use foam conduit sealant at accessible point near penetration to prevent condensation. This includes, but is not limited to:
  - a. Where conduits pass from outdoors into conditioned interior spaces.

- b. Where conduits pass from unconditioned interior spaces into conditioned interior spaces.
- J. Provide pull string in each empty conduit and in conduits where conductors and cables are to be installed by others. Leave minimum slack of 12 inches at each end.
- K. Provide grounding and bonding; see Section 260526.

## 6.03 FIELD QUALITY CONTROL

- A. Repair cuts and abrasions in galvanized finishes using zinc-rich paint recommended by manufacturer. Replace components that exhibit signs of corrosion.
- B. Correct deficiencies and replace damaged or defective conduits.

## 6.04 CLEANING

A. Clean interior of conduits to remove moisture and foreign matter.

## 6.05 PROTECTION

A. Immediately after installation of conduit, use suitable manufactured plugs to provide protection from entry of moisture and foreign material and do not remove until ready for installation of conductors.

# SECTION 260533.16 BOXES FOR ELECTRICAL SYSTEMS

## PART 1 GENERAL

### 1.01 SECTION INCLUDES

A. Outlet and device boxes up to 100 cubic inches, including those used as junction and pull boxes.

### 1.02 RELATED REQUIREMENTS

- A. Section 260529 Hangers and Supports for Electrical Systems.
- B. Section 260533.13 Conduit for Electrical Systems:
  - Conduit bodies and other fittings.
  - 2. Additional requirements for locating boxes to limit conduit length and/or number of bends between pulling points.
- C. Section 260553 Identification for Electrical Systems: Identification products and requirements.
- D. Section 262726 Wiring Devices:
  - 1. Additional requirements for locating boxes for wiring devices.

### 1.03 REFERENCE STANDARDS

- A. NECA 1 Standard for Good Workmanship in Electrical Construction; 2023.
- B. NECA 130 Standard for Installing and Maintaining Wiring Devices; 2016.
- C. NEMA FB 1 Fittings, Cast Metal Boxes, and Conduit Bodies for Conduit, Electrical Metallic Tubing, and Cable; 2014.
- D. NEMA OS 1 Sheet-Steel Outlet Boxes, Device Boxes, Covers, and Box Supports; 2013 (Reaffirmed 2020).
- E. NFPA 70 National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- F. UL 514A Metallic Outlet Boxes; Current Edition, Including All Revisions.

## 1.04 ADMINISTRATIVE REQUIREMENTS

#### A. Coordination:

- 1. Coordinate the work with other trades to avoid placement of ductwork, piping, equipment, or other potential obstructions within the dedicated equipment spaces and working clearances for electrical equipment required by NFPA 70.
- 2. Coordinate arrangement of electrical equipment with the dimensions and clearance requirements of the actual equipment to be installed.
- 3. Coordinate minimum sizes of boxes with the actual installed arrangement of conductors, clamps, support fittings, and devices, calculated according to NFPA 70.
- 4. Coordinate minimum sizes of pull boxes with the actual installed arrangement of connected conduits, calculated according to NFPA 70.
- 5. Coordinate the placement of boxes with millwork, furniture, devices, equipment, etc. installed under other sections or by others.
- 6. Coordinate the work with other trades to preserve insulation integrity.
- 7. Coordinate the work with other trades to provide walls suitable for installation of flush-mounted boxes where indicated.
- 8. Notify Engineer of any conflicts with or deviations from Contract Documents. Obtain direction before proceeding with work.

### 1.05 QUALITY ASSURANCE

A. Comply with requirements of NFPA 70.

### 1.06 DELIVERY, STORAGE, AND HANDLING

A. Receive, inspect, handle, and store products in accordance with manufacturer's instructions.

### **PART 2 PRODUCTS**

#### **2.01 BOXES**

- A. General Requirements:
  - 1. Do not use boxes and associated accessories for applications other than as permitted by NFPA 70 and product listing.
  - 2. Provide all boxes, fittings, supports, and accessories required for a complete raceway system and to accommodate devices and equipment to be installed.
  - 3. Provide products listed, classified, and labeled as suitable for the purpose intended.
  - 4. Where box size is not indicated, size to comply with NFPA 70 but not less than applicable minimum size requirements specified.
  - 5. Provide grounding terminals within boxes where equipment grounding conductors terminate.
- B. Outlet and Device Boxes Up to 100 cubic inches, Including Those Used as Junction and Pull Boxes:
  - 1. Use sheet-steel boxes for dry locations unless otherwise indicated or required.
  - 2. Use cast iron boxes or cast aluminum boxes for damp or wet locations unless otherwise indicated or required; furnish with compatible weatherproof gasketed covers.
  - 3. Use raised covers suitable for the type of wall construction and device configuration where required.
  - 4. Use shallow boxes where required by the type of wall construction.
  - 5. Do not use "through-wall" boxes designed for access from both sides of wall.
  - 6. Sheet-Steel Boxes: Comply with NEMA OS 1, and list and label as complying with UL 514A.
  - Cast Metal Boxes: Comply with NEMA FB 1, and list and label as complying with UL 514A; furnish with threaded hubs.
  - 8. Boxes for Supporting Luminaires and Ceiling Fans: Listed as suitable for the type and weight of load to be supported; furnished with fixture stud to accommodate mounting of luminaire where required.
  - 9. Boxes for Ganged Devices: Use multigang boxes of single-piece construction. Do not use field-connected gangable boxes unless specifically indicated or permitted.
  - 10. Minimum Box Size, Unless Otherwise Indicated:
    - a. Wiring Devices (Other Than Communications Systems Outlets): 4 inch square by 1-1/2 inch deep (100 by 38 mm) trade size.
    - b. Ceiling Outlets: 4 inch octagonal or square by 1-1/2 inch deep (100 by 38 mm) trade size.

### PART 3 EXECUTION

### 3.01 EXAMINATION

- A. Verify that field measurements are as indicated.
- B. Verify that mounting surfaces are ready to receive boxes.
- C. Verify that conditions are satisfactory for installation prior to starting work.

### 3.02 INSTALLATION

- A. Install products in accordance with manufacturer's instructions.
- B. Install boxes in accordance with NECA 1 (general workmanship) and, where applicable, NECA 130, including mounting heights specified in those standards where mounting heights are not indicated.
- Arrange equipment to provide minimum clearances in accordance with manufacturer's instructions and NFPA 70.
- D. Box Locations:
  - 1. Unless dimensioned, box locations indicated are approximate.
  - 2. Locate boxes as required for devices installed under other sections or by others.

- a. Switches, Receptacles, and Other Wiring Devices: Comply with Section 262726.
- 3. Locate boxes so that wall plates do not span different building finishes.
- 4. Locate junction and pull boxes as indicated, as required to facilitate installation of conductors, and to limit conduit length and/or number of bends between pulling points in accordance with Section 260533.13.

## E. Box Supports:

- 1. Secure and support boxes in accordance with NFPA 70 and Section 260529 using suitable supports and methods approved by the authority having jurisdiction.
- 2. Provide independent support from building structure except for cast metal boxes (other than boxes used for fixture support) supported by threaded conduit connections in accordance with NFPA 70. Do not provide support from piping, ductwork, or other systems.
- 3. Installation Above Suspended Ceilings: Do not provide support from ceiling grid or ceiling support system.
- F. Install boxes plumb and level.
- G. Install boxes as required to preserve insulation integrity.
- H. Close unused box openings.
- I. Install blank wall plates on junction boxes and on outlet boxes with no devices or equipment installed or designated for future use.
- J. Provide grounding and bonding in accordance with Section 260526.
- K. Identify boxes in accordance with Section 260553.

### 3.03 CLEANING

A. Clean interior of boxes to remove dirt, debris, plaster and other foreign material.

### 3.04 PROTECTION

A. Immediately after installation, protect boxes from entry of moisture and foreign material until ready for installation of conductors.

# SECTION 260583 WIRING CONNECTIONS

## PART 1 GENERAL

### 1.01 SECTION INCLUDES

A. Electrical connections to equipment.

### 1.02 REFERENCE STANDARDS

A. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

### 1.03 QUALITY ASSURANCE

A. Comply with requirements of NFPA 70.

## **PART 2 PRODUCTS**

## 2.01 EQUIPMENT CONNECTIONS

- A. Luminaires:
  - 1. Electrical Connection: Flexible conduit.
  - 2. Voltage: 277 volts, 1 phase, 60 Hz.
  - 3. Branch Circuit: 20 ampere breaker, maximum.

### PART 3 EXECUTION

### 3.01 EXAMINATION

A. Verify that equipment is ready for electrical connection, wiring, and energization.

## 3.02 ELECTRICAL CONNECTIONS

- A. Make electrical connections in accordance with equipment manufacturer's instructions.
- B. Make conduit connections to equipment using flexible conduit. Use liquidtight flexible conduit with watertight connectors in damp or wet locations.
- C. Install interconnecting conduit and wiring between devices and equipment to complete equipment wiring requirements.

## SECTION 262726 WIRING DEVICES

# PART 1 GENERAL

### 1.01 SECTION INCLUDES

- A. Wall switches.
- B. Wall dimmers.
- C. Receptacles.
- D. Wall plates and covers.

## 1.02 RELATED REQUIREMENTS

A. Section 260533.16 - Boxes for Electrical Systems.

### 1.03 REFERENCE STANDARDS

- A. FS W-C-596 Connector, Electrical, Power, General Specification for; 2014h (Validated 2022).
- B. FS W-S-896 Switches, Toggle (Toggle and Lock), Flush Mounted (General Specification); 2017g (Validated 2023).
- C. NECA 1 Standard for Good Workmanship in Electrical Construction; 2023.
- D. NECA 130 Standard for Installing and Maintaining Wiring Devices; 2016.
- E. NEMA WD 1 General Color Requirements for Wiring Devices; 1999 (Reaffirmed 2020).
- F. NEMA WD 6 Wiring Devices Dimensional Specifications; 2021.
- G. NFPA 70 National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- H. UL 20 General-Use Snap Switches; Current Edition, Including All Revisions.
- I. UL 498 Attachment Plugs and Receptacles; Current Edition, Including All Revisions.
- J. UL 514D Cover Plates for Flush-Mounted Wiring Devices; Current Edition, Including All Revisions.
- K. UL 943 Ground-Fault Circuit-Interrupters; Current Edition, Including All Revisions.
- L. UL 1472 Solid-State Dimming Controls; Current Edition, Including All Revisions.

### 1.04 ADMINISTRATIVE REQUIREMENTS

#### A. Coordination:

- 1. Coordinate the placement of outlet boxes with millwork, furniture, equipment, etc. installed under other sections or by others.
- 2. Coordinate wiring device ratings and configurations with the electrical requirements of actual equipment to be installed.
- 3. Coordinate the installation and preparation of uneven surfaces, such as split face block, to provide suitable surface for installation of wiring devices.
- 4. Notify Engineer of any conflicts or deviations from Contract Documents to obtain direction prior to proceeding with work.

### B. Sequencing:

1. Do not install wiring devices until final surface finishes and painting are complete.

#### 1.05 SUBMITTALS

- A. See Section 013300 Submittals, for submittal procedures.
- B. Product Data: Provide manufacturer's catalog information showing dimensions, colors, and configurations.
- C. Operation and Maintenance Data:
  - 1. Wall Dimmers: Include information on operation and setting of presets.

### Wiring Devices

### 1.06 QUALITY ASSURANCE

- A. Comply with requirements of NFPA 70.
- B. Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum three years documented experience.
- C. Products: Listed, classified, and labeled as suitable for the purpose intended.

### PART 2 PRODUCTS

### 2.01 WIRING DEVICES - GENERAL REQUIREMENTS

- A. Provide wiring devices suitable for intended use with ratings adequate for load served.
- B. Wiring Device Finishes:
  - 1. Provide wiring device finishes as described below, unless otherwise indicated.
  - 2. Wiring Devices, Unless Otherwise Indicated: Gray with stainless steel wall plate.

### 2.02 WALL SWITCHES

- A. Wall Switches General Requirements: AC only, quiet operating, general-use snap switches with silver alloy contacts, complying with NEMA WD 1 and NEMA WD 6, and listed as complying with UL 20 and where applicable, FS W-S-896; types as indicated.
  - 1. Wiring Provisions: Terminal screws for side wiring and screw actuated binding clamp for back wiring with separate ground terminal screw.
- B. Standard Wall Switches: Industrial specification grade, 20 A, 120/277 V with standard toggle type switch actuator and maintained contacts.

#### 2.03 WALL DIMMERS

- A. Manufacturers:
  - 1. Leviton Manufacturing Company, Inc: www.leviton.com.
  - 2. Lutron Electronics Company, Inc: www.lutron.com.
  - 3. Pass & Seymour, a brand of Legrand North America, Inc: www.legrand.us.
- B. Wall Dimmers General Requirements: Solid-state with continuous full-range even control following square law dimming curve, integral radio frequency interference filtering, power failure preset memory, air gap switch accessible without removing wall plate, complying with NEMA WD 1 and NEMA WD 6, and listed as complying with UL 1472; types and ratings suitable for load controlled as indicated on the drawings.
- C. Control: Slide control type with separate on/off switch.

### 2.04 RECEPTACLES

- A. Receptacles General Requirements: Self-grounding, complying with NEMA WD 1 and NEMA WD 6, and listed as complying with UL 498, and where applicable, FS W-C-596; types as indicated. Where
  - 1. Wiring Provisions: Terminal screws for side wiring or screw actuated binding clamp for back wiring with separate ground terminal screw.
  - 2. NEMA configurations specified are according to NEMA WD 6.

### B. GFCI Receptacles:

- GFCI Receptacles General Requirements: Self-testing, with feed-through protection and light to indicate ground fault tripped condition and loss of protection; listed as complying with UL 943, class A.
  - a. Provide test and reset buttons of same color as device.
- 2. Standard GFCI Receptacles: Industrial specification grade, duplex, 20A, 125V, NEMA 5-20R, rectangular decorator style.

## 2.05 WALL PLATES AND COVERS

- A. Wall Plates: Comply with UL 514D.
  - 1. Configuration: One piece cover as required for quantity and types of corresponding wiring devices.

- 2. Size: Standard.
- 3. Screws: Metal with slotted heads finished to match wall plate finish.
- B. Stainless Steel Wall Plates: Brushed satin finish, Type 302 stainless steel.

## PART 3 EXECUTION

### 3.01 EXAMINATION

- A. Verify that field measurements are as indicated.
- B. Verify that outlet boxes are installed in proper locations and at proper mounting heights and are properly sized to accommodate devices and conductors in accordance with NFPA 70.
- C. Verify that wall openings are neatly cut and will be completely covered by wall plates.
- D. Verify that final surface finishes are complete, including painting.
- E. Verify that branch circuit wiring installation is completed, tested, and ready for connection to wiring devices.
- F. Verify that conditions are satisfactory for installation prior to starting work.

#### 3.02 PREPARATION

- A. Provide extension rings to bring outlet boxes flush with finished surface.
- B. Clean dirt, debris, plaster, and other foreign materials from outlet boxes.

### 3.03 INSTALLATION

- A. Perform work in accordance with NECA 1 (general workmanship) and, where applicable, NECA 130, including mounting heights specified in those standards unless otherwise indicated.
- B. Coordinate locations of outlet boxes provided under Section 260533.16 as required for installation of wiring devices provided under this section.
  - 1. Mounting Heights: Unless otherwise indicated, as follows:
    - a. Wall Switches: Match existing location.
    - b. Wall Dimmers: 48 inches above finished floor.
    - c. Receptacles: Unless otherwise indicated, match existing location.
  - 2. Orient outlet boxes for vertical installation of wiring devices unless otherwise indicated.
- C. Install wiring devices in accordance with manufacturer's instructions.
- D. Connect wiring devices by wrapping conductor clockwise 3/4 turn around screw terminal and tightening to proper torque specified by the manufacturer. Where present, do not use push-in pressure terminals that do not rely on screw-actuated binding.
- E. Unless otherwise indicated, connect wiring device grounding terminal to branch circuit equipment grounding conductor and to outlet box with bonding jumper.
- F. Provide GFCI receptacles with integral GFCI protection at each location indicated. Do not use feed-through wiring to protect downstream devices.
- G. Install wiring devices plumb and level with mounting yoke held rigidly in place.
- H. Install wall switches with OFF position down.
- I. Install wall dimmers to achieve full rating specified and indicated after derating for ganging as instructed by manufacturer.
- J. Do not share neutral conductor on branch circuits utilizing wall dimmers.
- K. Install vertically mounted receptacles with grounding pole on top and horizontally mounted receptacles with grounding pole on left.
- L. Install wall plates to fit completely flush to wall with no gaps and rough opening completely covered without strain on wall plate. Repair or reinstall improperly installed outlet boxes or improperly sized rough openings. Do not use oversized wall plates in lieu of meeting this requirement.

M. Install blank wall plates on junction boxes and on outlet boxes with no wiring devices installed or designated for future use.

## 3.04 FIELD QUALITY CONTROL

- A. Inspect each wiring device for damage and defects.
- B. Operate each wall dimmer with circuit energized to verify proper operation.
- C. Test each receptacle to verify operation and proper polarity.
- D. Test each GFCI receptacle for proper tripping operation according to manufacturer's instructions.
- E. Correct wiring deficiencies and replace damaged or defective wiring devices.

## 3.05 ADJUSTING

- A. Adjust devices and wall plates to be flush and level.
- B. Adjust presets for wall dimmers according to manufacturer's instructions as directed by Engineer.

### 3.06 CLEANING

A. Clean exposed surfaces to remove dirt, paint, or other foreign material and restore to match original factory finish.

## SECTION 265100 INTERIOR LIGHTING

### **PART 1 GENERAL**

### 1.01 SECTION INCLUDES

- A. Interior luminaires.
- B. Exit signs.
- C. Ballasts and drivers.

## 1.02 RELATED REQUIREMENTS

- A. Section 260529 Hangers and Supports for Electrical Systems.
- B. Section 260533.16 Boxes for Electrical Systems.

## 1.03 REFERENCE STANDARDS

- A. IES LM-79 Approved Method: Optical and Electrical Measurements of Solid-State Lighting Products; 2019.
- B. IES LM-80 Approved Method: Measuring Maintenance of Light Output Characteristics of Solid-State Light Sources; 2021.
- C. NECA 1 Standard for Good Workmanship in Electrical Construction; 2023.
- D. NECA/IESNA 500 Standard for Installing Indoor Lighting Systems; 2006.
- E. NEMA LE 4 Recessed Luminaires, Ceiling Compatibility; 2023.
- F. NFPA 70 National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- G. NFPA 101 Life Safety Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- H. UL 924 Emergency Lighting and Power Equipment; Current Edition, Including All Revisions.
- I. UL 1598 Luminaires; Current Edition, Including All Revisions.
- J. UL 8750 Light Emitting Diode (LED) Equipment for Use in Lighting Products; Current Edition, Including All Revisions.

### 1.04 ADMINISTRATIVE REQUIREMENTS

### A. Coordination:

- Coordinate the installation of luminaires with mounting surfaces installed under other sections or by others. Coordinate the work with placement of supports, anchors, etc. required for mounting. Coordinate compatibility of luminaires and associated trims with mounting surfaces at installed locations.
- 2. Coordinate the placement of luminaires with structural members, ductwork, piping, equipment, diffusers, fire suppression system components, and other potential conflicts installed under other sections or by others.
- 3. Coordinate the placement of exit signs with furniture, equipment, signage or other potential obstructions to visibility installed under other sections or by others.
- 4. Notify Engineer of any conflicts or deviations from Contract Documents to obtain direction prior to proceeding with work.

### 1.05 SUBMITTALS

- A. See Section 013300 Submittals, for submittal procedures.
- B. Product Data: Provide manufacturer's standard catalog pages and data sheets including detailed information on luminaire construction, dimensions, ratings, finishes, mounting requirements, listings, service conditions, photometric performance, installed accessories, and ceiling compatibility; include model number nomenclature clearly marked with all proposed features.

Interior Lighting

- 1. LED Luminaires:
  - a. Include estimated useful life, calculated based on IES LM-80 test data.
- C. Operation and Maintenance Data: Instructions for each product including information on replacement parts.

### 1.06 QUALITY ASSURANCE

- A. Comply with requirements of NFPA 70.
- B. Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum three years documented experience.

# 1.07 DELIVERY, STORAGE, AND PROTECTION

- A. Receive, handle, and store products according to NECA/IESNA 500 (commercial lighting) and manufacturer's written instructions.
- B. Keep products in original manufacturer's packaging and protect from damage until ready for installation.

### 1.08 FIELD CONDITIONS

A. Maintain field conditions within manufacturer's required service conditions during and after installation.

### 1.09 WARRANTY

- A. Provide 3-year manufacturer warranty for LED luminaires, including drivers.
- B. Provide 10-year pro-rata warranty for batteries for self-powered exit signs.

### **PART 2 PRODUCTS**

### 2.01 LUMINAIRE TYPES

A. Furnish products as indicated in luminaire schedule included on the drawings.

### 2.02 LUMINAIRES

- A. Manufacturers:
  - 1. Cooper Lighting, a division of Cooper Industries: www.cooperindustries.com.
  - 2. Hubbell Lighting, Inc: www.hubbelllighting.com.
  - 3. Philips Lighting North America Corporation: www.lightingproducts.philips.com.
- B. Provide products that comply with requirements of NFPA 70.
- C. Provide products that are listed and labeled as complying with UL 1598, where applicable.
- D. Provide products listed, classified, and labeled as suitable for the purpose intended.
- E. Unless otherwise indicated, provide complete luminaires including lamp(s) and all sockets, ballasts, reflectors, lenses, housings and other components required to position, energize and protect the lamp and distribute the light.
- F. Unless specifically indicated to be excluded, provide all required conduit, boxes, wiring, connectors, hardware, supports, trims, accessories, etc. as necessary for a complete operating system.
- G. Provide products suitable to withstand normal handling, installation, and service without any damage, distortion, corrosion, fading, discoloring, etc.
- H. Recessed Luminaires:
  - 1. Ceiling Compatibility: Comply with NEMA LE 4.
- I. LED Luminaires:
  - 1. Components: UL 8750 recognized or listed as applicable.
  - 2. Tested in accordance with IES LM-79 and IES LM-80.
  - 3. LED Estimated Useful Life: Minimum of 50,000 hours at 70 percent lumen maintenance, calculated based on IES LM-80 test data.

### 2.03 EXIT SIGNS

- A. Description: Exit signs complying with NFPA 101 and applicable state and local codes, and listed and labeled as complying with UL 924.
  - 1. Number of Faces: Single- or double-face as indicated or as required for installed location.
  - 2. Directional Arrows: As indicated or as required for installed location.
- B. Powered Exit Signs: Internally illuminated with LEDs unless otherwise indicated.
  - 1. Manufacturers:
    - a. Acuity Brands, Inc: www.acuitybrands.com.
    - b. Cooper Lighting, a division of Cooper Industries: www.cooperindustries.com.
    - c. Hubbell Lighting, Inc: https://www.hubbell.com/progresslighting/en.
    - d. Philips Lighting North America Corporation: www.lightingproducts.philips.com.
  - 2. Self-Powered Exit Signs:
    - a. Operation: Upon interruption of normal power source or brownout condition exceeding 20 percent voltage drop from nominal, solid-state control automatically switches connected lamps to integral battery power for minimum of 90 minutes of rated emergency illumination, and automatically recharges battery upon restoration of normal power source.
    - b. Diagnostics: Provide power status indicator light and accessible integral test switch to manually activate emergency operation.
    - c. Provide low-voltage disconnect to prevent battery damage from deep discharge.

### 2.04 BALLASTS AND DRIVERS

- A. LED Emergency Backup Driver General Requirements:
  - 1. Description: Backup power supply capable of providing power to light fixture for up to 90 minutes upon interruption of normal power.
  - 2. Operation: Upon interruption of normal power source, driver will switch to battery power for attached luminaire. The luminaire shall be illuminated for a minimum of 90 minutes. When power is restored, the driver shall switch the luminaire back to normal power.

### PART 3 EXECUTION

### 3.01 EXAMINATION

- A. Verify that field measurements are as indicated.
- B. Verify that outlet boxes are installed in proper locations and at proper mounting heights and are properly sized to accommodate conductors in accordance with NFPA 70.
- C. Verify that suitable support frames are installed where required.
- D. Verify that branch circuit wiring installation is completed, tested, and ready for connection to luminaires.
- E. Verify that conditions are satisfactory for installation prior to starting work.

## 3.02 PREPARATION

- A. Provide extension rings to bring outlet boxes flush with finished surface.
- B. Clean dirt, debris, plaster, and other foreign materials from outlet boxes.

### 3.03 INSTALLATION

- A. Coordinate locations of outlet boxes provided under Section 260533.16 as required for installation of luminaires provided under this section.
- B. Perform work in accordance with NECA 1 (general workmanship).
- C. Install products in accordance with manufacturer's instructions.
- D. Install luminaires securely, in a neat and workmanlike manner, as specified in NECA 500 (commercial lighting).
- E. Provide required support and attachment in accordance with Section 260529.

- F. Install luminaires plumb and square and aligned with building lines and with adjacent luminaires.
- G. Suspended Ceiling Mounted Luminaires:
  - 1. Do not use ceiling tiles to bear weight of luminaires.
  - 2. Do not use ceiling support system to bear weight of luminaires unless ceiling support system is certified as suitable to do so.
  - 3. Secure lay-in luminaires to ceiling support channels using listed safety clips at four corners.
  - 4. See appropriate Division 9 section where suspended grid ceiling is specified for additional requirements.

# H. Suspended Luminaires:

- 1. Install using the suspension method indicated, with support lengths and accessories as required for specified mounting height.
- I. Install accessories furnished with each luminaire.
- J. Bond products and metal accessories to branch circuit equipment grounding conductor.
- K. Exit Signs:
  - 1. Unless otherwise indicated, connect unit to unswitched power from circuit indicated. Bypass local switches, contactors, or other lighting controls.

## 3.04 FIELD QUALITY CONTROL

- A. Inspect each product for damage and defects.
- B. Operate each luminaire after installation and connection to verify proper operation.
- C. Test self-powered exit signs and emergency lighting units to verify proper operation upon loss of normal power supply.
- D. Correct wiring deficiencies and repair or replace damaged or defective products. Repair or replace excessively noisy ballasts as determined by Engineer.

### 3.05 ADJUSTING

A. Exit Signs with Field-Selectable Directional Arrows: Set as indicated or as required to properly designate egress path as directed by Engineer or authority having jurisdiction.

### 3.06 CLEANING

A. Clean surfaces according to NECA 500 (commercial lighting) and manufacturer's instructions to remove dirt, fingerprints, paint, or other foreign material and restore finishes to match original factory finish.

## 3.07 PROTECTION

A. Protect installed luminaires from subsequent construction operations.

# SECTION 284600 FIRE DETECTION AND ALARM

### PART 1 GENERAL

### 1.01 SECTION INCLUDES

A. Replacement and removal of existing fire alarm system components, wiring, and conduit indicated.

#### 1.02 REFERENCE STANDARDS

- A. NFPA 70 National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- B. NFPA 72 National Fire Alarm and Signaling Code; Most Recent Edition Cited by Referring Code or Reference Standard.

### 1.03 SUBMITTALS

- A. See Section 013300 Submittals for submittal procedures.
- B. Product Data: Provide manufacturer's standard catalog pages and data sheets including detailed information on construction, dimensions, ratings, finishes, mounting requirements, listings, service conditions, performance, installed accessories, and ceiling compatibility; include model number nomenclature clearly marked with all proposed features.

### 1.04 QUALITY ASSURANCE

- A. Installer Qualifications: Firm with minimum 3 years documented experience installing fire alarm systems of the specified type and providing contract maintenance service as a regular part of their business
  - 1. Installer Personnel: At least 2 years of experience installing fire alarm systems.
  - Supervisor: NICET level III or IV (3 or 4) certified fire alarm technician; furnish name and address.

#### 1.05 WARRANTY

A. Provide installer's warranty that the installation is free from defects and will remain so for 1 year after date of Substantial Completion.

#### **PART 2 PRODUCTS**

### 2.01 MANUFACTURERS

- A. Initiating Devices and Notification Appliances:
  - 1. Honeywell Security & Fire Solutions/Fire-Lite: www.firelite.com.
  - 2. Siemens Building Technologies, Inc: www.sbt.siemens.com.
  - 3. Simplex, a brand of Johnson Controls: www.simplex-fire.com.
  - 4. Gentex Corporation: https://fireprotection.gentex.com.

### 2.02 EXISTING COMPONENTS

A. Existing Fire Alarm System: Building has an existing fire alarm system. Cooridnate with Owner to turn Fire Alarm System off during demolition and renovation of components indicated on drawings. Ensure all new components are integrated into existing Fire Alarm System. Perform work such that fire alarm system is active overnight.

## 2.03 COMPONENTS

- A. Initiating Devices:
  - 1. Smoke Detectors: Provide and install as indicated on the project drawings and within this specification.
- B. Notification Appliances:
  - 1. Strobes: Provide and install as indicated on project drawings and within this specification.
- C. Circuit Conductors: Copper or optical fiber; provide 200 feet extra; color code and label.

Fire Detection and Alarm

### PART 3 EXECUTION

### 3.01 INSTALLATION

- A. Install in accordance with applicable codes, NFPA 72, NFPA 70, and Contract Documents.
- B. Conceal all wiring, conduit, boxes, and supports where installed in finished areas.

### 3.02 INSPECTION AND TESTING FOR COMPLETION

- A. Notify Owner 7 days prior to beginning completion inspections and tests.
- B. Provide the services of the installer's supervisor or person with equivalent qualifications to supervise inspection and testing, correction, and adjustments.
- C. Prepare for testing by ensuring that all work is complete and correct; perform preliminary tests as required.
- D. Provide all tools, software, and supplies required to accomplish inspection and testing.
- E. Perform inspection and testing in accordance with NFPA 72 and requirements of local authorities; document each inspection and test.
- F. Correct defective work, adjust for proper operation, and retest until entire system complies with Contract Documents.