


CASTLEWOOD STATE PARK STREAMBANK RESTORATION PHASE I (Ballwin, Missouri)

LOCATION MAP:



OWNER: STATE OF MISSOURI
MICHAEL L. PARSON,
GOVERNOR

DEPARTMENT OF
NATURAL RESOURCES

PROJECT
MANAGEMENT: OFFICE OF ADMINISTRATION
DIVISION OF FACILITIES MANAGEMENT,
DESIGN AND CONSTRUCTION

DESIGNER: STANTEC CONSULTING SERVICES, INC.

PROJECT NUMBER: X2002-01

SITE NUMBER: 5205
ASSET NUMBER: 7815205028



3/24/2020

SHEET NUMBER:

G-001

1 OF 16 SHEETS
MARCH 24, 2020



3/24/2020



10309 Timberwood Circle, Suite 100
Louisville, Kentucky 40223-3301
www.stantec.com

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawings - any errors or omissions shall be reported to Stantec without delay. Stantec is not responsible for any errors or omissions that may occur during construction or use for any purpose other than that authorized by Stantec's authorization.

OFFICE OF ADMINISTRATION
DIVISION OF FACILITIES
MANAGEMENT,
DESIGN AND CONSTRUCTION

DEPARTMENT OF
NATURAL RESOURCES

CASTLEWOOD STATE PARK
STREAMBANK RESTORATION
PHASE I

BALLWIN, MO

PROJECT # X2002-01
SITE # 5205
ASSET # 7815205028

REVISION: _____
DATE: _____
REVISION: _____
DATE: _____
REVISION: _____
DATE: _____
ISSUE DATE: 03/24/2020

CAD DWG FILE: G-002.dwg
DRAWN BY: DLH
CHECKED BY: OKR
DESIGNED BY: MAS

SHEET TITLE:
GENERAL NOTES

SHEET NUMBER:

G-002

2 OF 16 SHEETS
03/24/2020

GENERAL NOTES

- DEFINITIONS - WHENEVER THE FOLLOWING TERMS ARE USED IN THESE PLANS FOR CONSTRUCTION, IT IS UNDERSTOOD THAT THEY REPRESENT THE FOLLOWING:
 - CONSTRUCTION DOCUMENTS:** PLANS FOR CONSTRUCTION, CONSTRUCTION SPECIFICATIONS, COST ESTIMATE, AND ANY OTHER REFERENCED SPECIFICATIONS OR STANDARDS CONSTITUTE THE COMPLETE CONSTRUCTION DOCUMENTS FOR THIS PROJECT.
 - CONTRACTOR:** ENTITY RESPONSIBLE FOR CONSTRUCTION.
 - ENGINEER:** STANTEC CONSULTING SERVICES INC. (STANTEC)
 - OWNER:** CASTLEWOOD STATE PARK
 - RESPONSIBLE PARTY:** THE NATURE CONSERVANCY, MISSOURI CHAPTER
 - STORM WATER POLLUTION PREVENTION PLAN (SWPPP):** A PLAN REQUIRED BY THE LAND DISTURBANCE GENERAL PERMIT NO. MO-R100038 THAT INCLUDES SITE MAP(S), AN IDENTIFICATION OF CONSTRUCTION/CONTRACTOR ACTIVITIES THAT COULD CAUSE POLLUTANTS IN THE STORM WATER, AND A DESCRIPTION OF MEASURES OR PRACTICES TO CONTROL THESE POLLUTANTS.
 - BEST MANAGEMENT PRACTICES (BMP):** ANY PROGRAM, TECHNOLOGY, PROCESS, SITING CRITERIA, OPERATING METHOD, MEASURE, OR DEVICE THAT CONTROLS, PREVENTS, REMOVES, OR REDUCES POLLUTION.
 - DISTURBANCE LIMITS:** THE BOUNDARY WITHIN WHICH ALL CONSTRUCTION, MATERIALS STORAGE, AND ALL OTHER CONSTRUCTION ACTIVITIES SHALL OCCUR.
 - BANKFULL ELEVATION:** THE POINT OF INCIPENT FLOODING IN AN ALLUVIAL CHANNEL.
 - THALWEG:** THE LOWEST POINT OF THE BANKFULL CHANNEL. THIS ELEVATION IS THE REFERENCE FOR ALL ELEVATIONS ON OR ALONG THE CHANNEL AND HYDRAULIC STRUCTURES DESCRIBED IN THIS SECTION AND THROUGHOUT THE CONSTRUCTION DOCUMENTS.
 - ROOT WADS:** THE ROOT MASS OF A TREE AND ATTACHED TRUNK. ROOT WADS AND LOGS MAY BE HARVESTED FROM THE SITE AS APPROVED BY THE LAND OWNER. ROOT WADS OR LOGS MAY BE BROUGHT IN FROM OFF-SITE. HARVESTING SHALL BE EXECUTED IN A MANNER AS NOT TO LEAVE SIGNIFICANT VOIDS IN THE EXISTING RIPARIAN CORRIDOR.
- THESE DRAWINGS WERE PREPARED BY STANTEC USING PUBLICLY AVAILABLE LIDAR DATED 2011 AND AERIAL IMAGERY DATED 2016. THE MAJOR DISCREPANCIES BETWEEN THE TWO FORMS OF DATA IS DUE TO LATERAL BANK EROSION. STANTEC PERFORMED A GEOMORPHIC ASSESSMENT OF THE PROJECT AREA IN APRIL 2016. THE GEOMORPHIC ASSESSMENT INCLUDED A GROUND SURVEY OF THE TOP OF BANK AND THALWEG OF PORTIONS OF KIEFER CREEK IN AND/OR NEAR THE PROJECT AREA.
- FOR DESIGN PURPOSES, THE LIDAR WAS ADJUSTED TO AGREE WITH THE MORE RECENT AERIAL IMAGERY WITHIN THE PROPOSED WORK AREAS.
- SURVEY COORDINATES REFERENCES TO MISSOURI STATE PLAN EAST COORDINATE SYSTEM NAD83. ELEVATIONS ARE BASED ON NAVD88.
- ALL EXISTING TOPOGRAPHIC, DRAINAGE, ROADWAY, AND ANY OTHER EXISTING PLANIMETRIC DATA SHOWN ON THE PLANS ARE ONLY APPROXIMATE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FINAL VERIFICATION AND LOCATION.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR HEALTH AND SAFETY OF ITS PERSONNEL. THE CONTRACTOR SHALL ADHERE TO REQUIREMENTS FOR SAFETY AND CONSTRUCTION FROM OSHA UNLESS OTHER REGULATORY REQUIREMENTS ARE MORE STRINGENT AND/OR SUPERSEDE OSHA REQUIREMENTS.
- THE CONTRACTOR SHALL CONDUCT ALL OPERATIONS IN ACCORDANCE WITH APPLICABLE ENVIRONMENTAL PERMITS, RULES, LAWS, AND REGULATIONS.
- THE CONTRACTOR SHALL PERFORM REQUIRED UTILITY LOCATION SERVICES, SURVEY AND DOCUMENT THOSE LOCATIONS. AT THE TIME THESE PLANS FOR CONSTRUCTION WERE PREPARED THERE WERE NO KNOWN EXISTING UNDERGROUND OR ABOVE GROUND UTILITIES WITHIN THE PROJECT'S DISTURBANCE LIMITS. HOWEVER, THE CONTRACTOR IS RESPONSIBLE FOR DETERMINING THE LOCATION OF ALL UTILITIES. IF ANY, NOT SHOWN AND SHALL PROVIDE NECESSARY MEASURES TO PROTECT UTILITIES FROM DAMAGE DUE TO CONSTRUCTION ACTIVITIES. SHOULD CONDUITS OR OTHER UTILITIES THAT ARE NOT SHOWN ON THE DRAWINGS BE ENCOUNTERED, THE CONTRACTOR SHALL CONTACT THE OWNER IMMEDIATELY.
- THE CONTRACTOR SHALL CONSULT WITH THE ENGINEER TO IDENTIFY DISTURBANCE LIMITS, HAUL ROUTES, AND STAGING AREAS AS SHOWN IN THESE PLANS FOR CONSTRUCTION. THE CONTRACTOR SHALL COOPERATE AT ALL TIMES WITH THE OWNER, ANY OTHER CONTRACTORS, AND ENGINEER TO HELP RESOLVE ANY SCHEDULING OR OTHER CONFLICTS THAT MIGHT ARISE.
- ALL EQUIPMENT, GAS TANKS, DUMPSTERS, AND PORTABLE RESTROOMS SHALL BE STORED WITHIN THE STAGING AREAS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTENANCE OF ALL HAUL ROUTES AND STAGING AREAS USED DURING CONSTRUCTION. THE CONTRACTOR SHALL RESTORE THESE AREAS TO THEIR ORIGINAL CONDITION OR BETTER, UNLESS THE OWNER GIVES WRITTEN PERMISSION TO THE CONTRACTOR TO RETAIN THE AREA "AS-IS".
- THE CONTRACTOR SHALL UTILIZE NATIVE MATERIAL FROM THE SITE WHERE AVAILABLE WITHIN THE DISTURBANCE LIMITS AND ALLOWED BY THE OWNER. NATIVE MATERIAL THAT CAN BE FOUND ON SITE INCLUDES TREES THAT CAN PROVIDE LIVE STAKES, TREES THAT CAN BE USED FOR ROOT WADS, AND EXISTING BED MATERIAL FOR ROCK SILT SCREENS AND THE NATIVE ROCK RIFFLE.
 - ALL AREAS TO RECEIVE FILL
 - ALL AREAS WHICH WILL BE EXCAVATED
- ALL MATERIAL STRIPPED SHALL BE REMOVED FROM WITHIN THE LIMITS OF EXCAVATION OR AREAS TO BE FILLED AND SHALL BE TEMPORARILY STOCKPILED FOR USE AS FINAL DRESSING OF THE SITE OR PLACED IN THE TOPSOIL STOCKPILE. STOCKPILING AND PLACEMENT OF STRIPPED MATERIAL SHALL BE CONSIDERED INCIDENTAL TO CONSTRUCTION.
- TO MINIMIZE IMPACTS TO INDIANA AND NORTHERN LONG-EARED BATS DURING THE SUMMER AND FALL, ALL CLEARING OF TREES GREATER THAN 3 INCHES DIAMETER AT BREAST HEIGHT IS PROHIBITED BETWEEN APRIL 1ST AND OCT. 14TH, UNLESS APPROVED BY U.S. FISH AND WILDLIFE SERVICES (USFWS).
- THE CONTRACTOR SHALL STAKE THE PROPOSED BANK STABILIZATION FOR REVIEW BY THE ENGINEER BEFORE INITIATING EXCAVATION. DEPENDING ON ENCOUNTERED CONDITIONS SOME SHIFTING OF THE PROPOSED BANK LOCATIONS MAY BE NECESSARY. ANY COST ASSOCIATED WITH CHANGING STRUCTURE LOCATIONS OR ALIGNMENT SHALL BE CONSIDERED INCIDENTAL TO CONSTRUCTION.
- THE CONTRACTOR SHALL NOTIFY ENGINEER 72 HOURS PRIOR TO INSTALLING ANY STRUCTURES. PLACEMENT AND ELEVATION OF STRUCTURES SHALL BE DIRECTED BY THE ENGINEER
- THE CONTRACTOR SHALL NOT CONSTRUCT MORE THAN 500 FEET OF BANK AND CHANNEL WITHOUT EROSION CONTROL BLANKET IN PLACE.
- THE PROPOSED BANK STABILIZATION SHALL BE CONSTRUCTED BY FIRST EXCAVATING TO THE PROPER DEPTHS INDICATED IN THE DETAIL AND CROSS SECTIONS TO PLACE BOULDER TOE. THIS SHALL BE DONE AS CHANNEL EXCAVATION AND IS TYPICALLY ACCOMPLISHED WITH A TRACKED EXCAVATOR. THE DETAILS AND CROSS SECTIONS SHOWN PROVIDE WIDTHS AND SLOPES FOR AID IN CONSTRUCTING THE CHANNEL TO THE APPROPRIATE DIMENSIONS. THE SLOPING OF THE CROSS SECTIONS SHALL THEN BE PERFORMED AS SHOWN ON THE CROSS SECTIONS. ANY STOCKPILING OF MATERIALS OR "DOUBLE HANDLING" NECESSARY TO BUILD THE CHANNEL SHALL BE CONSIDERED INCIDENTAL TO CONSTRUCTION.
- THE PROPOSED GRADE SHALL BE FINISHED TO A SMOOTH AND COMPACT SURFACE IN ACCORDANCE WITH THE LINES, GRADES AND CROSS SECTIONS OR ELEVATIONS SHOWN ON THE DRAWINGS. THE DEGREE OF FINISH FOR ELEVATIONS SHALL BE WITHIN 0.1 FEET OF THE GRADES AND ELEVATIONS INDICATED.

- CONTRACTOR SHALL USE AN EXCAVATOR WITH A HYDRAULIC THUMB TO CONSTRUCT BOULDER TOE WITH ROOT WADS AND LIVE BRUSH LAYERING.
- THE BID ITEMS, BOULDER TOE WITH ROOT WADS, LIVE BRUSH LAYERING, OR ANY OTHER WORK NOTED HEREIN SHALL INCLUDE ALL LABOR AND MATERIALS NECESSARY TO CONSTRUCT. BID ITEMS INCLUDE SEEDING, PLANTING AND MULCH, AND EROSION CONTROL BLANKETS NECESSARY TO RESTORE AREAS DISTURBED DURING CONSTRUCTION OF STRUCTURES.
- CONSTRUCTION SPECIFICATIONS FOR CROSS SECTIONS WILL BE HELD TO THE TOLERANCES SHOWN ON SHEET C-104.
- BANK STABILIZATION AREAS SHALL BE RE-VEGETATED AS SOON AS POSSIBLE BY SEEDING IN ACCORDANCE WITH THE PLANTING TABLE AND BY INSTALLING EROSION CONTROL BLANKET. ALL SEEDING AND INSTALLATION OF EROSION CONTROL BLANKET SHALL BE PERFORMED IN ACCORDANCE WITH THE CONSTRUCTION SPECIFICATIONS.
- PERMANENT SEED MIX IS TYPICALLY INSTALLED IN THE FALL, AND IF THE TIMING OF PROJECT IS SUCH THAT THE PERMANENT SEED MIX CANNOT BE PLACED IN THE FALL, THEN THE CONTRACTOR SHALL SEED WITH THE TEMPORARY SEED MIX TO PROVIDE TEMPORARY COVER UNTIL PERMANENT MIX CAN BE SEED. HOWEVER, FOR THIS PROJECT ALL PERMANENT SEEDING SHALL OCCUR DURING CONSTRUCTION WITH THE ANTICIPATION OF A LOW SUCCESS RATE. THE CLIENT ANTICIPATES HAVING TO RE-SEED WITH PERMANENT SEED MIX IN THE FALL.
- TYPICALLY ANY HARVESTING AND INSTALLATION OF LIVE STAKES AND LIVE BRUSH IS PERFORMED ONLY DURING THE DORMANT SEASON, TYPICALLY BETWEEN NOVEMBER 1 AND MARCH 31. HOWEVER, FOR THIS PROJECT ALL HARVESTING AND INSTALLATION OF LIVE STAKES AND LIVE BRUSH SHALL BE PERFORMED DURING CONSTRUCTION WITH THE ANTICIPATION OF A HIGH MORTALITY RATE. THE CLIENT ANTICIPATES HAVING TO RE-INSTALL LIVE STAKES AND LIVE BRUSH DURING DORMANT SEASON.
- LIVE STAKES SHALL BE INSTALLED WHERE INDICATED ON THE DRAWINGS AND DETAILS. LIVE STAKES SHALL BE INSTALLED IN ACCORDANCE WITH THE DETAILS AND CONSTRUCTION SPECIFICATIONS.
- TOPSOIL SHALL BE REMOVED FROM EXCAVATION AND SPOIL AREAS PRIOR TO CUT OR FILL AND RE-APPLIED TO AREAS AFTER ROUGH GRADING IS COMPLETE. FOUR INCHES OF TOPSOIL SHALL BE PLACED ON DISTURBED AREAS TO MEET GRADE. STOCKPILING AND PLACEMENT OF TOPSOIL SHALL BE CONSIDERED INCIDENTAL TO CONSTRUCTION.
- THE CONTRACTOR WILL LIKELY HAVE TO SOURCE ADDITIONAL TOPSOIL FROM OFF-SITE.
- SPOIL AREAS SHALL BE SEEDED WITH THE TEMPORARY MIX WITHIN 14 DAYS FOLLOWING PLACEMENT.
- THE PLACEMENT OF STRAW MULCH SHALL OCCUR A MAXIMUM 48 HOURS AFTER PLANTING. MULCH WILL BE SPREAD TO COVER THE INSTALLED AREAS AT A MINIMUM RATE OF 40 BALES PER ACRE.
- THE CONTRACTOR SHALL NOTIFY THE ENGINEER AND THE OWNER 72 HOURS BEFORE FINISH GRADING AND SEEDING ANY STAGING AREAS ON SITE.
- THE CONTRACTOR SHALL GRADE ALL CONFLUENCES IN SUCH A WAY TO PROVIDE SMOOTH TRANSITIONS.
- BANK STABILIZATION PROJECTS THAT UTILIZE NATURAL CHANNEL DESIGN RELY ON VEGETATION TO MINIMIZE EROSION. IF VEGETATION IS NOT ESTABLISHED PRIOR TO WINTER MONTHS OR PRIOR TO LARGE FLOWS SOME EROSION MAY OCCUR WHICH MAY REQUIRE ADDITIONAL SITE WORK, PLANTINGS, SEEDING, AND EROSION CONTROL BLANKET INSTALLATION. CONTRACTOR SHALL MAKE EVERY EFFORT TO SECURE EROSION CONTROL BLANKET QUICKLY AND RE-VEGETATE THE SITE QUICKLY.
- THE CONTRACTOR SHALL COMMUNICATE CONSTRUCTION ISSUES, PROBLEMS OR DISCREPANCIES IN THE CONSTRUCTION DOCUMENTS TO THE ENGINEER IMMEDIATELY UPON BECOMING AWARE OF SUCH ISSUES. ANY REQUESTS FOR INFORMATION OR CLARIFICATION OF THE CONSTRUCTION DOCUMENTS SHALL BE IN ACCORDANCE TO SECTION 012600 OF THE CONSTRUCTION SPECIFICATIONS.
- ANY PROPOSED MODIFICATION TO DESIGN FEATURES AS SHOWN (OR DESCRIBED) IN THE CONSTRUCTION DOCUMENTS SHALL BE CONTINGENT UPON ENGINEER APPROVAL. THE ENGINEER SHALL PROVIDE SUPPLEMENTAL INSTRUCTIONS FOR ANY DESIGN CHANGES IN ACCORDANCE WITH SECTION 012600 OF THE CONSTRUCTION SPECIFICATIONS.

AS-BUILT DRAWINGS

DURING CONSTRUCTION, THE CONTRACTOR AND THE ENGINEER SHALL WORK TOGETHER TO MAINTAIN A SET OF PRINTS SHOWING ANY CHANGES OR CORRECTIONS IN RED. THESE PRINTS SHALL BE SUBMITTED TO THE ENGINEER AT THE COMPLETION OF THE WORK.

INDEX OF SHEETS

SHEET NO.	TITLE	SHEET NO.	TITLE
GENERAL			
G-001	COVER SHEET	C-106	PROPOSED CROSS SECTIONS REACH 1
G-002	GENERAL NOTES	C-107	PROPOSED CROSS SECTIONS REACH 2
CIVIL			
C-101	ALIGNMENT LAYOUT & CONTROL POINT	C-108	PROPOSED CROSS SECTIONS REACH 3
C-102	ALIGNMENT LAYOUT TABLES	C-109	PROPOSED CROSS SECTIONS REACH 3
C-103	KIEFER CREEK PROPOSED PLAN	C-110	PLANTING PLAN
C-104	TYPICAL CROSS SECTIONS	C-111	DETAILS
C-105	PROPOSED CROSS SECTIONS REACH 1	C-112	DETAILS
		C-113	DETAILS
		C-114	EROSION PREVENTION & SEDIMENT CONTROL PLAN

PROJECT QUANTITIES *				
LINE ITEM NO.	SECTION	ITEM	UNIT	QUANTITY
1	310516	MODOT TYPE 4 ROCK DITCH LINER	TONS	1060
2	310516	MODOT TYPE 1 ROCK DITCH LINER	TONS	240
3	310516	MODOT TYPE 7 AGGREGATE FOR BASE	TONS	180
4	312000	EXCAVATION	CY	1330
5	312000	FILL (INCLUDES CHANNEL AND FILLING VOID SPACE IN BOULDER TOE)	CY	830
6	312000	TOPSOIL (SOURCED FROM OFF-SITE)	CY	330
7	312500	WOVEN EROSION CONTROL BLANKET	SY	1220
8	312500	SILT FENCE	LF	2054
9	312500	STRAW MULCH	Bale	48800
10	313501.2	LIVE BRUSH LAYERING (INCLUDES 3 LIFTS PER RUNNING LF)	LF	48800
11	313501.2	CONTINUOUS WEAVE EROSION CONTROL BLANKET	SY	610
12	313502	ROOT WAD	EACH	46
13	313502	BOULDER TOE WITH ROOT WADS	LF	530
14	314000	GEOTEXTILE FABRIC	SY	310
15	329200	TEMPORARY SEEDING (TOTAL DISTURBED AREA ON SITE)	AC	1.8
16	329200	PERMANENT SEEDING (DISTURBED AREAS WITHIN RIPARIAN)	AC	1.8
17	329300	TREES & SHRUBS	EACH	370
18	329350.1	LIVE STAKES (LBL & GRAVEL BAR)	EACH	11108
19	329350.1	LIVE BRANCHES (LBL)	EACH	15892

* NOT FOR BIDDING PURPOSES - FOR CONTRACTOR INFORMATION ONLY.

PLAN LEGEND

- 100 PROPOSED INDEX CONTOURS
- PROPOSED INTERIM CONTOURS
- 100 EXISTING INDEX CONTOURS
- EXISTING INTERIM CONTOURS
- EXISTING STREAM CENTERLINE
- LIMITS OF DISTURBANCE
- SF SF SILT FENCE
- BOULDER TOE WITH ROOT WADS AND LIVE BRUSH LAYERING
- GRAVEL BAR LIVE STAKING
- STAGING AREAS
- TEMPORARY CONSTRUCTION ENTRANCE

PROFILE & SECTION LEGEND

- EXISTING GROUND
- PROPOSED GRADE
- PROPOSED BANKFULL ELEVATION
- PROPOSED INNER BERM ELEVATION



3/24/2020



CONTROL POINT TABLE				
POINT	NORTHING	EASTING	ELEVATION	DESCRIPTION
1000	990265.02	807021.49	447.81	SL-67 (STAMPED ALUMINUM DISK)



10509 Timberwood Circle, Suite 100
Louisville, Kentucky 40228-5301
www.stantec.com

The Contractor shall verify and be responsible for the accuracy of all data used in this drawing. The Contractor shall verify and be responsible for the accuracy of all data used in this drawing. The Contractor shall verify and be responsible for the accuracy of all data used in this drawing.

OFFICE OF ADMINISTRATION
DIVISION OF FACILITIES
MANAGEMENT,
DESIGN AND CONSTRUCTION

DEPARTMENT OF
NATURAL RESOURCES

CASTLEWOOD STATE PARK
STREAMBANK RESTORATION
PHASE I

BALLWIN, MO

PROJECT # X2002-01
SITE # 5205
ASSET # 7815205028

REVISION: _____
DATE: _____
REVISION: _____
DATE: _____
REVISION: _____
DATE: _____
ISSUE DATE: 03/24/2020

CAD DWG FILE: C-101.dwg
DRAWN BY: DLH
CHECKED BY: OKR
DESIGNED BY: MAS

SHEET TITLE:
ALIGNMENT LAYOUT
& CONTROL POINT

SHEET NUMBER:

C-101

3 OF 16 SHEETS
03/24/2020

COORDINATE SYSTEM NOTE:

SURVEY COORDINATES REFER TO MISSOURI STATE
PLAN EAST COORDINATE SYSTEM NAD83.
ELEVATIONS ARE BASED ON NAVD83.





3/24/2020



10509 Timberwood Circle, Suite 100
Louisville, Kentucky 40223-6301
www.stantec.com
The Contractor shall verify the accuracy of the information provided in this drawing. The Contractor shall be responsible for all dimensions, locations, and elevations shown on this drawing. The Contractor shall be responsible for all dimensions, locations, and elevations shown on this drawing. The Contractor shall be responsible for all dimensions, locations, and elevations shown on this drawing.

OFFICE OF ADMINISTRATION
DIVISION OF FACILITIES
MANAGEMENT,
DESIGN AND CONSTRUCTION

DEPARTMENT OF
NATURAL RESOURCES

CASTLEWOOD STATE PARK
STREAMBANK RESTORATION
PHASE I

BALLWIN, MO

PROJECT # X2002-01
SITE # 5205
ASSET # 7815205028

REVISION: _____
DATE: _____
REVISION: _____
DATE: _____
REVISION: _____
DATE: _____

ISSUE DATE: 03/24/2020

CAD DWG FILE: C-102.dwg
DRAWN BY: DLH
CHECKED BY: OKR
DESIGNED BY: MAS

SHEET TITLE:

ALIGNMENT LAYOUT
TABLES

SHEET NUMBER:

C-102

4 OF 16 SHEETS
03/24/2020

KIEFER CREEK REACH 1 ALIGNMENT									
NUMBER	START STATION	END STATION	LENGTH	RADIUS	LINE/CHORD DIRECTION	START NORTHING	END NORTHING	START EASTING	END EASTING
L1	10+00.0	10+18.4	18.37		N89° 27' 10.58"E	989382.548	989382.72	807508.573	807526.943
C1	10+18.4	10+77.7	59.37	150.00	N78° 06' 50.45"E	989382.723	989394.87	807526.943	807584.662
L2	10+77.7	11+14.3	36.55		N66° 46' 30.31"E	989394.872	989409.28	807584.662	807618.246
C2	11+14.3	12+33.8	119.54	110.40	N35° 45' 18.13"E	989409.283	989501.62	807618.246	807684.734
L3	12+33.8	12+85.0	51.17		N4° 44' 05.95"E	989501.623	989552.62	807684.734	807688.958

KIEFER CREEK REACH 2 ALIGNMENT									
NUMBER	START STATION	END STATION	LENGTH	RADIUS	LINE/CHORD DIRECTION	START NORTHING	END NORTHING	START EASTING	END EASTING
L4	20+00.0	20+18.1	18.13		N79° 49' 55.36"E	989739.797	989743.00	807616.064	807633.905
C3	20+18.1	20+27.6	9.49	20.00	N66° 14' 09.68"E	989742.997	989746.79	807633.905	807642.511
L5	20+27.6	20+38.6	10.93		N52° 38' 24.00"E	989746.786	989753.42	807642.511	807651.202
C4	20+38.6	21+17.5	78.99	75.50	N82° 36' 44.91"E	989753.421	989763.12	807651.202	807726.013
L6	21+17.5	21+26.1	8.56		S67° 24' 54.18"E	989763.120	989759.83	807726.013	807733.917
C5	21+26.1	21+34.4	8.26	50.00	S72° 08' 52.01"E	989759.833	989757.30	807733.917	807741.770
L7	21+34.4	21+48.5	14.13		S76° 52' 49.83"E	989757.304	989754.10	807741.770	807755.531

KIEFER CREEK REACH 3 ALIGNMENT									
NUMBER	START STATION	END STATION	LENGTH	RADIUS	LINE/CHORD DIRECTION	START NORTHING	END NORTHING	START EASTING	END EASTING
L8	30+00.0	30+38.2	38.19		S67° 56' 21.30"E	989686.251	989671.91	808001.048	808036.442
C6	30+38.2	30+50.8	12.61	100.00	S71° 33' 03.00"E	989671.907	989667.92	808036.442	808048.393
L9	30+50.8	30+55.9	5.06		S75° 09' 44.69"E	989667.920	989666.62	808048.393	808053.283
C7	30+55.9	31+47.5	91.63	90.40	S46° 07' 25.52"E	989666.625	989605.80	808053.283	808116.544
L10	31+47.5	31+48.8	1.32		S17° 05' 06.36"E	989605.798	989604.53	808116.544	808116.933
C8	31+48.8	31+79.0	30.18	49.60	S34° 30' 48.99"E	989604.533	989580.05	808116.933	808133.768
L11	31+79.0	31+83.4	4.44		S51° 56' 31.62"E	989580.050	989577.31	808133.768	808137.268

COORDINATE SYSTEM NOTE:

SURVEY COORDINATES REFERENCES TO MISSOURI STATE
PLAN EAST COORDINATE SYSTEM NAD83.
ELEVATIONS ARE BASED ON NAVD88.



NOTES:
 1. THE AERIAL IMAGERY SHOWN IS DATED 2016 AND IS THE MOST RECENT AVAILABLE. TOPOGRAPHIC INFORMATION SHOWN IS LIDAR DATED 2011. THE MAJOR DISCREPANCIES BETWEEN THE TWO FORMS OF DATA IS DUE TO LATERAL BANK EROSION.



10509 Timberwood Circle, Suite 100
 Louisville, Kentucky 40223-5301
 www.stantec.com
 The Contractor shall verify and be responsible for all dimensions, DO NOT rely on the drawing. Any errors or omissions shall be reported to Stantec without delay. The Copyright to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that indicated on this drawing is forbidden.

OFFICE OF ADMINISTRATION
 DIVISION OF FACILITIES
 MANAGEMENT,
 DESIGN AND CONSTRUCTION
 DEPARTMENT OF
 NATURAL RESOURCES

CASTLEWOOD STATE PARK
 STREAMBANK RESTORATION
 PHASE I

BALLWIN, MO

PROJECT # X2002-01
 SITE # 5205
 ASSET # 7815205028

REVISION: _____
 DATE: _____
 REVISION: _____
 DATE: _____
 REVISION: _____
 DATE: _____
 ISSUE DATE: 03/24/2020

CAD DWG FILE: C-103.dwg
 DRAWN BY: DLH
 CHECKED BY: OKR
 DESIGNED BY: MAS

SHEET TITLE:
**KIEFER CREEK
 PROPOSED PLAN**

SHEET NUMBER:

C-103

5 OF 16 SHEETS
 03/24/2020



3/24/2020



10529 Timberwood Circle, Suite 100
Louisville, Kentucky 40223-5301
www.stantec.com

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing. Any errors or omissions shall be reported to Stantec, without delay, for correction. This drawing is for informational purposes only and is not intended to be used for any purpose other than that authorized by Stantec's field office.

OFFICE OF ADMINISTRATION
DIVISION OF FACILITIES
MANAGEMENT,
DESIGN AND CONSTRUCTION

DEPARTMENT OF
NATURAL RESOURCES

CASTLEWOOD STATE PARK
STREAMBANK RESTORATION
PHASE I

BALLWIN, MO

PROJECT # X2002-01
SITE # 5205
ASSET # 7815205028

REVISION: _____
DATE: _____
REVISION: _____
DATE: _____
REVISION: _____
DATE: _____
ISSUE DATE: 03/24/2020



CAD DWG FILE: C-104.dwg
DRAWN BY: DLH
CHECKED BY: OKR
DESIGNED BY: MAS

SHEET TITLE:
TYPICAL
CROSS SECTIONS

SHEET NUMBER:

C-104

6 OF 16 SHEETS
03/24/2020





3/24/2020



10509 Timberwood Circle, Suite 100
Louisville, Kentucky 40223-3301
www.stantec.com

The Contractor shall verify and be responsible for all dimensions. DO NOT SCALE the drawing. All errors or omissions shall be reported to Stantec without delay. Stantec shall not be responsible for any errors or omissions in the production or use for any purpose other than that authorized by Stantec's jobbooks.

OFFICE OF ADMINISTRATION
DIVISION OF FACILITIES
MANAGEMENT,
DESIGN AND CONSTRUCTION

DEPARTMENT OF
NATURAL RESOURCES

CASTLEWOOD STATE PARK
STREAMBANK RESTORATION
PHASE I

BALLWIN, MO

PROJECT # X2002-01
SITE # 5205
ASSET # 7815205028

REVISION: _____
DATE: _____
REVISION: _____
DATE: _____
REVISION: _____
DATE: _____
ISSUE DATE: 03/24/2020




CAD DWG FILE: C-105.dwg
DRAWN BY: DLH
CHECKED BY: OKR
DESIGNED BY: MAS

SHEET TITLE:
**PROPOSED
CROSS SECTIONS
REACH 1**

SHEET NUMBER:

C-105

7 OF 16 SHEETS
03/24/2020





3/24/2020



10509 Timberwood Circle, Suite 100
Louisville, Kentucky 40223-5301
www.stantec.com

The Contractor and user will be responsible for all dimensions. DO NOT scale the drawing. Any errors or omissions shall be reported to Stantec without delay. The Contractor shall be responsible for all dimensions. Stantec is not responsible for any errors or omissions that may occur in the reproduction of this drawing.

OFFICE OF ADMINISTRATION
DIVISION OF FACILITIES
MANAGEMENT,
DESIGN AND CONSTRUCTION

DEPARTMENT OF
NATURAL RESOURCES

CASTLEWOOD STATE PARK
STREAMBANK RESTORATION
PHASE I

BALLWIN, MO

PROJECT # X2002-01
SITE # 5205
ASSET # 7815205028

REVISION: _____
DATE: _____
REVISION: _____
DATE: _____
REVISION: _____
DATE: _____
ISSUE DATE: 03/24/2020





CAD DWG FILE: C-106.dwg
DRAWN BY: DLH
CHECKED BY: OKR
DESIGNED BY: MAS

SHEET TITLE:
**PROPOSED
CROSS SECTIONS
REACH 1**

SHEET NUMBER:

C-106

8 OF 16 SHEETS
03/24/2020





3/24/2020



10509 Timberwood Circle, Suite 100
Louisville, Kentucky 40223-5301
www.stantec.com

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec, without delay. This drawing is for informational purposes only and shall not be used for construction or any other purpose other than that authorized by Stantec's field office.

OFFICE OF ADMINISTRATION
DIVISION OF FACILITIES
MANAGEMENT,
DESIGN AND CONSTRUCTION

DEPARTMENT OF
NATURAL RESOURCES

CASTLEWOOD STATE PARK
STREAMBANK RESTORATION
PHASE I

BALLWIN, MO

PROJECT # X2002-01
SITE # 5205
ASSET # 7815205028

REVISION: _____
DATE: _____
REVISION: _____
DATE: _____
REVISION: _____
DATE: _____

ISSUE DATE: 03/24/2020




CAD DWG FILE: C-107.dwg
DRAWN BY: DLH
CHECKED BY: OKR
DESIGNED BY: MAS

SHEET TITLE:
**PROPOSED
CROSS SECTIONS
REACH 2**

SHEET NUMBER:

C-107

9 OF 16 SHEETS
03/24/2020





3/24/2020



10509 Timberwood Circle, Suite 100
Louisville, Kentucky 40223-3301
www.stantec.com

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing. The Contractor shall be responsible for any reproduction or use for any purpose other than that authorized by Stantec's laborer.

OFFICE OF ADMINISTRATION
DIVISION OF FACILITIES
MANAGEMENT,
DESIGN AND CONSTRUCTION

DEPARTMENT OF
NATURAL RESOURCES

CASTLEWOOD STATE PARK
STREAMBANK RESTORATION
PHASE I

BALLWIN, MO

PROJECT # X2002-01
SITE # 5205
ASSET # 7815205028

REVISION: _____
DATE: _____
REVISION: _____
DATE: _____
REVISION: _____
DATE: _____

ISSUE DATE: 03/24/2020


CAD DWG FILE: C-108.dwg
DRAWN BY: DLH
CHECKED BY: OKR
DESIGNED BY: MAS

SHEET TITLE:
PROPOSED
CROSS SECTIONS
REACH 3

SHEET NUMBER:

C-108

10 OF 16 SHEETS
03/24/2020





3/24/2020



10800 Timberwood Circle, Suite 100
Louisville, Kentucky 40223-3301
www.stantec.com

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing. Any errors or omissions shall be reported to Stantec without delay. Stantec is not responsible for any errors or omissions in the production or use for any purpose other than that authorized by Stantec. It is forbidden.

OFFICE OF ADMINISTRATION
DIVISION OF FACILITIES
MANAGEMENT,
DESIGN AND CONSTRUCTION

DEPARTMENT OF
NATURAL RESOURCES

CASTLEWOOD STATE PARK
STREAMBANK RESTORATION
PHASE I

BALLWIN, MO

PROJECT # X2002-01
SITE # 5205
ASSET # 7815205028

REVISION: _____
DATE: _____
REVISION: _____
DATE: _____
REVISION: _____
DATE: _____

ISSUE DATE: 03/24/2020


CAD DWG FILE: C-109.dwg
DRAWN BY: DLH
CHECKED BY: OKR
DESIGNED BY: MAS

SHEET TITLE:
**PROPOSED
CROSS SECTIONS
REACH 3**

SHEET NUMBER:

C-109

11 OF 16 SHEETS
03/24/2020





10509 Timberwood Circle, Suite 100
Louisville, Kentucky 40223-5301
www.stantec.com

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing. Any errors or omissions shall be reported to Stantec without delay. The Copyright in all design and drawings are the property of Stantec. Reproduction of any part of any drawing without the written consent of Stantec is prohibited.

OFFICE OF ADMINISTRATION
DIVISION OF FACILITIES
MANAGEMENT,
DESIGN AND CONSTRUCTION

DEPARTMENT OF
NATURAL RESOURCES

CASTLEWOOD STATE PARK
STREAMBANK RESTORATION
PHASE I

BALLWIN, MO

PROJECT # X2002-01
SITE # 5205
ASSET # 7815205028

REVISION: _____
DATE: _____
REVISION: _____
DATE: _____
REVISION: _____
DATE: _____
ISSUE DATE: 03/24/2020


CAD DWG FILE: C-110.dwg
DRAWN BY: DLH
CHECKED BY: OKR
DESIGNED BY: MAS

SHEET TITLE:
PLANTING PLAN

SHEET NUMBER:

C-110

12 OF 16 SHEETS
03/24/2020



All Zones and Disturbed Areas Temporary Seed Mix (October - April) (1.8 acres total)					
Common Name	Scientific Name	Welland Indicator Status	Composition %	Pounds per Acre in Seedmix	Total Pounds in Zones 1 & 2
Winter Wheat	Triticum aestivum	n/a	100%	80.00	144.00

All Zones and Disturbed Areas Temporary Seed Mix (May - September) (1.8 acres)					
Common Name	Scientific Name	Welland Indicator Status	Composition %	Pounds per Acre in Seedmix	Total Pounds in Zones 1 & 2
Browntop Millet	Urochloa ramosa	n/a	100%	10.00	18.00

Zone 1 (Low Flow to Bankfull): Permanent Seed Mix (0.08 acres)					
Common Name	Scientific Name	Welland Indicator Status	Composition %	Pounds per Acre in Seedmix	Total Pounds in Zone 1
Fowl Mannagrass	Glyceria striata	OBL	15%	0.392	0.03
Virginia Wild Rye	Elymus virginicus	FACW	15%	3.920	0.31
Switchgrass	Panicum virgatum	FAC	5%	0.841	0.07
Little Bluestem	Schizachyrium scaporum	FACU	15%	2.723	0.22
Fox Sedge	Carex vulpinoidea	FACW	15%	0.603	0.05
Alternate Wingsstem	Verbesina alternifolia	FACW	5%	0.901	0.07
Beggars Ticks	Bidens frondosa	FACW	5%	1.005	0.08
Common Rush	Juncus effusus	OBL	5%	0.058	0.00
Boneset	Eupatorium perfoliatum	OBL	5%	0.131	0.01
Mistflower	Conoclinium coelestinum	FACW	5%	0.174	0.01
Crass-Leaved Goldenrod	Euthamia graminifolia	FACW	5%	0.871	0.07
Culiac Coneflower	Rudbeckia laciniata	FACW	5%	0.864	0.07
TOTAL			100%	12.484	1.00

Zone 1 (Low Flow to Bankfull): Live Stakes (0.08 acres)					
Common Name	Scientific Name	Welland Indicator Status	Composition %	Stems per Acre (1 per ft ²)	Total Stems in Zone 1
TREES & SHRUBS					
Buttonbush	Cephalanthus occidentalis	OBL	25%	10890	871
Silky Dogwood	Cornus amomum	FACW	25%	10890	871
Black Willow	Salix nigra	OBL	25%	10890	871
Elderberry	Sambucus nigra	FAC	25%	10890	871
TOTAL			100%	43560	3485

Zone 2 (Above Bankfull), Haul Routes, and Staging Areas: Permanent Seed Mix (1.72 acres)					
Common Name	Scientific Name	Welland Indicator Status	Composition %	Pounds per Acre in Seedmix	Total Pounds in Zone 2
Bottlebrush Grass	Elymus hystrix	UPL	15%	3.403	5.85
Big Bluestem	Andropogon gerardii	FAC	5%	0.908	1.56
River Oats	Chamaerhynchium latifolium	FACW	15%	4.356	7.49
Purple Top	Tridens flavus	UPL	10%	0.937	1.61
Silky Wild Rye	Elymus villosus	FACU	20%	5.227	8.99
Indiangrass	Sorghastrum nutans	FACU	5%	1.245	2.14
Common Milkweed	Asclepias syriaca	FACU	5%	2.723	4.68
Bergamot	Monarda fistulosa	FACU	5%	0.209	0.36
Illinois Bundleflower	Desmanthus illinoensis	FACU	5%	1.089	1.87
Partridge Pea	Chamaecrista fasciculata	FACU	5%	1.742	3.00
Black Eyed Susan	Rudbeckia hirta	FACU	5%	0.163	0.28
Tall Goldenrod	Solidago altissima	FACU	5%	0.373	0.64
TOTAL			100%	22.375	38.48

Zone 2 (Above Bankfull): Bare-Root or Containerized Plantings (0.54 acres)					
Common Name	Scientific Name	Welland Indicator Status	Composition %	Stems per Acre	Total Stems in Zone 2
SHRUBS					
Redbud	Cercis canadensis	FACU	20%	31	17
Hornwood	Carpinus caroliniana	FAC	20%	31	17
Roughleaf Dogwood	Cornus drummondii	FAC	20%	31	17
Carolina Buckthorn	Rhamnus caroliniana	FAC	20%	31	17
Bladdernut**	Staphylea trifolia**	FAC	20%	31	17
TOTAL			100%	155	84
TREES					
Sugar Maple	Acer saccharum	FACU	15%	42	23
Shelbark Hickory	Carya laevis	FACW	15%	42	23
Burr Oak	Quercus macrocarpa	FAC	15%	42	23
Shumard Oak	Quercus shumardii	FACW	15%	42	23
Black Walnut	Juglans nigra	FACU	10%	28	15
Sycamore	Platanus occidentalis	FACW	10%	28	15
Cottonwood	Populus deltoides	FAC	10%	28	15
American Elm	Ulmus americana	FACW	10%	28	15
TOTAL			100%	280	151


** If unavailable, Bladdernut (Staphylea trifolia) may be substituted with Hoptree (Ptelea trifoliata)

Gravel Bar: Live Stakes (0.35 acres)					
Common Name	Scientific Name	Welland Indicator Status	Composition %	Stems per Acre (see detail - 1/10)	Total Stems
TREES & SHRUBS					
Buttonbush	Cephalanthus occidentalis	OBL	25%	5445	1906
Silky Dogwood	Cornus amomum	FACW	25%	5445	1906
Black Willow	Salix nigra	OBL	25%	5445	1906
Elderberry	Sambucus nigra	FAC	25%	5445	1906
TOTAL			100%	21780	7623

NOTE: ALL VEGETATION OUTSIDE OF THE LIMITS OF DISTURBANCE SHALL BE PRESERVED TO PROVIDE NATURAL BUFFERING.



3/24/2020



NOTES:

1. A 4-FEET DEEP BY 3-FEET WIDE FOOTING CONSISTING OF MODOT TYPE 4 ROCK DITCH LINER SHALL BE CONSTRUCTED BENEATH THE CHANNEL BOTTOM ELEVATION RELATIVE TO THE TYPICAL SECTION.
2. PLACE A MINIMUM OF 2.8 FEET OF MODOT TYPE 4 ROCK DITCH LINER, STARTING AT CHANNEL BOTTOM, TO PROVIDE BASE TO RECONSTRUCT SLOPE. THE OUTER FACE OF THE ROCK SHALL BE STACKED IN A 1:1 SLOPE OR FLATTER. THE ROCK, AFTER PLACEMENT, SHOULD OCCUPY THE FIRST 6.5 FEET OF RECONSTRUCTED BANK WIDTH AT THE TOE AND 5 FEET BANK WIDTH AT THE APPROXIMATE BASE FLOW ELEVATION. AT TRANSITIONS AT BOTH ENDS OF THE LIVE BRUSH LAYERING.
3. BOULDER TOE SHALL BE COMPLETED BY FIRST PLACING A LAYER OF MACHINED STONE (MODOT TYPE 4 ROCK DITCH LINER) AND THEN TOP DRESSING WITH NATIVE COBBLE/GRAVEL MATERIAL TO HELP FILL VOID SPACE. THIS SEQUENCE SHALL BE FOLLOWED UNTIL REACHING APPROXIMATE BASEFLOW ELEVATION. THE INTENT OF USING NATIVE COBBLE/GRAVEL MATERIAL TO HELP FILL VOID SPACE IS TO PROVIDE A MORE STABLE MATRIX OF BANK MATERIAL AND TO ALSO FUNCTION AS A FILTER THAT SHOULD HELP PREVENT LOSS OF SOIL BACKFILL MATERIAL FROM THE LIVE BRUSH LAYERING.
4. ROOT WADS AND ACCOMPANYING WOODY DEBRIS SHALL BE PLACED ON APPROXIMATE 25' SPACING AS SHOWN IN THE PLAN SHEETS, OR AS INSTRUCTED BY THE ENGINEER BASED ON SITE AVAILABILITY. ROOT WADS SHOULD BE PLACED IN PAIRS AT APPROXIMATE ELEVATION SHOWN IN THE DETAIL CROSS SECTION. THE ENTIRE UPSTREAM ROOT WAD SHALL PROTRUDE FROM THE BANK TO ADD ROUGHNESS AND SLOW NEAR BANK VELOCITIES WHILE THE IMMEDIATE DOWNSTREAM ROOT WAD SHALL BE PLACED FLUSH WITH THE BANK TO HELP REDUCE POTENTIAL SCOUR FROM TURBULENCE CREATED BY THE IMMEDIATE UPSTREAM ROOT WAD.
5. TREES USED FOR ROOT WADS SHALL, ON AVERAGE, BE A MINIMUM OF 6 INCHES IN DIAMETER AT BREST HEIGHT. ACCOMPANYING WOODY DEBRIS DOES NOT HAVE A MINIMUM DIAMETER REQUIREMENT. TREES USED FOR ROOT WADS SHALL BE HARDWOOD SPECIES FREE OF ANY DECAY THAT WOULD RESULT IN RISK OF STABILITY.
6. ROOT WADS SHALL TIE BACK INTO THE BANK A MINIMUM OF 10' AND SHALL BE ANGLED UPSTREAM AS SHOWN IN THE PROPOSED PLAN SHEETS.
7. PLACE TYPE I NON-WOVEN GEOTEXTILE FABRIC ON TOP OF THE FINISHED BOULDER

TOE BEGINNING 6 INCHES FROM THE FACE OF THE PROPOSED BANK AND EXTENDING BACK A MINIMUM OF 3 FEET INTO THE PROPOSED BANK TO HELP PREVENT PIPING OF SOIL MATERIAL INTO ANY REMAINING VOID SPACE WITHIN THE BOULDER TOE.

8. INSTALL LIVE BRUSH LAYERING ON TOP OF THE GEOTEXTILE FABRIC. LIVE BRUSH LAYERING SHALL BE INSTALLED IN ACCORDANCE WITH DETAIL 2 ON SHEET C-112.
9. STRUCTURE MAY BE MODIFIED IN FIELD BY ENGINEER.

1
C-111
DETAIL -- BOULDER TOE WITH ROOT WADS
NOT TO SCALE



10509 Timberwood Circle, Suite 100
Louisville, Kentucky 40223-5301
www.stantec.com

The Contractor shall verify and be responsible for all dimensions. DO NOT SCALE the drawing. Any errors or omissions shall be reported to Stantec, without delay. Stantec shall not be responsible for any errors or omissions in the drawing or for any consequences other than those caused by Stantec's negligence.

OFFICE OF ADMINISTRATION
DIVISION OF FACILITIES
MANAGEMENT,
DESIGN AND CONSTRUCTION

DEPARTMENT OF
NATURAL RESOURCES

CASTLEWOOD STATE PARK
STREAMBANK RESTORATION
PHASE I

BALLWIN, MO

PROJECT # X2002-01
SITE # 5205
ASSET # 7815205028

REVISION: _____
DATE: _____
REVISION: _____
DATE: _____
REVISION: _____
DATE: _____

ISSUE DATE: 03/24/2020

CAD DWG FILE: C-111.dwg
DRAWN BY: DLH
CHECKED BY: OKR
DESIGNED BY: MAS

SHEET TITLE:

DETAILS

SHEET NUMBER:

C-111

13 OF 16 SHEETS
03/24/2020



10599 Timberwood Circle, Suite 100
Louisville, Kentucky 40225-5301
www.stantec.com

The Contractor and user shall be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec, without delay. The Contractor shall be responsible for the accuracy of the information provided. All dimensions are in feet and inches unless otherwise specified.

OFFICE OF ADMINISTRATION
DIVISION OF FACILITIES
MANAGEMENT,
DESIGN AND CONSTRUCTION

DEPARTMENT OF
NATURAL RESOURCES

CASTLEWOOD STATE PARK
STREAMBANK RESTORATION
PHASE I

BALLWIN, MO

PROJECT # X2002-01
SITE # 5205
ASSET # 7815205028

REVISION: _____
DATE: _____
REVISION: _____
DATE: _____
REVISION: _____
DATE: _____
ISSUE DATE: 03/24/2020





CAD DWG FILE: C-112.dwg
DRAWN BY: DLH
CHECKED BY: OKR
DESIGNED BY: MAS

SHEET TITLE:
DETAILS

SHEET NUMBER:


C-112

14 OF 16 SHEETS
03/24/2020




- NOTES:
- GRAVEL BAR LIVE STAKES SHALL BE INSTALLED IN LOCATIONS SPECIFIED ON THE PLANS.
 - STAKES SHALL BE CUT FROM AN APPROVED SOURCE WITH A SHARP TOOL. STAKES SHALL BE FREE FROM DISEASE OR EXCESS DEAD TWIGS. 4 - 6 FEET IN LENGTH WITH A BASAL END AT 0.5 - 2 INCHES IN DIAMETER. PRIOR TO INSTALLATION BASAL END SHALL BE CUT AT A 45 DEGREE ANGLE AND THE OPPOSITE END SHALL BE CUT FLAT WITHOUT CRACKS.
 - STARTING FROM THE DOWNSTREAM END OF THE EXISTING GRAVEL BAR, THE CONTRACTOR SHALL EXCAVATE TRENCHES RUNNING PERPENDICULAR TO THE CHANNEL. FOR THE ENTIRE WIDTH OF THE GRAVEL BAR, THESE TRENCHES SHALL BE SPACED FOUR (4) FEET ON CENTER.
 - THE CONTRACTOR SHALL USE AN EXCAVATOR WITH A MAXIMUM BUCKET WIDTH OF 2.0 FEET TO EXCAVATE TRENCHES.
 - THE TRENCHES SHALL BE EXCAVATED TO A DEPTH AND ANGLE WHICH ALLOWS LIVE STAKES TO BE INSTALLED AT A 45° ANGLE DOWNSTREAM AND BURIED WITH 1/4 OF THE TOTAL STAKE LENGTH EXPOSED.
 - LIVE STAKES SHALL BE PLANTED TWO (2) PER RUNNING LINEAR FOOT OF TRENCH.
 - THE EXCAVATED MATERIAL SHALL THEN BE USED TO COVER THE PLACED STAKES.
 - PLANTING SHALL BEGIN ON THE DOWNSTREAM, STREAMWARD SIDE OF RESPECTIVE PLANTING AREA AND SHALL BE COMPLETED PERPENDICULARLY ACROSS THE EXISTING GRAVEL BAR. ONCE A ROW OF PLANTINGS HAS BEEN COMPLETED ACROSS THE AREA, THE EXCAVATOR SHALL TRENCH AND PLANT IN SUCCESSIVE ROWS MOVING UPSTREAM.
 - LIVE STAKES ARE TYPICALLY INSTALLED WHEN THEY ARE DORMANT, WHICH TYPICALLY OCCURS BETWEEN NOVEMBER 1 AND MARCH 31. HOWEVER, FOR THIS PROJECT ALL LIVE STAKES SHALL BE INSTALLED DURING CONSTRUCTION WITH THE ANTICIPATION OF A HIGH MORTALITY RATE.
 - THE CLIENT ANTICIPATES RE-INSTALLING LIVE STAKES DURING DORMANCY.

1
C-112
DETAIL - TYPICAL GRAVEL BAR LIVE STAKE
NOT TO SCALE



- NOTE:
TOPSOIL SHALL BE PLACED IMMEDIATELY ABOVE AND BELOW LIVE BRANCHES.
- NOTE:
LENGTH VARIES (TYP. 3 TO 4 FT.)
DIAMETER VARIES (TYP. 1/4 TO 1/2")
LIVE BRANCH
- NOTE:
PLANT SEED MIX ON SLOPE FACE BENEATH COIR EROSION CONTROL BLANKET
- NOTE:
MATCH SLOPE TO PROPOSED CROSS SECTION
- NOTE:
LIVE BRUSH LAYERING (PLACED ON 5% SLOPE AWAY FROM CREEK). REFER TO ZONE 1 PLANTING TABLE FOR SPECIES.
- NOTE:
WOVEN COIR EROSION CONTROL BLANKET (OUTSIDE)
- NOTE:
CONTINUOUS WEAVE EROSION CONTROL BLANKET (INSIDE)
- NOTE:
SEE PLAN VIEW SHEETS FOR REQUIRED TREATMENT
• NATIVE ROCK RIFLE - SEE CONSTRUCTION SPECIFICATIONS
• BOULDER TOE WITH ROOT WADS - DETAIL 1/C-111
- NOTE:
APPROX. INNER BERM/BASEFLOW ELEV.
- NOTE:
SLOPE VARIES (3H:1V MAX.)
- NOTE:
BANKFULL ELEVATION
- NOTE:
6'-1" (TYP.)
- NOTE:
2'-3" (MIN.)
- NOTE:
6'-1" (TYP.)
- NOTE:
6'-1" (TYP.)
- NOTE:
5%
- NOTES:
- CONSTRUCT REQUIRED TOE TREATMENTS PER CORRESPONDING DETAIL.
 - SOIL BACKFILL USED FOR LIFTS AND TOPSOIL USED FOR LAYERING WITH THE LIVE BRUSH SHALL BE FREE OF ANY LARGE ROOTS OR WOODY DEBRIS AND COBBLE MATERIAL.
 - BACKFILL ON TOP OF ROCK/GEOTEXTILE WITH SOIL TO CREATE A PLANTING SURFACE SLOPE APPROXIMATELY 5% AWAY FROM CREEK. WIDTH OF PLANTING SURFACE SHOULD BE A MINIMUM OF 2 FEET. PLACE TOPSOIL ON PLANTING SURFACE AND PLACE LIVE BRUSH SUCH THAT 2/3 OF THE BRUSH WILL BE COVERED WITH SOIL AND 1/3 OF THE BRUSH IS EXPOSED, EXTENDING BEYOND THE FACE OF THE BANK. PLACE A MINIMUM OF 8 TO 12 STEMS PER RUNNING FOOT OF BANK IN A SLIGHT CRISS-CROSS PATTERN. BACKFILL ABOVE LIVE BRUSH WITH A 4 INCH LAYER OF TOPSOIL.
 - PLACE A LAYER OF 6.5 FT WIDE (MIN.) GEOCOIR DEKOWE 700 WOVEN EROSION CONTROL BLANKET, OR APPROVED EQUIVALENT, ON TOP OF THE TOPSOIL AND LIVE BRANCHES SUCH THAT A MINIMUM OF 2 FEET OF THE BLANKET WILL BE BURIED BELOW THE NEXT SOIL LIFT. ALLOW THE EXCESS BLANKET TO LAY OVER THE BANK, TOWARD THE CHANNEL.
 - PLACE A LAYER OF 3.3 FT WIDE (MIN.) C-125BN CONTINUOUS WEAVE EROSION CONTROL BLANKET, OR APPROVED EQUIVALENT, OVER THE WOVEN EROSION CONTROL BLANKET SUCH THAT IT COVERS THE ENTIRE FACE OF THE LIFT BENEATH THE WOVEN EROSION CONTROL BLANKET. ALLOW EXCESS BLANKET TO LAY OVER THE BANK, ON TOP OF THE WOVEN EROSION CONTROL BLANKET.
 - PLACE SOIL BACKFILL UP TO THE LIFT HEIGHT SPECIFIED OF NO GREATER THAN 1.0 FOOT BEING CAREFUL NOT TO PUSH/PULL OR TEAR THE BLANKET PREVIOUSLY PLACED.
 - THE TOP OF THE SOIL BACKFILL SHALL BE FLAT WITHIN THE LIFT SETBACK DISTANCE SPECIFIED. BEYOND THE LIFT SETBACK DISTANCE, THE SOIL BACKFILL SHALL BE SLOPED AT AN APPROXIMATE 5% SLOPE AWAY FROM THE STREAM.
 - FOR THE TOP COURSE, TOP DRESS THE SOIL LIFT WITH TOPSOIL FROM THE FACE OF THE SOIL LIFT BACK INTO THE FLOODPLAIN AT LEAST 4FT.
 - SPRINKLE SEED MIX ON SOIL AT THE SEEDING RATE SHOWN IN PLANTING PLAN WHERE IT WILL BE EXPOSED AND APPLY STRAW MULCH.
 - WRAP THE FACE AND TOP OF THE SOIL LIFT USING THE WOVEN AND CONTINUOUS WEAVE EROSION CONTROL BLANKET HANGING OVER THE PREVIOUS LIFT OR BOULDER TOE.
 - THE EROSION CONTROL BLANKET SHALL BE PULLED AS TIGHT AS POSSIBLE WITHOUT TEARING OR EXCESSIVELY DISTORTING THE BLANKET.
 - SECURE THE WOVEN EROSION CONTROL AND CONTINUOUS WEAVE EROSION CONTROL BLANKET IN PLACE BY STAKING THE END OF THE EROSION CONTROL BLANKET WITH WOOD STAKES ON 3-FOOT CENTERS. SEE WOOD STAKE DETAIL FOR SPECIFICATIONS.
 - BEGIN CONSTRUCTION OF THE NEXT SOIL LIFT BY REPEATING THE PREVIOUS NOTES STARTING WITH NOTE 3.
 - THE OVERALL SLOPE CREATED BY THE LIVE BRUSH LAYERING SHALL MATCH THE PROPOSED CROSS SECTION SHAPE FOR THE OUTER BANK OF THE TYPICAL POOL CROSS-SECTION.
 - THE EROSION CONTROL BLANKETS USED FOR THE UPPER MOST SOIL LIFT WILL BE SECURED BY STAKING THE END OF THE BLANKET APPROXIMATELY 4 INCHES BELOW FINISH GRADE ELEVATION AS SHOWN IN THE DETAIL AND BACKFILLING OVER THE END OF THE BLANKET AND STAKE DURING FINISH GRADING OPERATIONS.
 - THE SURFACE OF THIS STRUCTURE SHALL BE FINISHED TO A SMOOTH AND COMPACT SURFACE IN ACCORDANCE WITH THE LINES, GRADES, AND CROSS-SECTIONS OR ELEVATIONS SHOWN ON THE DRAWINGS. THE DEGREE OF FINISH FOR ELEVATIONS SHALL BE WITHIN 0.1 FT OF THE GRADES AND ELEVATIONS INDICATED.
 - LIVE BRUSH IS TYPICALLY INSTALLED WHEN THEY ARE DORMANT, WHICH TYPICALLY OCCURS BETWEEN NOVEMBER 1 AND MARCH 31. HOWEVER, FOR THIS PROJECT ALL LIVE BRUSH SHALL BE INSTALLED DURING CONSTRUCTION WITH THE ANTICIPATION OF A HIGH MORTALITY RATE.
 - THE CLIENT ANTICIPATES RE-INSTALLING LIVE BRUSH DURING DORMANCY.

2
C-112
LIVE BRUSH LAYERING
NOT TO SCALE



- NOTES:
- WOOD STAKES SHALL BE OF MINIMUM DIMENSIONS SHOWN AND SHALL BE GENERALLY FREE OF ANY KNOTS.
 - ALL WOOD STAKES SHALL BE RELATIVELY STRAIGHT AND WITHOUT ANY ROT OR WATER DAMAGE.
 - ONE 3-INCH NAIL SHALL BE DRIVEN THROUGH A PRE-DRILLED HOLE 1" TO 2" BELOW THE TOP OF THE WOOD STAKE.
 - THE PRE-DRILLED HOLE SHALL BE SMALL ENOUGH THAT THE NAIL MUST BE DRIVEN INTO THE STAKE, YET LARGE ENOUGH TO PREVENT SPLITTING OF THE STAKE WHILE DRIVING THE NAIL.
 - THE NAIL SHALL BE DRIVEN SUCH THAT AN EQUAL AMOUNT OF THE NAIL PROTRUDES THROUGH BOTH SIDES OF THE WOOD STAKE.
 - IN LIEU OF PRE-DRILLING HOLES THROUGH THE WOOD STAKES, A PNEUMATIC NAIL-GUN MAY BE USED; HOWEVER, THE AIR PRESSURE MUST BE ADJUSTED SUCH THAT NO SPLITTING OF THE WOOD STAKE OCCURS.

3
C-112
TYPICAL WOOD STAKE
NTS



10359 Timberwood Circle, Suite 100
Louisville, Kentucky 40223-5301
www.stantec.com

The Designer, Engineer, Architect, or other professional responsible for all drawings, documents, and specifications shall be responsible for the accuracy of the drawings, documents, and specifications. The Designer, Engineer, Architect, or other professional shall be responsible for the accuracy of the drawings, documents, and specifications. The Designer, Engineer, Architect, or other professional shall be responsible for the accuracy of the drawings, documents, and specifications.

OFFICE OF ADMINISTRATION
DIVISION OF FACILITIES
MANAGEMENT,
DESIGN AND CONSTRUCTION
DEPARTMENT OF
NATURAL RESOURCES

CASTLEWOOD STATE PARK
STREAMBANK RESTORATION
PHASE I

BALLWIN, MO

PROJECT # X2002-01
SITE # 5205
ASSET # 7815205028


REVISION: _____
DATE: _____
REVISION: _____
DATE: _____
REVISION: _____
DATE: _____
ISSUE DATE: 03/24/2020

CAD DWG FILE: C-113.dwg
DRAWN BY: DLH
CHECKED BY: OKR
DESIGNED BY: MAS

SHEET TITLE:
DETAILS


SHEET NUMBER:
C-113

15 OF 16 SHEETS
03/24/2020




- NOTES:**
- ROCK SILT SCREENS WILL BE INSTALLED, IF NEEDED, AT ACTIVE CHANNEL WORK AREAS.
 - EXCAVATE ENOUGH CHANNEL MATERIAL FROM WORK AREA TO CONSTRUCT ROCK SILT SCREEN AS SHOWN TO SEPARATE MAIN CHANNEL FLOW FROM WORK AREA.
 - THE DOWNSTREAM END OF THE ROCK SILT SCREEN SHALL BE CONSTRUCTED WITH A LOW POINT SUCH THAT THE PONDED WATER IS ABLE TO FLOW OVER THE LOW POINT, BUT NOT ABLE TO FLOW OVER ANY OTHER LOCATION OF THE ROCK SILT SCREEN DURING BASEFLOW CONDITIONS.
 - EXCAVATE CHANNEL MATERIAL FROM WORK AREA WHERE BOULDER TOE WILL BE CONSTRUCTED.
 - ONCE THE TOE STABILIZATION TREATMENT HAS BEEN COMPLETED, THE ROCK SILT SCREEN SHALL BE LEFT IN PLACE UNTIL THE OBSERVED TURBIDITY OF THE PONDED WATER IN THE WORK AREA RETURNS TO THE NORMAL LEVEL.
 - REMOVE THE SILT SCREEN BY USING THE ROCK MATERIAL AS BACKFILL FOR THE REMAINING BANK STABILIZATION WORK.

1
C-113
ROCK SILT SCREEN
NTS




- NOTES:**
- ALL THE DIMENSIONS IN THE DRAWING ARE RECOMMENDED MINIMUMS.
 - THE CONTRACTOR SHALL INSTALL TWO SEPARATE LAYERS OF ROCK SEPARATED BY GEOTEXTILE FABRIC. THE TOP LAYER SHALL CONSIST OF 8 INCHES OF MACHINED STONE (MODOT TYPE 1 ROCK DITCH LINER) AND THE BOTTOM LAYER SHALL BE 6 INCHES OF MODOT TYPE 7 AGGREGATE FOR BASE.
 - THE ENTRANCE SHOULD BE A MINIMUM OF 100 FEET IN LENGTH AND 22 FEET IN WIDTH.
 - THE CONTRACTOR SHALL MAKE EVERY EFFORT TO MINIMIZE THE AMOUNT OF SOIL AND MUD LEAVING THE CONSTRUCTION SITE. STONE IN THE ENTRANCE SHOULD BE ADDED OR CLEANED WHENEVER THE ENTRANCE FAILS TO PREVENT MUD TRACKING ON THE PUBLIC ROADWAY.
 - THE CONTRACTOR SHALL RESTORE GROUND BACK TO ORIGINAL CONDITION POST CONSTRUCTION.
 - PIPING SHALL BE OF SUFFICIENT DIAMETER AND SLOPE TO PASS ROADSIDE DITCH FLOWS.

2
C-113
TEMPORARY CONSTRUCTION ENTRANCE
NOT TO SCALE




- NOTES:**
- SILT FENCE SHALL BE INSTALLED ACROSS SLOPES ON THE CONTOUR LINE.
 - ATTACH FILTER FABRIC TO POSTS WITH STAPLES, HOGRINGS OR OTHER MATERIALS APPROVED BY THE ENGINEER.
 - POSTS SHALL BE WOOD, STEEL, OR SYNTHETIC.
 - POSTS SHALL BE INSTALLED ON THE DOWNHILL SIDE OF FILTER FABRIC.
 - BURY THE BOTTOM 12 INCHES OF FILTER FABRIC IN A 6\"/>

3
C-113
SILT FENCE
NOT TO SCALE




- NOTES:**
- LIVE STAKES SHALL BE INSTALLED AS SPECIFIED IN THE PLANTING PLAN.
 - LIVE STAKES SHALL BE CUT FROM AN APPROVED SOURCE WITH A SHARP TOOL. STAKES SHALL BE FREE FROM DISEASE OR EXCESS DEAD TWIGS. 2 TO 2.5 FEET IN LENGTH WITH A BASAL END 0.5 TO 1.5 INCH IN DIAMETER. PRIOR TO INSTALLATION BASAL END SHALL BE CUT AT A 45 DEGREE ANGLE AND THE OPPOSITE END SHALL BE CUT FLAT WITHOUT CRACKS.
 - LIVE STAKES SHALL BE INSTALLED BY GENTLY TAMPING INTO THE SOIL LEAVING 8 TO 10 INCHES EXPOSED (I.E. 8 INCHES FOR 2 FEET LONG STAKES).
 - STAKES SHALL BE PLACED IN A RANDOM PATTERN AT A RATE OF 1 LIVE STAKE PER 3 LINEAR FEET PER LIFT.
 - LIVE STAKES ARE TYPICALLY INSTALLED WHEN THEY ARE DORMANT, WHICH TYPICALLY OCCURS BETWEEN NOVEMBER 1 AND MARCH 31. HOWEVER, FOR THIS PROJECT ALL LIVE STAKES SHALL BE INSTALLED DURING CONSTRUCTION WITH THE ANTICIPATION OF A HIGH MORTALITY RATE.
 - THE CLIENT ANTICIPATES RE-INSTALLING LIVE STAKES DURING DORMANCY.

4
C-113
DORMANT LIVE STAKE
NTS



- NOTES:**
- PLANTING HOLES SHALL BE EXCAVATED BY HAND USING A DIBBLE BAR, MATTOCK, PICK, OR IRON BAR.
 - PLANTING HOLES SHALL BE EXCAVATED DEEP ENOUGH TO ACCOMMODATE THE ENTIRETY OF THE TAP ROOT VERTICALLY WITHOUT \"J-ROOTING\" THE PLANT, AND TO ALLOW THE FIRST LATERAL ROOT OF THE ROOT MASS TO BE FLUSH WITH THE EXISTING GRADE.
 - ROOTS PROTRUDING ABOVE THE SOIL SURFACE WILL BE REJECTED.
 - ENSURE THAT PLANT REMAINS STRAIGHT WHILE PLACING BACKFILL, BEING CAREFUL TO AVOID BREAKING ROOTS.
 - PRUNE IN ACCORDANCE WITH THE CONSTRUCTION SPECIFICATIONS.

5
C-113
BARE-ROOT PLANTING
NOT TO SCALE



- NOTES:**
- PRUNE AS DIRECTED BY PRODUCER.
 - STAKING SCHEDULE:
 - 1.5\"/>
 - 2 STAKES

6
C-113
TREE STAKING AND PLANTING
NOT TO SCALE



3/24/2020



10509 Timberwood Circle, Suite 100
Louisville, Kentucky 40223-5301
www.stantec.com

The contractor shall be responsible for all design, engineering, and construction work. The contractor shall be responsible for all design, engineering, and construction work. The contractor shall be responsible for all design, engineering, and construction work.

OFFICE OF ADMINISTRATION
DIVISION OF FACILITIES
MANAGEMENT,
DESIGN AND CONSTRUCTION

DEPARTMENT OF
NATURAL RESOURCES

CASTLEWOOD STATE PARK
STREAMBANK RESTORATION
PHASE I

BALLWIN, MO

PROJECT # X2002-01
SITE # 5205
ASSET # 7815205028

REVISION: _____
DATE: _____
REVISION: _____
DATE: _____
REVISION: _____
DATE: _____
ISSUE DATE: 03/24/2020


CAD DWG FILE: C-114.dwg
DRAWN BY: DJH
CHECKED BY: OKR
DESIGNED BY: MAS

SHEET TITLE:
EROSION PROTECTION
AND SEDIMENT
CONTROL PLAN

SHEET NUMBER:

C-114

16 OF 16 SHEETS
03/24/2020



EPSC PLAN

EROSION AND SEDIMENT CONTROL NOTES:

ANY LAND CLEARING, CONSTRUCTION, OR DEVELOPMENT INVOLVING THE MOVEMENT OF EARTH SHALL BE IN ACCORDANCE WITH THE SWPPP, AND THE APPLICANT SHALL ASSUME AND ACKNOWLEDGE RESPONSIBILITY FOR COMPLIANCE WITH THE CODE AND THE APPROVED SWPPP AT THE SITE OF THE PERMITTED ACTIVITY.

ALL AREAS NOT WITHIN THE LIMITS OF DISTURBANCE WITH EXISTING VEGETATION WILL BE PRESERVED TO PROVIDE NATURAL BUFFERING.

THE TIME PERIOD FOR DISTURBED AREAS TO BE WITHOUT VEGETATIVE COVER IS TO BE MINIMIZED TO THE MAXIMUM EXTENT PRACTICABLE AND SHALL BE IN ACCORDANCE WITH THE SWPPP.

PERIPHERAL OR BORDER BMPs TO CONTROL RUNOFF FROM DISTURBED AREAS SHALL BE INSTALLED OR MARKED FOR PRESERVATION BEFORE GENERAL SITE CLEARING IS STARTED.

NATURAL CONTOURS WILL BE UTILIZED TO DIRECT STORM WATER RUNOFF TO VEGETATED AREAS SUCH THAT CONCENTRATED FLOW IS CONVERTED TO SHEET FLOW BEFORE ENTERING THE CHANNEL.

ALL STREAM BANKS ABOVE BANKFULL ELEVATION WILL BE GRADED AT A 3:1 OR FLATTER SLOPE AND STABILIZED WITH SEED, STRAW AND EROSION CONTROL BLANKET.

THE CHANGE IN THE RUNOFF COEFFICIENT FOR THE SITE FROM PRE-CONSTRUCTION TO POST-CONSTRUCTION WILL BE NEGLIGIBLE DUE TO RE-VEGETATION OF DISTURBED AREAS.

ALL EROSION CONTROL MEASURES SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE SWPPP AND ALL LOCAL, STATE, AND FEDERAL REGULATIONS.

EROSION AND SEDIMENT CONTROL MEASURES SHALL BE MAINTAINED CONTINUOUSLY, RELOCATED AS NECESSARY, AND SHALL BE INSPECTED IN ACCORDANCE WITH THE SWPPP AND CONSTRUCTION SPECIFICATIONS. SEEDING AREAS SHALL BE CHECKED REGULARLY AND SHALL BE WATERED, RE-SEEDING, AND MULCHED AS NECESSARY TO OBTAIN A DENSE STAND OF GRASS.

STABILIZATION IS THE BEST FORM OF EROSION CONTROL. ALL DISTURBED AREAS THAT ARE NOT OTHERWISE STABILIZED SHALL BE AMENDED AND SEEDING, TEMPORARILY OR PERMANENTLY IN ACCORDANCE WITH THE SWPPP AND CONSTRUCTION SPECIFICATIONS.

ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN 14 DAYS AFTER FINAL SITE STABILIZATION OR AFTER THE TEMPORARY MEASURES ARE NO LONGER NEEDED. TRAPPED SEDIMENT AND THE DISTURBED SOIL AREAS RESULTING FROM THE DEPOSITION OF TEMPORARY MEASURES SHALL BE PERMANENTLY STABILIZED TO PREVENT FURTHER EROSION AND SEDIMENTATION.

WHERE SEDIMENT IS TRANSPORTED ONTO A PAVED OR PUBLIC ROAD SURFACE, THE ROAD SURFACE SHALL BE CLEANED THOROUGHLY AT THE END OF EACH DAY. SEDIMENT SHALL BE REMOVED FROM THE ROADS BY SHOVELING OR SWEEPING AND TRANSPORTED TO A SEDIMENT CONTROL DISPOSAL AREA. STREET WASHING SHALL BE ALLOWED ONLY AFTER SEDIMENT IS REMOVED IN THIS MANNER, AND WHEN THE WATER CAN BE DISCHARGED TO A SEDIMENT TRAP OR BASIN.

SITE PRESERVATION AGREEMENT:

THE CONTRACTOR SHALL BE RESPONSIBLE FOR REPAIRING ANY DAMAGE TO EXISTING PATHS, ROADS, GATES, FENCES, ETC. CONSTRUCTION ENTRANCES SHALL BE INSTALLED/MAINTAINED AT ALL ACCESS LOCATIONS PER THE PLANS AND SPECIFICATIONS.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY IMPROVEMENT TO THE ROAD/PATH CONDITION, GATES, AND FENCES, REQUIRED FOR ACCESS DURING CONSTRUCTION.

EROSION CONTROL MEASURES DURING CONSTRUCTION:

DURING CONSTRUCTION THE CONTRACTOR SHALL BE RESPONSIBLE FOR INSTALLING ADDITIONAL EROSION CONTROL MEASURES NOT SHOWN ON THE PLANS BUT NECESSARY TO CONTROL ERODING SEDIMENT, IF DETERMINED BY THE ENGINEER OR MISSOURI DEPARTMENT OF NATURAL RESOURCES PERSONNEL.

STAGING AND STOCKPILE AREAS:

SPECIFIED AREAS SHOWN ON THE PLANS HAVE BEEN ESTABLISHED AS STAGING AREAS AND STOCKPILING AREAS. THE CONTRACTOR MAY ESTABLISH ADDITIONAL STAGING AND STOCKPILING AREAS ALONG THE PROJECT, AS NECESSARY, TO CARRY OUT THE WORK. ALL STAGING AND STOCKPILING AREAS MUST BE APPROVED BY THE ENGINEER. SILT FENCE SHALL BE REQUIRED IN AREAS WHERE LOOSE SOIL HAS BEEN PLACED IN THE STAGING AND STOCKPILING AREAS.

SPECIAL NOTES:

ACTIVITIES ASSOCIATED WITH CONSTRUCTION OF THE NEW CHANNEL BED, BANKS, IN-STREAM STRUCTURES, AND STABILIZATION MEASURES REQUIRE THAT CONSTRUCTION OCCUR IN THE ACTIVE CHANNEL (FLOWING WATER). EXCESS CHANNEL MATERIAL SHALL BE PLACED AROUND THE IN-STREAM WORK AREA TO DIVERT FLOW AND REDUCE SEDIMENT INTRODUCTION TO THE STREAM. MATERIAL USED FOR THIS PURPOSE WILL BE REPLACED AFTER COMPLETION OF WORK IN THE RESPECTIVE AREA. CONTRACTOR WILL LIMIT WORK IN CHANNEL TO ONLY WHAT IS NECESSARY TO COMPLETE THE PROJECT.

ALL REFUELING AND EQUIPMENT MAINTENANCE ACTIVITIES MUST OCCUR OUTSIDE OF THE ACTIVE CHANNEL.

CONTRACTOR MUST KEEP ON SITE AN EMERGENCY SPILL KIT CAPABLE OF RESPONDING TO A POTENTIAL SPILL ASSOCIATED WITH THE SIZE EQUIPMENT BEING USED ON SITE. SPILL PREVENTION SHALL BE IN ACCORDANCE WITH THE SWPPP.

ALL EQUIPMENT MUST BE REMOVED FROM THE ACTIVE CHANNEL AND GRAVEL BAR AT THE END OF EACH WORKING DAY.

MISCELLANEOUS:

CONTRACTOR SHALL BE RESPONSIBLE FOR HAVING A RAIN GAUGE ON THE PROJECT SITE AND FOR RECORDING DAILY RAINFALL AMOUNT DURING CONSTRUCTION.

THE HOLDER OF A MAJOR LAND DISTURBANCE PERMIT, OR HIS / HER AGENT, SHALL PERFORM REGULAR AND AFTER-RAIN INSPECTIONS OF LAND DISTURBANCE SITES BY A QUALIFIED SPECIAL INSPECTOR APPROVED BY THE COUNTY. ALL INSPECTIONS SHALL BE DOCUMENTED AND SUBMITTED IN ACCORDANCE WITH THE SWPPP.

CONSTRUCTION SEQUENCE:

THE CONTRACTOR IS RESPONSIBLE FOR FOLLOWING THE SEQUENCE OF CONSTRUCTION IN ACCORDANCE WITH THE PLANS AND THE FOLLOWING PROVISIONS, AND AS DIRECTED BY THE ENGINEER. DEVIATIONS FROM THE SEQUENCE DESCRIBED BELOW MAY BE ALLOWED WITH APPROVAL BY THE ENGINEER.

GENERAL SITE NOTE:

THE CONTRACTOR SHALL CONDUCT WORK SUCH THAT A MAXIMUM OF 500 LINEAR FEET OF CHANNEL IS OPENED UP AT ANY TIME (I.E. IN A STATE OF ACTIVE CONSTRUCTION). SOIL STOCKPILE AREAS WILL ONLY BE PLACED OUTSIDE THE ACTIVE CHANNEL AND SHALL HAVE SILT FENCE INSTALLED AROUND THE PERIMETER.

PHASE 1: INITIAL SITE PREPARATION

1. IDENTIFY PROJECT BOUNDARY, LIMITS OF DISTURBANCE, SENSITIVE AREAS, STAGING AREAS, STABILIZED ENTRANCES, HAUL ROUTES, AND ACCESS POINTS WITH THE ENGINEER.
2. INSTALL EROSION CONTROL MEASURES IN ACCORDANCE WITH THE EROSION AND SEDIMENT CONTROL PLANS, CONSTRUCTION SPECIFICATIONS, SWPPP, AND AS DIRECTED BY THE ENGINEER.
3. CONSTRUCT STAGING AREAS IN A MANNER TO SUPPORT EXECUTION OF THE WORK ON EACH REACH AS INDICATED IN THE PLANS AND AS DIRECTED BY THE ENGINEER.

PHASE 2: BANK STABILIZATION MEASURES

1. EXCAVATE PROPOSED CHANNEL AND/OR BANKS. INSTALL HABITAT AND BANK STABILIZATION FEATURES AS REQUIRED, GRADE FLOODPLAIN, AND COVER WITH STRAW, SEED MIX, AND EROSION CONTROL BLANKET.

PHASE 3: PROJECT COMPLETE/DEMOLITION

1. UPON PROJECT APPROVAL, REMOVE EROSION AND SEDIMENT CONTROL MEASURES, PROVIDE FINAL STABILIZATION AND ADD ADDITIONAL SEED AS NECESSARY.

DISTURBED AREA SOIL TYPES		
SOIL TYPE	AREA	COMPOSITION
	ACRES	%
Freeburg silt loam, 2 to 5 percent slopes, occasionally flooded	0.100	2.0
Haymond silt loam, 0 to 3 percent slopes, frequently flooded	3.000	61.2
Wilbur silt loam, 0 to 2 percent slopes, frequently flooded	0.600	12.2
Horsecreek silt loam, 2 to 5 percent slopes, occasionally flooded	1.200	24.5
*SOIL DATA PER USDA NRCS WEB SOIL SURVEY		

PLAN LEGEND	
--- 100 ---	EXISTING INDEX CONTOURS
- - - - -	EXISTING INTERIM CONTOURS
•••••	LIMITS OF DISTURBANCE
— SF — SF	SILT FENCE
[Hatched Box]	STAGING AREAS